

September 11, 2020  
Sacramento, California

In Compliance with CA Executive Orders N-25-20 and N-29-20 the Board of Trustees of the American River Flood Control District met in regular session at 11:00 a.m. on Friday, September 11, 2020 by teleconference. In attendance were Trustee Shah, Trustee Johns Trustee Holloway, Trustee L'Ecluse and Trustee Vander Werf. Trustee Shah presided. Also present from the District were General Manager (GM) Tim Kerr, Field Supervisor Scott Webb, Legal Counsel Rebecca Smith and Office Manager Malane Chapman. Three members of the public were present.

The meeting was called to order at 11:00 a.m. Roll call was taken and a quorum was present.

*Item No. 1 Public Comments on Non-Agenda Items:* No public comment on non-agenda items.

*Item No. 2 Approval of Consent Agenda Items:* On a motion by Trustee Johns seconded by Trustee Vander Weft, the Board unanimously approved items 2a) Minutes of Regular Meeting on August 14, 2020, 2b) Approval of Report of Investment Transactions July 2020 (City Pool, LAIF, River City) and Treasurer's Certification and 2c) District Financial Reports: Statement of Operations (August 2020) and Cash Flow Report

Roll Call Vote:

Trustee Shah:	AYE	Trustee Vander Werf:	AYE
Trustee L'Ecluse:	AYE	Trustee Johns:	AYE
Trustee Holloway:	AYE		

*Item No. 2d Correspondence: MBK Engineers, Ric Reinhardt and City of Sacramento Police Department, Lieutenant Brian Ellis:* Trustee Vander Werf inquired about the Districts response, if any, to the Sacramento Police Department. Following explanation by staff and discussion with the Board it was determined that no response was needed. Item 2d was purely for informational purposes. On a motion by Trustee Vander Werf seconded by Trustee Johns, the Board unanimously accepted the correspondence as presented without need for response.

Roll Call Vote:

Trustee Shah:	AYE	Trustee Vander Werf:	AYE
Trustee L'Ecluse:	AYE	Trustee Johns:	AYE
Trustee Holloway:	AYE		

*Item No. 3 Accounts Payable and General Fund Expenses (August 2020):* Trustee Vander Werf asked for clarification on payment made to Kent Arborist Services. Trustee Shah asked for clarification on payment made to SCI Consulting Group. Following explanation by staff and on a motion by Trustee Holloway seconded by Trustee L'Ecluse, the Board unanimously approved payments on the Schedule of Accounts Payable (August 2020) of \$146,022.77 and General Fund Expenses of \$92,325.91 (total aggregate sum \$238,348.68).

## Roll Call Vote:

Trustee Shah:	AYE	Trustee L'Ecluse:	AYE
Trustee Johns:	AYE	Trustee Vander Werf:	AYE
Trustee Holloway:	AYE		

*Item No. 4 Administrative Staff Reports:*a) *General Manager Tim Kerr reported on the following:*

- General Manager's August Meeting Summary: ARFCD Fire Extinguisher Training was discussed. Trustee L'Ecluse requested a count of fires within the last six months;
- District Carbon Footprint: Trustee Vander Werf feels that it is a good idea for the District to learn about its carbon footprint, Trustee Johns recommended that the District meet with SMUD regarding fleet electric cars;
- Board Encroachment Remediation Discussion: Board suggested sending letters to homeowners stating encroachments are creating a public safety issue;
- MA9 – City of Sacramento – AR South SWIF Update: Successful submitting the update removed about one half of the items from previous inspections;
- District Roof Repair/Replacement Update: Work started September 8 and currently part of the interior space doesn't have AC;
- Hydrologic Conditions: Folsom Lake 47% of capacity with an outflow 2,479 cfs. The gauge at the I Street Bridge shows a water surface elevation of 6.5 feet above sea level;
- Next Board Meeting is scheduled for October 16, 2020.

b) *Legal Counsel Rebecca Smith had nothing further to report.*c) *Office Manager Malane Chapman thanked the Board again for moving the October 9, 2020 Board Meeting to October 16, 2020.**Item No. 5 Operations and Maintenance Staff Reports:*a) *Superintendent Ross Kawamura, presented by Field Supervisor Scott Webb:*

- Crew activities including slope repair, camp cuts, trash removal, vegetation removal, tree removal, created walking paths, mowing and practiced new grading techniques.

*Item No. 6 Questions and Comments by Trustees:* Trustee L'Ecluse asked how the District was doing in regard to disinfecting and PPEs. Field Supervisor Webb express his gratitude to Trustee L'Ecluse on providing the District with hand sanitizer during times when it was difficult to purchase through vendors.

*Item No. 7 Adjourn:* There being no further business requiring action by the Board, the meeting was adjourned by Trustee Shah at 11:55 a.m.

Attest:

\_\_\_\_\_  
Secretary\_\_\_\_\_  
President

**American River Flood Control District  
Staff Report**

**Investment Transactions Summary; August 2020**

**LAIF:**

- There were no transactions in this account during the month of August.

**City Pool A**

- Accrued Interest Receivable for the month of August was \$10,836.29.
- As of August 31, 2020, the balance of Interest Receivable in this account was \$22,530.34.

Interest Receivable is accrued and transferred to the Cash Balance at the discretion of the City.

---

**River City Bank Money Market:**

- On August 26, 2020 a transfer was sent to River City Checking in the amount of \$235,765.00.
- On August 31, 2020 a monthly interest payment was deposited in the amount of \$599.51.

**River City Bank Checking:**

- On August 7, 2020 a deposit was received from Sacramento County Tax Collector in the amount of \$30,998.97.
- On August 20, 2020 a miscellaneous deposit was received in the amount of \$51.83.
- On August 26, 2020 a transfer was received from River City Money Market in the amount of \$235,765.00.
- On August 31, 2020 a monthly interest payment was deposited in the amount of \$17.18.
- Total amount of Accounts Payable cleared during the month of August was \$265,867.45.

**American River  
Flood Control  
District**

**AMERICAN RIVER FLOOD CONTROL DISTRICT**

**MONTHLY REVIEW – AUGUST 2020**


**STRATEGY**

The ARFCD funds are invested in the City of Sacramento’s Pool A investment fund. The Fund is invested pursuant to the objectives and requirements set forth in the City’s investment policy. The three objectives of the investment policy, in order of priority, are (1) the preservation of capital by the investment in safe instruments, (2) the liquidity needs of the City and pool participants so such parties will have access to cash when they need it, and (3) the maximizing of current income while remaining consistent with the other more important objectives. The City’s investment policy incorporates applicable provisions of state law including, among other things, the prudent person standard and California Code Section 53601 pertaining to eligible investments.

**PORTFOLIO STATISTICS**

Beginning Balance	8,835,211
Contributions	-
Withdrawals	-
Interest Earned	10,836
Ending Balance	8,846,047

**CITY POOL A PORTFOLIO COMPOSITION**




**PERFORMANCE COMPARISON**

City Pool A	1.44%
LAIF	0.78%
90 Day T-Bill	0.09%
Federal Funds	0.10%

Asset Type	Pct. Assets	YTM
Corp Bonds	32.76%	2.16%
CalTRUST	19.36%	0.71%
Treasuries/Agencies	15.13%	1.12%
CPs	7.74%	1.45%
Muni Bonds	6.59%	2.17%
Bank Deposits	6.42%	0.92%
LAIF	5.53%	0.78%
CDs	4.61%	1.26%
Supranationals	1.86%	2.08%

**CITY POOL A MATURITY SCHEDULE**

Maturity	Market Value	Pct. Holdings
< 1 Year	792,169,039	58.25%
1 - 2 Years	130,654,839	9.60%
2 - 3 Years	99,365,242	7.30%
3 - 4 Years	32,678,033	2.40%
4 - 5 Years	295,530,491	21.72%
5 Yrs+30 Dys	9,995,864	0.73%
Total	1,360,393,508	100.00%



City of Sacramento  
CASH LEDGER  
*American River Flood Control District*  
From 08-01-20 To 08-31-20

**All Cash Accounts**

Trade Date	Settle Date	Tran Code	Quantity	Security	Amount	Cash Balance
<b>Pool A Interest Receivable</b>						
08-01-20				Beginning Balance		11,694.05
08-31-20	08-31-20	in		Pool A Cash	10,836.29	22,530.34
				Aug 2020 estimated Pool A interest		
					10,836.29	
<b>08-31-20</b>				<b>Ending Balance</b>		<b>22,530.34</b>
<b>Pool A Cash</b>						
08-01-20				Beginning Balance		8,823,516.56
<b>08-31-20</b>				<b>Ending Balance</b>		<b>8,823,516.56</b>

# California State Treasurer *Fiona Ma, CPA*



Local Agency Investment Fund  
P.O. Box 942809  
Sacramento, CA 94209-0001  
(916) 653-3001

September 01, 2020

[LAIF Home](#)  
[PMIA Average Monthly Yields](#)

AMERICAN RIVER FLOOD CONTROL DISTRICT

DISTRICT ENGINEER/MANAGER  
165 COMMERCE CIRCLE, SUITE D  
SACRAMENTO, CA 95815

[Tran Type Definitions](#)

**Account Number:** 90-34-002

August 2020 Statement

**Account Summary**

Total Deposit:	0.00	Beginning Balance:	465,223.75
Total Withdrawal:	0.00	Ending Balance:	465,223.75



# River City Bank

WWW.RIVERCITYBANK.COM

PO Box 15247, Sacramento, CA 95851-0247

Return Service Requested

Item 2b



Last statement: July 31, 2020  
This statement: August 31, 2020  
Total days in statement period: 31

AMERICAN RIVER FLOOD CONTROL DISTRICT  
C/O ROBERT MERRITT, CPA  
4000 MAGNOLIA HILLS DR  
EL DORADO HILLS CA 95762-6561

Page 1  
0811100952  
( 0)

Direct inquiries to:  
916-567-2836

## Public Fund Money Market

Account number	0811100952	Beginning balance	\$1,235,765.26
Low balance	\$1,000,000.26	Total additions	599.51
Average balance	\$1,190,133.32	Total subtractions	235,765.00
Avg collected balance	\$1,190,133	Ending balance	\$1,000,599.77
Interest paid year to date	\$3,661.21		

### DEBITS

Date	Description	Subtractions
08-26	Cash Mgmt Trsfr Dr REF 2391401L FUNDS TRANSFER TO DEP XXXXX0736 FROM	235,765.00

### CREDITS

Date	Description	Additions
08-31	Interest Credit	599.51

### DAILY BALANCES

Date	Amount	Date	Amount	Date	Amount
07-31	1,235,765.26	08-26	1,000,000.26	08-31	1,000,599.77

### INTEREST INFORMATION

Annual percentage yield earned	0.60%
Interest-bearing days	31
Average balance for APY	\$1,190,133.32
Interest earned	\$599.51



AMERICAN RIVER FLOOD CONTROL DISTRICT  
August 31, 2020

Page 2  
0811100952

**OVERDRAFT/RETURN ITEM FEES**

	Total for this period	Total year-to-date
Total Overdraft Fees	\$0.00	\$0.00
Total Returned Item Fees	\$0.00	\$0.00



**River City Bank**

WWW.RIVERCITYBANK.COM

PO Box 15247, Sacramento, CA 95851-0247

Return Service Requested

Item 2b



Last statement: July 31, 2020  
This statement: August 31, 2020  
Total days in statement period: 31

AMERICAN RIVER FLOOD CONTROL DISTRICT  
C/O ROBERT MERRITT, CPA  
4000 MAGNOLIA HILLS DR  
EL DORADO HILLS CA 95762-6561

Page 1  
0811090736  
( 58)

Direct inquiries to:  
916-567-2836

---

### Public Fund Interest Checking

Account number	0811090736	Beginning balance	\$208,978.86
Enclosures	58	Total additions	266,832.98
Low balance	\$66,026.70	Total subtractions	265,867.45
Average balance	\$203,890.98	Ending balance	\$209,944.39
Avg collected balance	\$203,889		

### CHECKS

Number	Date	Amount	Number	Date	Amount
7666	08-31	24,658.27	7742	08-24	530.67
7683 *	08-11	851.00	7743	08-24	4,356.39
7722 *	08-24	1,374.11	7744	08-31	130.00
7723	08-25	31,333.87	7745	08-21	99.06
7724	08-25	12,051.47	7746	08-20	25,000.00
7725	08-27	71.72	7747	08-25	1,083.15
7726	08-25	691.22	7748	08-28	3,150.51
7727	08-25	367.02	7749	08-20	4,090.60
7728	08-24	220.34	7750	08-25	2,085.00
7729	08-26	158.06	7751	08-21	1,020.69
7730	08-28	43.28	7752	08-21	1,055.75
7731	08-21	350.00	7753	08-21	600.00
7732	08-24	10,866.50	7754	08-24	499.83
7733	08-31	690.42	7755	08-21	30.00
7734	08-25	85.16	7756	08-25	366.12
7735	08-27	92.00	7757	08-24	188.52
7736	08-26	1,072.51	7758	08-24	826.95
7737	08-21	836.00	7759	08-20	968.41
7738	08-24	386.60	7760	08-24	1,500.00
7739	08-21	1,370.35	7762 *	08-25	1,574.88
7740	08-24	3,120.90	7763	08-24	368.60
7741	08-24	5,960.25	7764	08-26	979.88

AMERICAN RIVER FLOOD CONTROL DISTRICT  
August 31, 2020

Page 2  
0811090736

Number	Date	Amount	Number	Date	Amount
7765	08-21	1,062.85	7771	08-31	1,341.27
7766	08-25	200.00	7772	08-25	568.68
7767	08-28	13,639.92	7773	08-26	532.43
7768	08-21	5,782.96	7774	08-24	737.32
7769	08-27	183.66	7775	08-26	615.54
7770	08-24	519.00	* Skip in check sequence		

## DEBITS

Date	Description	Subtractions
08-04	' ACH Withdrawal CALPERS 1900 100000016126545	3,119.44
08-04	' ACH Withdrawal CALPERS 1900 100000016125629	127.94
08-04	' ACH Withdrawal CALPERS 3100 100000016063812	2,274.21
08-04	' ACH Withdrawal CALPERS 3100 100000016063767	3,660.81
08-04	' ACH Withdrawal CALPERS 1900 100000016125622	6,404.99
08-05	' ACH Withdrawal HEALTHEQUITY INC HealthEqui 200805	150.00
08-07	Incoming Wire Fee 202008070031564 COUNTY OF SACRAMENSACRAMENTO CA 9581 PROPERTY TAX DISTR	15.00
08-14	' ACH Withdrawal INTUIT PAYROLL S QUICKBOOKS 200814 946000047	32,734.70
08-20	' ACH Withdrawal INTUIT PAYROLL S QUICKBOOKS 200820 946000047	535.65
08-27	' ACH Withdrawal CALPERS 1900 100000016149287	700.00
08-27	' ACH Withdrawal CALPERS 3100 100000016101094	1,895.17
08-27	' ACH Withdrawal CALPERS 3100 100000016101060	3,402.21
08-28	' ACH Withdrawal HEALTHEQUITY INC HealthEqui 200828	152.95
08-28	' ACH Withdrawal CALPERS 1900 100000016153443	3,012.04
08-31	' ACH Withdrawal INTUIT PAYROLL S QUICKBOOKS 200831 946000047	35,339.99
08-31	' Service Charge ADDITIONAL DEBITS	2.66

AMERICAN RIVER FLOOD CONTROL DISTRICT  
 August 31, 2020

Page 3  
 0811090736

**CREDITS**

Date	Description	Additions
08-07	Incoming Wire 202008070031564 COUNTY OF SACRAMENSACRAMENTO CA 9581 PROPERTY TAX DISTR	30,998.97
08-20	Deposit	51.83
08-26	Cash Mgmt Trsfr Cr REF 2391401L FUNDS TRANSFER FRMDEP XXXXX0952 FROM	235,765.00
08-31	Interest Credit	17.18

**DAILY BALANCES**

Date	Amount	Date	Amount	Date	Amount
07-31	208,978.86	08-14	190,639.74	08-26	298,433.28
08-04	193,391.47	08-20	160,096.91	08-27	292,088.52
08-05	193,241.47	08-21	147,889.25	08-28	272,089.82
08-07	224,225.44	08-24	116,433.27	08-31	209,944.39
08-11	223,374.44	08-25	66,026.70		

**INTEREST INFORMATION**

Annual percentage yield earned	0.10%
Interest-bearing days	31
Average balance for APY	\$203,889.30
Interest earned	\$17.18

**OVERDRAFT/RETURN ITEM FEES**

	Total for this period	Total year-to-date
Total Overdraft Fees	\$0.00	\$0.00
Total Returned Item Fees	\$0.00	\$0.00

**CERTIFICATION**

The American River Flood Control District's investment portfolio [] is [ is not] in compliance with the District's Financial Management Investments Plan.

The District's investment portfolio is not in compliance in the following respects:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

A cash flow analysis confirms that the District [ is] [ is not] expected to be able to meet its expenditure requirements for the next six months.

The District's cash is insufficient to meet obligations for the next six months as a result of the following:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Attached hereto are the most recent statements of accounts of the following District accounts:

- LAIF Account, State Treasurer's Office      **Dated August 2020**
- Investment Pool A Account, City of Sacramento      **Dated August 2020**
- District Checking Account, River City Bank      **Dated August 2020**
- District Repurchase Account, River City Bank      **Dated August 2020**

Certified by: \_\_\_\_\_ Date: \_\_\_\_\_  
Rachelanne Vander Werf, District Treasurer

American River Flood Control District  
Statement of Operations  
July 1, 2020 to September 30, 2020 (Three Months Ending of Fiscal 2021)  
For Internal Use Only

	Year to Date July 1, 2020 to September 30, 2020	Budget	Percent of Budget
<b>Revenues</b>			
Benefit assessment	\$ -	\$ 1,429,793	0.00%
Consolidated capital assessment	-	980,000	0.00%
Interest	24,781	77,267	32.07%
O & M agreements	-	231,801	0.00%
Miscellaneous	-	-	Not budgeted
<b>Total Revenues</b>	<u>24,781</u>	<u>2,718,861</u>	0.91%
<b>M &amp; O Expenses</b>			
Salaries and wages	231,382	833,238	27.77%
Payroll tax expense	17,509	66,659	26.27%
Pension expense	50,157	189,428	26.48%
Compensation insurance	-	41,662	0.00%
Medical/dental/vision	78,296	216,125	36.23%
Fuel/oil reimbursement	5,269	35,000	15.05%
Equipment rental	5,960	20,000	29.80%
Equipment repairs/parts	16,736	50,000	33.47%
Equipment purchases (< \$5,000)	-	15,000	0.00%
Shop supplies	13,978	20,000	69.89%
Levee maint. (supp. & material)	6,014	20,000	30.07%
Levee maint. chemicals	14,872	27,500	54.08%
Levee maint. services	52,036	80,000	65.05%
Rodent abatement (supplies & materials)	880	10,000	8.80%
Employee uniforms	5,119	7,500	68.25%
Staff training	1,175	7,500	15.67%
Regulation Compliance (OSHA)	-	6,000	0.00%
Miscellaneous	-	2,000	0.00%
Small tools & equipment	274	7,500	3.65%
Emergency preparedness program	4,200	35,000	12.00%
Engineering services	3,294	20,000	16.47%
Environmental services/studies	-	5,000	0.00%
Encroachment remediation	-	15,000	0.00%
Urban camp cleanup	6,044	50,000	12.09%
<b>Total M &amp; O Expenses</b>	<u>513,195</u>	<u>1,780,112</u>	28.83%
<b>Administration Expenses</b>			
Board of trustees compensation	1,558	7,600	20.50%
Trustee expenses	-	2,400	0.00%
Trustee training	-	5,000	0.00%
Accounting services	700	15,000	4.67%
Legal services (general)	3,733	50,000	7.47%
Utilities	8,369	40,000	20.92%
Telephone	2,970	25,000	11.88%
Retiree benefits	46,171	143,000	32.29%
Office/shop/yard lease	1,800	7,200	25.00%
Office equipment/furniture	479	7,500	6.39%
Office supplies	-	-	Not budgeted
Auto allowance	1,775	6,600	26.89%
Parking reimbursement	-	500	0.00%
General office expense	1,740	15,000	11.60%
Technology and software	5,724	10,000	57.24%
Legislative services	-	-	Not budgeted
Dues and associations	14,221	25,000	56.88%
Property and liability insurance	10,786	42,000	25.68%
Conference/workshop/seminar	-	-	Not budgeted
Public relations/information	-	30,000	0.00%
Miscellaneous	881	5,000	17.62%
Election expense	-	99,723	0.00%
Employee morale/wellness	-	2,000	0.00%
Investment fees	-	20,000	0.00%
Community services	-	1,500	0.00%
Bookkeeping services	2,213	14,000	15.81%
Property taxes	-	3,000	0.00%
Building maintenance	156	10,000	1.56%
County Dtech fees for DLMS	31,669	55,000	57.58%
Interest expense	138	-	Not budgeted
<b>Total Administration Expenses</b>	<u>135,083</u>	<u>642,023</u>	21.04%
<b>Special Projects Expenses</b>			
Engineering studies/survey studies	-	170,000	0.00%
Levee standards compliance	-	25,000	0.00%
Encroachment remediation	-	-	Not budgeted
Vegetation management	-	-	Not budgeted
Small capital projects	-	50,000	0.00%
<b>Total Special Project Expenses</b>	<u>-</u>	<u>245,000</u>	0.00%
<b>Capital Outlay</b>			
Bank protection	-	-	Not budgeted
Magpie Creek	-	-	Not budgeted
Property acquisition	-	-	Not budgeted
Miscellaneous	-	-	Not budgeted
Equipment purchases (over \$5,000)	-	100,000	0.00%
<b>Total Capital Outlay</b>	<u>-</u>	<u>100,000</u>	
<b>Capital Outlay: District Headquarters Build-Out</b>			
Building improvements/maintenance	1,575	700,000	0.23%
La Riviera improvements/maintenance	-	2,000	0.00%
	<u>1,575</u>	<u>702,000</u>	

Note: Amounts above are not audited

The above information is current through the last day of the previous month's bank activity.

Data has been verified by the bookkeeper and physical copies of checks have not been reviewed or received and some checks may not have cleared the bank account.

Cash Flow Report													
Maintenance and Operations Expens	20-Jul	20-Aug	20-Sep	20-Oct	20-Nov	20-Dec	21-Jan	21-Feb	21-Mar	21-Apr	21-May	21-Jun	TOTAL
500 - Salary/Wages	84,955.85	72,305.42	71,963.98	74,588.44	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	303,813.69
501 - Payroll Taxes	6,551.57	5,583.83	5,557.69	5,202.81	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	22,895.90
502 - Pension	17,202.17	15,822.01	21,318.10	10,707.39	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	65,049.67
503 - Compensation Insurance	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
504 - Medical/Dental/Vision	24,342.88	19,791.24	19,837.24	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	63,971.36
508 - Fuel/Oil	2,345.10	4,356.39	2,664.57	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	9,366.06
509 - Equipment Rental	0.00	5,960.25	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5,960.25
510 - Equipment Purchase(< \$5000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
511 - Equipment Repair/Parts	15,604.93	6,143.91	9,008.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	30,756.86
512 - Shop Supplies	4,256.28	8,016.10	4,875.31	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	17,147.69
514 - Levee Maint(Supplies&Materi	100.38	5,826.24	187.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	6,114.31
515 - Levee Maintenance Services	2,200.00	25,393.37	26,643.08	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	54,236.45
516 - Employee Uniforms	0.00	0.00	5,768.62	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5,768.62
518 - Staff Training	1,529.00	0.00	525.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2,054.00
519 - Miscellaneous O&M	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
521 - Small Tools & Equip	0.00	0.00	273.52	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	273.52
523 - Levee Maint. (Chemicals)	0.00	13,414.68	1,344.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	14,759.42
525 - Emergency Preparedness Pr	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
530 - Encroachment Remediation I	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
532 - Rodent Abatement	0.00	225.24	766.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	992.04
533 - Urban Camp Cleanup	1,380.45	2,421.74	3,622.43	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	7,424.62
605 - Engineering Services	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
615 - Survey Services	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
616 - Environmental Services/Studi	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Total M&amp;O Expense</b>	<b>160,468.61</b>	<b>185,260.42</b>	<b>174,356.79</b>	<b>90,498.64</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>610,584.46</b>

Administrative Expenses	20-Jul	20-Aug	20-Sep	20-Oct	20-Nov	20-Dec	21-Jan	21-Feb	21-Mar	21-Apr	21-May	21-Jun	TOTAL
505 - Telephone	1,521.70	1,626.92	1,545.83	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	4,694.45
506 - Utility Charges	3,362.49	4,354.93	3,882.24	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	11,599.66
507 - Office/Shop Lease	600.00	600.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1,800.00
513 - Office Supplies	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
517 - Auto Allowance	550.00	550.00	550.00	550.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2,200.00
520 - Retiree Benefits	11,542.63	11,542.63	11,542.63	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	34,627.89
522 - Office Equipment/Furniture	129.24	0.00	478.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	607.74
526 - Mileage/Parking Reimburse	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
527 - General Office Expense	1,081.26	1,386.08	951.91	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3,419.25
529 - Pre-funding Retiree Benefits	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
531 - Technology & Software	467.39	1,139.73	5,407.82	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	7,014.94
600 - Board of Trustees Compensa	1,380.45	2,421.74	3,622.43	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	7,424.62
601 - Trustee Expenses	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
602 - Accounting Services	475.00	475.00	475.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1,425.00
603 - Legal Fees (General)	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
604 - Flood Litigation	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
606 - Legislative Services	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
607 - Dues and Assoc. Expenes	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	700.00
608 - Insurance Premiums	4,832.00	11,702.50	3,733.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	20,267.50
609 - Conference /Workshops/Sem	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
610 - Public Relations Information	3,591.00	4,090.60	3,294.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	10,975.60
611 - Election Expenses	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
612 - District Annexations	0.00	0.00	5,862.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5,862.00
613 - Community Services	0.00	12,051.47	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	12,051.47
614 - Miscellaneous Admin	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
617 - Investment Fees	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
618 - Property Tax	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
619 - Building Maintenance	3,579.77	238.25	172.36	34.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	4,024.38
620 - Bookkeeping Services	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
621 - County Assessment Fees	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
622 - County DTEch Fees for DLMS	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

AMERICAN RIVER FLOOD CONTROL DISTRICT  
Cash Flow Report  
July 2020 through June 2021

623 - Employee Morale/Wellness	0.00	4,391.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	4,391.00
<b>Total Administrative</b>	<b>33,112.93</b>	<b>57,270.85</b>	<b>42,117.72</b>	<b>584.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>133,085.50</b>

Special Projects Expenses	20-Jul	20-Aug	20-Sep	20-Oct	20-Nov	20-Dec	21-Jan	21-Feb	21-Mar	21-Apr	21-May	21-Jun	TOTAL
702 - Engineering/Survey Studies	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
703 - Encroachment Remediation §	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
704 - Vegetation Management	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
705 - Small Capital Projects	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
707 - Levee Standards Compliance	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Total Special Projects</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>

Capital Outlay: Flood Control	20-Jul	20-Aug	20-Sep	20-Oct	20-Nov	20-Dec	21-Jan	21-Feb	21-Mar	21-Apr	21-May	21-Jun	TOTAL
700 - Bank Protection	0.00	0.00	31,669.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	31,669.50
701 - Magpie Creek	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
706 - Property Acquisition	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
709 - Equipment Purchase (> \$500)	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Total Capital Outlay: Flood Control</b>	<b>0.00</b>	<b>0.00</b>	<b>31,669.50</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>31,669.50</b>

Income	20-Jul	20-Aug	20-Sep	20-Oct	20-Nov	20-Dec	21-Jan	21-Feb	21-Mar	21-Apr	21-May	21-Jun	TOTAL
120 - Benefit Assessment	0.00	30,998.97	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	30,998.97
122 - SAFCA CAD4	980,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	980,000.00
123 - Interest	2,388.20	616.69	328.85	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3,333.74
124 - O&M Agreements	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
126 - Miscellaneous Income	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Total Income</b>	<b>982,388.20</b>	<b>31,615.66</b>	<b>328.85</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>1,014,332.71</b>

Fund Balance

District Operations Fund	Jul 20	Aug 20	Sept 20	Oct 20	Nov 20	Dec 20	Jan 21	Feb 21	Mar 21	Apr 21	May 21	Jun 21
Beginning Balance	1,665,499.72	2,804,306.38	2,593,390.77	2,377,245.11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Income	1,332,388.20	31,615.66	328.85	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Expenses	193,581.54	242,531.27	216,474.51	91,082.64	0.00	0.00	0.00	0.00	0.00	0.00	0.00	72,000.00
Ending Balance	2,804,306.38	2,593,390.77	2,377,245.11	2,286,162.47	0.00	0.00	0.00	0.00	0.00	0.00	0.00	(72,000.00)

Capital Outlay Reserve Fund	Jul 20	Aug 20	Sept 20	Oct 20	Nov 20	Dec 20	Jan 21	Feb 21	Mar 21	Apr 21	May 21	Jun 21
Beginning Balance	1,270,000.00	920,000.00	920,000.00	920,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Income	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Expenses	350,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Ending Balance	920,000.00	920,000.00	920,000.00	920,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Retiree Health Benefit Reserve Fund	Jul 20	Aug 20	Sept 20	Oct 20	Nov 20	Dec 20	Jan 21	Feb 21	Mar 21	Apr 21	May 21	Jun 21
Beginning Balance	3,552,014.00	3,552,014.00	3,552,014.00	3,552,014.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Income	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	72,000.00
Expenses	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Ending Balance	3,552,014.00	3,552,014.00	3,552,014.00	3,552,014.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	72,000.00

Flood Emergency Response Reserve Fund	Jul 20	Aug 20	Sept 20	Oct 20	Nov 20	Dec 20	Jan 21	Feb 21	Mar 21	Apr 21	May 21	Jun 21
Beginning Balance	1,500,000.00	1,500,000.00	1,500,000.00	1,500,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Income	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Expenses	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Ending Balance	1,500,000.00	1,500,000.00	1,500,000.00	1,500,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Emergency Repair Reserve Fund	Jul 20	Aug 20	Sept 20	Oct 20	Nov 20	Dec 20	Jan 21	Feb 21	Mar 21	Apr 21	May 21	Jun 21
Beginning Balance	1,500,000.00	1,500,000.00	1,500,000.00	1,500,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Income	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Expenses	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Ending Balance	1,500,000.00	1,500,000.00	1,500,000.00	1,500,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

<b>Total Balance</b>	<b>10,276,320.38</b>	<b>10,065,404.77</b>	<b>9,849,259.11</b>	<b>9,758,176.47</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>
----------------------	----------------------	----------------------	---------------------	---------------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------	-------------







**American River Flood Control District  
Central Valley Flood Protection Board Permit Application  
Sump 103 Modifications (City of Sacramento)  
Staff Report**

**Discussion:**

The City of Sacramento submitted this encroachment permit application to modify facilities at their Sump 103 Pump Station. The work proposed is to remove and replace approximately 50 ft of two (2) 36" welded steel pipes at the pump discharge location and outfall structure.

Sump 103 is located adjacent to the Arcade Creek North Levee and is just west of the bike trail bridge crossing.

These modifications are required to upgrade the pipe outfall system at the pump station. Recent work conducted by SAFCA under the North Area Streams Project replaced only the segments of pipe that crossed through the levee. This work will complete the upgrade to the facility by replacing the pipe discharge sections at the pumps and also the pipe outfall sections and flap gates.

These modifications will be routine construction installations and do not present considerable engineering challenges. It is not anticipated that this work will pose significant operations and maintenance impacts to the District.

**Recommendation:**

The General Manager recommends that the Board of Trustees endorse the CVFPB permit application.

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

**Application No.** \_\_\_\_\_  
(For Office Use Only)

1. Description of proposed work being specific to include all items that will be covered under the issued permit.  
Sump 103 Modifications: Remove and replace approximately 50 ft of two (2) 36" welded steel pipes at the pump discharge location and outfall structure.

2. Project  
Location: Sacramento County, in Section See Attachment A  
Township: See Attachment A (N) (S), Range: See Attachment A (E) (W), M. D. B. & M.  
Latitude: 38.62590 Longitude: -121.44775  
Stream: Arcade Creek, Levee: Right Bank Designated Floodway: Arcade Creek  
APN: See Attachment A

3. Raymond Kong, PE of 1395 35th Ave  
Name of Applicant / Land Owner Address  
Sacramento CA 95822 (916) 808-1435  
City State Zip Code Telephone Number  
RKong@cityofsacramento.org  
E-mail

4. Ashley Smith, PE of Peterson Brustad Inc.  
Name of Applicant's Representative Company  
Folsom CA 95630 (916) 608-2212 x 123  
City State Zip Code Telephone Number  
asmith@pbieng.com  
E-mail

5. Endorsement of the proposed project from the Local Maintaining Agency (LMA):

We, the Trustees of American River Flood Control District approve this plan, subject to the following conditions:  
Name of LMA

Conditions listed on back of this form       Conditions Attached       No Conditions

\_\_\_\_\_  
Trustee Date      Trustee Date  
\_\_\_\_\_  
Trustee Date      Trustee Date

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

6. Names and addresses of adjacent property owners sharing a common boundary with the land upon which the contents of this application apply. If additional space is required, list names and addresses on back of the application form or an attached sheet.

Name	Address	Zip Code
See Attachment A		

7. Has an environmental determination been made of the proposed work under the California Environmental Quality Act of 1970?  Yes  No  Pending

If yes or pending, give the name and address of the lead agency and State Clearinghouse Number:

City of Sacramento  
1395 35th Avenue  
Sacramento, CA 95822

SCH No. Pending

8. When is the project scheduled for construction? April 2021

9. Please check exhibits accompanying this application.

- A.  Regional and vicinity maps showing the location of the proposed work.
- B.  Drawings showing plan view(s) of the proposed work to include map scale.
- C.  Drawings showing the cross section dimensions and elevations (vertical datum?) of levees, berms, stream banks, flood plain,
- D.  Drawings showing the profile elevations (vertical datum?) of levees, berms, flood plain, low flow, etc.
- E.  A minimum of four photographs depicting the project site.

\_\_\_\_\_  
Signature of Applicant

\_\_\_\_\_  
Date

Include any additional information:

A summary of the Project and a description of the proposed methods are provided in Attachment A. Attachment B includes relevant plan sheets which are an excerpt from a larger plan set. Attachment C includes the categorical permission checklist. The intent of this application is to modify the existing encroachment permit. The existing Permit number for Sump 103 is 16687.

**Attachment A – Summary of Proposed Work**

**CITY OF SACRAMENTO PUMP OUTFALLS PROJECT:  
CENTRAL VALLEY FLOOD PROTECTION BOARD ENCROACHMENT PERMIT**

**SUMMARY OF PROPOSED WORK**

September 15, 2020

**INTRODUCTION**

As mandated by the Sacramento Area Flood Control Agency (SAFCA) and the U.S. Army Corps of Engineers (USACE), sump station outfalls that penetrate and cross major levees are inspected on a 5-year cycle. The project entails the complete replacement of the pump discharge for three (3) drainage sump station facilities and partial replacement of the pump discharge pipe for five (5) drainage sump station facilities. The following information pertains to a partial replacement sump (Sump 103) that will need an updated Encroachment Permit from the CVFPB.

**APN Parcels**

Sump	Existing Permit #	APN
103	16687	250-0270-012-0000, 263-0010-015-0000, 263-0010-016-0000

**ADJACENT PARCELS**

All of the parcels adjacent to the Sump to be modified are listed in the table presented below as provided by the Sacramento County Assessor's Office.

APN	Address	Owner	Owner Address	City	Zip
250-0270-009-0000	ALTOS AVE	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
250-0260-014-0000	760 CARROLL AVE	JAGDISH PRASAD	1237 BELL AVE	SACRAMENTO	95838
250-0260-019-0000	3241 ALTOS AVE	CHARLES E CHASE	3241 ALTOS AVE	SACRAMENTO	95838
250-0260-016-0000	3233 ALTOS AVE	SYED ISHAQ HAMDANI	3233 ALTOS AVE	SACRAMENTO	95838
263-0041-019-0000	813 ARCADE BLVD	SHARON LEE NAYLOR	813 ARCADE BLVD	SACRAMENTO	95815
263-0260-010-0000	TRACTION AVE	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814

**TOWNSHIP AND RANGE INFORMATION**

Note that gaps exist in Townships and Ranges within the project area. Land not covered by T9N R5E has been in private ownership since before California joined the United States and therefore is not part of the Township and Range system, which was a survey of federal lands.

**SITE PHOTOGRAPHS**

Attached to this Summary of Proposed Work are photographs showing levee and channel areas representative of proposed work sites.



Figure 1: Arcade Creek north levee near Sump 103 looking south west





Figure 2: View looking west on the land side of the levee.





Figure 3: View looking northwest toward the Sump 103 outfall as it enters Arcade Creek



Figure 4: View looking south toward the Sump 103 outfall as it enters Arcade Creek.

**Attachment B – Plan Sheets**

*(Excerpt from larger plan set for Pump Outfalls Replacement Project – A)*



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

<b>BENCH MARK</b>	ELEV. 44.82
DESCRIPTION:	CP/RBR&CAP

<b>FIELD BOOK</b>	0000
SCALE:	1" = 10'
H: H:	
V: V:	

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21





IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 103**  
**DEMO PLAN**

65% SUBMITTAL

PN: W14130615	DWG. NO. C21
	SHEET 24 OF 47

Page 11



PN: W14130615

PN: W14130615

65% SUBMITTAL

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.82
DESCRIPTION:	CP/RBR&CAP	


FIELD BOOK	0000
SCALE:	1" = 10'
H: H:	
V: V:	

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY:	E. TUTEJA	DESIGNED BY:	B. JENSEN
DATE:	09/15/20	R.C.E. NO.:	C90949
		DATE:	03/31/22
		R.C.E. NO.:	C86512
		DATE:	03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 103**  
**SITE PLAN**

DWG. NO.	C22
SHEET	25
OF	47
Page 12	



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 30" WSP AND APPURTENANCES FROM STA -0+54.8 TO STA -0+51.7 AND STA 0+38.1 TO STA 0+55.4 PER DETAIL 2/C38
  - 2 INSTALL 30" WSP FROM STA -0+54.8 TO STA -0+51.7 AND STA 0+38.1 TO STA 0+55.4 PER DETAIL 3/C38
  - 3 CONNECT TO EXISTING STEEL COUPLING
  - 4 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 5 CONNECT TO EXISTING PIPE PER DETAIL 3/C37
  - 6 REMOVE AND SALVAGE STEEL COUPLING
  - 7 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

PN: W14130615

65% SUBMITTAL

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.82
DESCRIPTION:	CP/RBR&CAP	

FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"	


**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 103**  
**PLAN AND PROFILE 1 - 30" WSP**

DWG. NO.	C23
SHEET	26
OF	47
Page	13



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 30" WSP AND APPURTENANCES FROM STA -0+59.6 TO STA -0+56.5 AND STA 0+37.1 TO STA 0+55.4 PER DETAIL 2/C38
  - 2 INSTALL 30" WSP FROM STA -0+54.8 TO STA -0+51.7 AND STA 0+37.1 TO STA 0+55.4 PER DETAIL 3/C38
  - 3 CONNECT TO EXISTING STEEL COUPLING
  - 4 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 5 CONNECT TO EXISTING PIPE PER DETAIL 3/C37
  - 6 REMOVE AND SALVAGE STEEL COUPLING
  - 7 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.82
DESCRIPTION:	CP/RBR&CAP	

FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"	
H: H:	
V: V:	

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

DRAWN BY: E. TUTEJA      DESIGNED BY: B. JENSEN      CHECKED BY: A. SMITH  
 DATE: 09/15/20      R.C.E. NO. C90949      DATE: 03/31/22      R.C.E. NO. C86512      DATE: 03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 103**  
**PLAN AND PROFILE 2 - 30" WSP**


65% SUBMITTAL

DWG. NO.	C24
SHEET	27
OF	47






OUTFALL STRUCTURE CONNECTION DETAIL **1**  
NTS



NOTES:  
1. PROVIDE HAND HOLES AS NEEDED TO INSTALL FIELD LINING. WELD HAND HOLE CLOSED WHEN COMPLETE. HAND HOLES NOT REQUIRED AT OUTLETS IF ACCESSIBLE THROUGH FLAP GATE.

NEW OR EXISTING STEEL  
PIPE CONNECTION DETAIL **2**  
NTS



TRENCH SECTION AND SEQUENCING **3**  
NTS

NOTES:


- CONTRACTOR SHALL REPLACE EXISTING PAVEMENT IN KIND. BASED ON LIMITED FIELD INVESTIGATIONS, EXISTING PAVEMENT SECTION ARE ASSUMED 2" AC ON 6" AB
- THE OWNER AND THE CONTRACTOR SHALL JOINTLY DETERMINE THE FINAL WIDTH AND LENGTH OF THE BIKE PATH CROSSING BASED ON FIELD CONDITIONS AND CONSTRUCTION PROCEDURES.
- CONTRACTOR SHALL REMOVE EXISTING BIKE PATH AS NEEDED TO CONSTRUCT PROPOSED PIPE. IMPACTED AREAS SHALL BE REPLACED IN ACCORDANCE WITH CITY OF SACRAMENTO STANDARD DETAIL T-21

CONSTRUCTION SEQUENCE:

- STEP 1: SAWCUT LIMITS 09F TRENCH EXCAVATION TO CLEAN CUT LIMITS. REMOVE EXISTING ASPHALT CONCRETE TO THE MIN EXTENT REQUIRED TO CONSTRUCT PROPOSED PIPE. PROPOSED PIPE SHALL BE CONSTRUCTED A MIN OF 2' FROM FG. TRENCH PLATES SHALL BE PROVIDED TO MAINTAIN ACCESS OVER CUTOFF WALL DURING CONSTRUCTION IN ACCORDANCE WITH THE SPECIFICATIONS.
- STEP 2: PLACE AB TO MATCH EXISTING THICKNESS. PLACE AC OVERLAY FROM EXTENT APPROVED BY AGENCY AND CONTRACTOR TO LIMITS OF SAWCUT. PROVIDE PAVEMENT MARKING AND STRIPING TO MATCH EXISTING.

LEGEND:

- |                                    |          |
|------------------------------------|----------|
| EXISTING                           | PROPOSED |
|                                    |          |
| GRIND AND OVERLAY ASPHALT CONCRETE |          |
|                                    |          |
| AGGREGATE BASE (AB)                |          |
|                                    |          |
| ASPHALT CONCRETE (AC)              |          |



CROWN SURFACING DETAIL **4**  
NTS

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK DESCRIPTION:	ELEV. _____

FIELD BOOK	0000
SCALE:	1" = _____
H:	
V:	

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"


<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
MISCELLANEOUS DETAILS I

65% SUBMITTAL


DWG. NO. C37
SHEET 40 OF 47




TYPICAL SLOPE BENCHING NOTES:

1. PLACE FILL IN HORIZONTAL LIFTS AGAINST VERTICAL FACES CUT INTO EXISTING LEVEE MATERIAL.
2. THE BOTTOM OF THE KEY TRENCH SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES AND RECOMPACTED TO 95% MAX DENSITY PER ASTM D698.

SLOPE BENCHING (LANDSIDE OR WATERSIDE) DETAIL 1  
NTS



TYPICAL REMOVAL OF EXISTING PIPE DETAIL 2  
NTS



INSTALLATION OF NEW PIPE DETAIL 3  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.
DESCRIPTION:	

FIELD BOOK	0000
SCALE:	1" = 1'
H:	
V:	

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

<b>CITY OF SACRAMENTO</b> DEPARTMENT OF UTILITIES			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**MISCELLANEOUS DETAILS II**

65% SUBMITTAL

PN: W14130615	DWG. NO. C38
	SHEET 41 OF 47
	Page 16

PN: W14130615

**Attachment C – Categorical Permission Checklist**

## Categorical Permission Alteration Description – 16. Pressurized Pipes

The categorical permission covers the installation, modification, and replacement of pressurized pipes that comply with certain terms and conditions. Particularly, all pressurized pipes must be designed and installed in accordance with current USACE standards. The total area of disturbance, including staging and access areas, must not exceed 5 acres. Pressurized pipes must also be designed to prevent, (1) flotation from uplift, (2) scour or erosion, (3) damage from debris on the waterside, particularly during flood flows, (4) leakage, (5) seepage along proposed pipes, (6) corrosion, and (7) damage from vehicular loads.

All new pressurized pipes should go up and over the levee DWSE. Pressurized pipes passing over or within the freeboard zone of a levee (i.e., above the levee DWSE), should be made of metal, preferably ductile iron or coated steel, suitable for use with flexible couplings.

Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM). Pipes that pass above the DWSE must have 2 feet of cover (low permeability or CLSM) to prevent damage by vehicles and equipment. Cover material on the levee crown must be placed at a ratio of 10H:1V, in the upstream/downstream direction of the levee. Pipes on the sides of the levee should be covered with a minimum of 1 foot of low permeability material, compacted in 4- to 6-inch lifts or CLSM to protect them from debris during high water (waterside) or to keep them from interfering with or being damaged by operations or maintenance of the levee (landside). Fill must be free of deleterious materials and construction debris and placed in 4- to 6-inch-thick loose lifts and compacted to not less than 95% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D698 (USACE preferred method), or alternately, 90% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D1557. At the sponsor and levee maintaining agency's discretion, pipes on the levee slopes may be left exposed.

Only suitable material must be used as levee fill materials. Fill must be free from: roots and other organic matter, contaminated hazardous or toxic material, trash, debris, and frozen materials. Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve.

Pressurized pipes terminating in the channel require a positive closure device on the waterside that is accessible from the levee crown. Pressurized pipes transporting product completely across or through the federal project easement require positive closure devices located landward of any levees and channel. The positive closure device shall be located within one mile on both sides of the federal project. If the invert of the pipe is over the levee crown, the combination of a pump station on the waterside and a siphon breaker is considered an appropriate means of closure. Pipes located within or beneath a levee must have watertight joints that can accommodate movements resulting from settlement.

All pressurized pipes that cross the levee foundation at a depth less than or equal to two times the height of the levee should be evaluated for uplift. Pipes crossing the surface of the levee must be designed to counteract buoyancy forces of an empty pipe, with water at the DWSE.

Pressurized pipelines running parallel to flood risk management projects should be located at least 15 feet beyond the levee toes. Pipe location and orientation must be clearly marked in the field so they can be easily identified for flood fighting crews.

If appropriate, the requester should prepare an excavation plan demonstrating the effects of excavation on the stability of the embankments.

The site layout should provide adequate access for maintenance vehicles to refill fuel tanks and service/replace pumps, generators, etc. Pressurized pipes must also allow easy access for rapid closure in the event of leakage or rupture.

No plastic pipes (HDPE, PVC, etc.) are allowed in the levee embankment or its foundation unless they are embedded in concrete.

If an electrochemical or chemical reaction between the substratum or groundwater and pipe materials is expected, the pipe and pipe couplings must be protected.

After installation of pressurized pipes, the requester must demonstrate 0% pipe leakage in pipes in the levee. Pipes must be pressure tested to industry standards. Pipes must be regularly inspected, including the interior, if possible, looking for signs of maintenance issues. If an inspection indicates corrosion, alignment sag or heave, or separation at joints, corrective action must be taken as soon as possible to avoid failure. Pipe valves must be periodically inspected and pressure tested to ensure that they are functioning properly. Pressure tests must show no significant loss in pressure. Leaks and other deficiencies must be addressed as soon as possible. All replacement parts must be of equivalent or better quality than those being replaced.

The preferred method for abandoning pipes that pass through or over a levee is complete removal. If removal is not feasible, the pipes and other structures may be filled with a cement/bentonite-based grout or flowable fill. The grout needs to be sufficiently fluid so that it can be pumped to completely fill the pipe leaving no voids.

### Categorical Permission Alteration Checklist – 16. Pressurized Pipes

*Note:* The following checklist is intended for planning purposes only, and includes information that USACE reviewers look for when considering a Section 408 request for pressurized pipes under the Categorical Permission. To be reviewed under the Categorical Permission, the proposed project must adhere to all requirements of the Categorical Permission, including the full alteration description (see previous page). The plans and narrative project description should reflect this information.

1.	<input type="checkbox"/> New Construction <input checked="" type="checkbox"/> Replacement <input type="checkbox"/> Modification <input type="checkbox"/> Authorize Existing		
2.	Maximum total area of disturbance is 5 acres:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Area of disturbance is 0.006 acre.</u>		
3.	Pipes are designed to prevent flotation from uplift, scour or erosion, damage from debris on the waterside (particularly during flood flows), seepage along proposed pipes, corrosion, leakage, and damage from vehicular loads:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
4.	Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM):	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
5.	Pipes passing over the DWSE will have a minimum of 2 feet of cover (low permeability or CLSM):	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
6.	If material must be added to the levee crown, the added material must be sloped at a ratio of 10H:1V horizontal to vertical, in the upstream/downstream direction to prevent a “speed bump” effect and facilitate vehicle access:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment:		
7.	Fill will be compacted to at least 95% of maximum density as determined by ASTM D698, between -2 and +3% of optimum moisture content:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.6B.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
8.	Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 2.2A.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
9.	All fill will be free of organics or other inappropriate materials:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.9.B.1.6.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		

10.	Pipes terminating in the channel have a positive closure device on the waterside that is accessible from the levee crown:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
11.	Pipes transporting product completely across the federal project have a positive closure devices located within 1 mile on both sides of the federal project:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
12.	Pipes located within or beneath a levee have watertight joints that can accommodate movements resulting from settlement:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>Refer to detail 2 on Sheet 40</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
13.	Pipes crossing the surface of the levee are designed to counteract buoyancy forces of an empty pipe, with water at the DWSE:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	
	Reference: <u>Refer to detail 3 on sheet 41</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
14.	Pipe location and orientation will be clearly marked in the field:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>pipe location and orientation can be identified by vault structure and outfall location</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
15.	Pipes will allow easy access for rapid closure:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: <u>Positive valve closures on the levee crest will ensure easy access for rapid closure.</u>			
16.	Plastic pipes within the levee embankment or its foundation are embedded in concrete:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
17.	If a chemical or electrochemical reaction is expected, the pipe and pipe couplings must be protected:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
18.	Any work within the levee embankment or foundation?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
19.	Any work ≤50 feet beneath the channel invert?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
20.	Hydraulic blockage calculation ≥1%?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
21.	Hydraulic model used for hydraulic analysis?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			

– For Official Use Only below this line –

*Comment*

**CP Eligibility Review**

<u>Yes</u>	<u>No</u>	<u>Add'l. Info Requested</u>		
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Environmental Reviewer: _____	Date: <small>Click date</small> _____
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Engineering Reviewer: _____	Date: <small>Click date</small> _____



**American River Flood Control District  
Central Valley Flood Protection Board Permit Application  
Sump 151 Modifications (City of Sacramento)  
Staff Report**

**Discussion:**

The City of Sacramento submitted this encroachment permit application to modify facilities at their Sump 151 Pump Station. The work proposed is to remove and replace approximately 140 ft of one (1) 54" welded steel pipe, 140 ft of one (1) 42" HDPE pipe, 140 ft of one (1) 42" welded steel pipe, 280 ft of two (2) 30" welded steel pipes, and 140 ft of one (1) 16" welded steel pipe. Install positive closure vault at top of levee hinge-point. Replace approximately 2,250 square feet of asphalt paving at the south end of the sump station and bike path.

Sump 151 is located adjacent to the American River North Levee and off Canterbury Road (near Costco).

These modifications are required to upgrade the pipe outfall system at the pump station. The current system does not meet modern U.S. Army Corps of Engineers' standards. The USACE now requires that all pressurized pipes cross the levee at or above the 200-year flood elevation for the adjacent channel and that the pipes each have a positive closure device (shut-off valve) at the waterside crown hinge point. The proposed work will upgrade the facility to meet all State and Federal requirements.

Once the work is complete, it is not anticipated that this work will pose significant operations and maintenance impacts to the District. There will be temporary loss of access and thoroughfare for the District during construction.

**Recommendation:**

The General Manager recommends that the Board of Trustees endorse the CVFPB permit application.

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

**Application No.** \_\_\_\_\_  
(For Office Use Only)

1. Description of proposed work being specific to include all items that will be covered under the issued permit.

Sump 151 Modifications: Remove and replace approximately 140 ft of one (1) 54" welded steel pipe, 140 ft of one (1) 42" HDPE pipe, 140 ft of one (1) 42" welded steel pipe, 280 ft of two (2) 30" welded steel pipes, and 140 ft of one (1) 16" welded steel pipe. Install positive closure vault at top of levee hinge-point. Replace approximately 2,250 square feet of asphalt paving at the south end of the sump station and bike path.

2. Project  
Location: Sacramento County, in Section 32  
Township: 9N (N) (S), Range: 5E (E) (W), M. D. B. & M.  
Latitude: 38.59587 Longitude: -121.45773  
Stream: American River, Levee: Right Bank Designated Floodway: American River  
APN: See Attachment A

3. Raymond Kong, PE of 1395 35th Ave  
Name of Applicant / Land Owner Address  
Sacramento CA 95822 (916) 808-1435  
City State Zip Code Telephone Number  
RKong@cityofsacramento.org  
E-mail

4. Ashley Smith, PE of Peterson Brustad Inc.  
Name of Applicant's Representative Company  
Folsom CA 95630 (916) 608-2212 x 123  
City State Zip Code Telephone Number  
asmith@pbieng.com  
E-mail

5. Endorsement of the proposed project from the Local Maintaining Agency (LMA):

We, the Trustees of American River Flood Control District approve this plan, subject to the following conditions:  
Name of LMA

Conditions listed on back of this form  Conditions Attached  No Conditions

\_\_\_\_\_  
Trustee Date Trustee Date  
\_\_\_\_\_  
Trustee Date Trustee Date

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

6. Names and addresses of adjacent property owners sharing a common boundary with the land upon which the contents of this application apply. If additional space is required, list names and addresses on back of the application form or an attached sheet.

Name	Address	Zip Code
See Attachment A		

7. Has an environmental determination been made of the proposed work under the California Environmental Quality Act of 1970?       Yes       No       Pending

If yes or pending, give the name and address of the lead agency and State Clearinghouse Number:

City of Sacramento  
1395 35th Avenue  
Sacramento, CA 95822

SCH No. Pending

8. When is the project scheduled for construction? April 2021

9. Please check exhibits accompanying this application.

- A.  Regional and vicinity maps showing the location of the proposed work.
- B.  Drawings showing plan view(s) of the proposed work to include map scale.
- C.  Drawings showing the cross section dimensions and elevations (vertical datum?) of levees, berms, stream banks, flood plain,
- D.  Drawings showing the profile elevations (vertical datum?) of levees, berms, flood plain, low flow, etc.
- E.  A minimum of four photographs depicting the project site.

\_\_\_\_\_  
Signature of Applicant

\_\_\_\_\_  
Date

Include any additional information:

A summary of the Project and a description of the proposed methods are provided in Attachment A. Attachment B includes relevant plan sheets which are an excerpt from a larger plan set. Attachment C includes the categorical permission checklist. The intent of this application is to modify the existing encroachment permit. The existing Permit number for Sump 151 is 5365.

**Attachment A – Summary of Proposed Work**

**CITY OF SACRAMENTO PUMP OUTFALLS PROJECT:  
CENTRAL VALLEY FLOOD PROTECTION BOARD ENCROACHMENT PERMIT**

**SUMMARY OF PROPOSED WORK**

September 15, 2020

**INTRODUCTION**

As mandated by the Sacramento Area Flood Control Agency (SAFCA) and the U.S. Army Corps of Engineers (USACE), sump station outfalls that penetrate and cross major levees are inspected on a 5-year cycle. The project entails the complete replacement of the pump discharge for three (3) drainage sump station facilities and partial replacement of the pump discharge pipe for five (5) drainage sump station facilities. The following information pertains to a complete replacement sump (Sump 151) that will need an updated Encroachment Permit from the CVFPB.

**APN Parcels**

Sump	Existing Permit #	APN
151	5365	275-0270-036-0000

**ADJACENT PARCELS**

All of the parcels adjacent to the Sump to be modified are listed in the table presented below as provided by the Sacramento County Assessor's Office.

APN	Address	Owner	Owner Address	City	Zip
275-0260-007-0000	CANTERBURY RD	SOUTHERN PACIFIC	1400 DOUGLAS ST	OMAHA	68179
275-0260-014-0000	CANTERBURY RD	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
275-0260-015-0000	CANTERBURY RD	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
275-0260-023-0000	CANTERBURY RD	COUNTY OF SACRAMENTO	10361 ROCKINGHAM DR #100	SACRAMENTO	95827
275-0270-035-0000	236 LATHROP WAY	COUNTY OF SACRAMENTO	10361 ROCKINGHAM DR #100	SACRAMENTO	95827
275-0300-008-0000	281 LATHROP WAY	281 LATHROP CAPITAL LLC	2699 AZALEA RD	SACRAMENTO	95864

**SITE PHOTOGRAPHS**

Attached to this Summary of Proposed Work are photographs showing levee and channel areas representative of proposed work sites.



Figure 1: View of pump station



Figure 2: View of landside levee slope



Figure 3: View from crest of Levee facing eastward






Figure 4: View of outfall structure into American River

**Attachment B – Plan Sheets**

*(Excerpt from larger plan set for Pump Outfalls Replacement Project – A)*



Item 5

PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	46.60
DESCRIPTION:	SPINDLE	

FIELD BOOK	0000
SCALE:	1" = 100'
H:	NTS
V:	NTS

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY:	E. TUTEJA	DESIGNED BY:	B. JENSEN
DATE:	09/15/20	R.C.E. NO.:	C90949 DATE: 03/31/22
		CHECKED BY:	A. SMITH
		R.C.E. NO.:	C86512 DATE: 03/31/21





IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT – A**  
**STAGING AREA**

65% SUBMITTAL

NO.	63
SHEET	3
OF	47

Page 11



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

<b>BENCH MARK</b>	ELEV. 46.60
DESCRIPTION:	
SPINDLE	



<b>FIELD BOOK</b>	0000
SCALE:	
H: 1"=10"	
V: 1"=5"	

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	



IMPROVEMENT PLANS FOR:	
PUMP OUTFALLS REPLACEMENT PROJECT - A	
SUMP 151	
DEMO PLAN	
Page 12	DWG. NO. C1 SHEET 4 OF 47

65% SUBMITTAL



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

<b>BENCH MARK</b>	ELEV. 46.60
DESCRIPTION:	
SPINDLE	

<b>FIELD BOOK</b>	0000
SCALE:	
H: 1"=10"	
V: 1"=5"	

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21



IMPROVEMENT PLANS FOR:



**PUMP OUTFALLS REPLACEMENT PROJECT - A**

**SUMP 151**  
**SITE PLAN**


65% SUBMITTAL

DWG. NO. c2
SHEET 5 OF 47

Page 13



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 30" WSP AND APPURTENANCES FROM STA -0+63.9 TO STA 0+71.6 PER DETAIL 2/C38
  - 2 INSTALL 30" WSP FROM STA -0+63.9 TO STA 0+71.6 PER DETAIL 3/C38
  - 3 INSTALL 42" FL x FL KNIFE GATE VALVE
  - 4 INSTALL COMBINATION ANTI-SIPHON AND AIR RELIEF VALVE PER DETAIL 3/C35
  - 5 INSTALL ANTI-SIPHON VAULT PER DETAIL 1/C9
  - 6 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 7 CONNECT TO EXISTING STEEL COUPLING
  - 8 RECONSTRUCT LEVEE EMBANKMENT WITH LEVEE FILL MATERIAL PER DETAIL 2/C38
  - 9 INSTALL RSP PER DETAIL 1/C35
  - 10 REPLACE EXISTING AGGREGATE SURFACE COURSE PER DETAIL 4/C37
  - 11 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

<b>BENCH MARK</b>	ELEV. 46.60
DESCRIPTION:	SPINDLE

<b>FIELD BOOK</b>	0000
SCALE:	1"=10"
H:	1"=10"
V:	1"=5"

**CITY OF SACRAMENTO  
DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21



IMPROVEMENT PLANS FOR:

**PUMP OUTFALLS REPLACEMENT PROJECT - A**



**SUMP 151**

**PLAN AND PROFILE 1 - 30" WSP**


Page 14

PN: W14130615	DWG. NO. C3
	SHEET 6 OF 47

65% SUBMITTAL



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 30" WSP AND APPURTENANCES FROM STA -0+66.5 TO STA 0+70.4 PER DETAIL 2/C38
  - 2 INSTALL 30" WSP FROM STA -0+66.5 TO STA 0+70.4 PER DETAIL 3/C38
  - 3 INSTALL 42" FL x FL KNIFE GATE VALVE
  - 4 INSTALL COMBINATION ANTI-SIPHON AND AIR RELIEF VALVE PER DETAIL 3/C35
  - 5 INSTALL ANTI-SIPHON VAULT PER DETAIL 1/C9
  - 6 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 7 CONNECT TO EXISTING STEEL COUPLING
  - 8 RECONSTRUCT LEVEE EMBANKMENT WITH LEVEE FILL MATERIAL PER DETAIL 2/C38
  - 9 INSTALL RSP PER DETAIL 1/C35
  - 10 REPLACE EXISTING AGGREGATE SURFACE COURSE PER DETAIL 4/C37
  - 11 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

<b>BENCH MARK</b>	ELEV. 46.60
DESCRIPTION:	SPINDLE

<b>FIELD BOOK</b>	0000
SCALE:	1" = 10'
H:	1" = 10'
V:	1" = 5'

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21





IMPROVEMENT PLANS FOR:


**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 151**  
**PLAN AND PROFILE 2 - 30" WSP**

65% SUBMITTAL

PN: W14130615	DWG. NO. C4
	SHEET 7 OF 47
	Page 15



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 16" WSP AND APPURTENANCES FROM STA -0+64.2 TO STA 0+80.1 PER DETAIL 2/C38
  - 2 INSTALL 16" WSP FROM STA -0+64.2 TO STA 0+80.1 PER DETAIL 3/C38
  - 3 INSTALL 42" FL x FL KNIFE GATE VALVE
  - 4 INSTALL COMBINATION ANTI-SIPHON AND AIR RELIEF VALVE PER DETAIL 3/C35
  - 5 INSTALL ANTI-SIPHON VAULT PER DETAIL 1/C9
  - 6 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 7 CONNECT TO EXISTING STEEL COUPLING
  - 8 RECONSTRUCT LEVEE EMBANKMENT WITH LEVEE FILL MATERIAL PER DETAIL 2/C38
  - 9 INSTALL RSP PER DETAIL 1/C35
  - 10 REPLACE EXISTING AGGREGATE SURFACE COURSE PER DETAIL 4/C37
  - 11 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

<b>BENCH MARK</b>	ELEV. 46.60
DESCRIPTION:	SPINDLE

<b>FIELD BOOK</b>	0000
SCALE:	1" = 10'
H:	1" = 10'
V:	1" = 5'

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21



65% SUBMITTAL



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 151**  
**PLAN AND PROFILE 3 - 16" WSP**

Page 16


DWG. NO.	C5
SHEET	8
OF	47

PN: W14130615





- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 42" WSP AND APPURTENANCES FROM STA -0+63.3 TO STA 0+78.9 PER DETAIL 2/C38
  - 2 INSTALL 42" WSP FROM STA -0+63.3 TO STA 0+78.9 PER DETAIL 3/C38
  - 3 INSTALL 42" FL x FL KNIFE GATE VALVE
  - 4 INSTALL COMBINATION ANTI-SIPHON AND AIR RELIEF VALVE PER DETAIL 3/C35
  - 5 INSTALL ANTI-SIPHON VAULT PER DETAIL 1/C9
  - 6 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 7 CONNECT TO EXISTING STEEL COUPLING
  - 8 RECONSTRUCT LEVEE EMBANKMENT WITH LEVEE FILL MATERIAL PER DETAIL 2/C38
  - 9 INSTALL RSP PER DETAIL 1/C35
  - 10 REPLACE EXISTING AGGREGATE SURFACE COURSE PER DETAIL 4/C37
  - 11 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

<b>BENCH MARK</b>	ELEV. 46.60
DESCRIPTION:	SPINDLE

<b>FIELD BOOK</b>	0000
SCALE:	1"=10"
H:	1"=10"
V:	1"=5"

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21





IMPROVEMENT PLANS FOR:

**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 151**  
**PLAN AND PROFILE 4 - 42" WSP**


Page 17

<b>65% SUBMITTAL</b>
DWG. NO. c6
SHEET 9 OF 47

PN: W14130615



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 54" WSP AND APPURTENANCES FROM STA -0+62.2 TO STA 0+80.0 PER DETAIL 2/C38
  - 2 INSTALL 54" WSP FROM STA -0+62.2 TO STA 0+80.0 PER DETAIL 3/C38
  - 3 INSTALL 42" FL x FL KNIFE GATE VALVE
  - 4 INSTALL COMBINATION ANTI-SIPHON AND AIR RELIEF VALVE PER DETAIL 3/C35
  - 5 INSTALL ANTI-SIPHON VAULT PER DETAIL 1/C9
  - 6 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 7 CONNECT TO EXISTING STEEL COUPLING
  - 8 RECONSTRUCT LEVEE EMBANKMENT WITH LEVEE FILL MATERIAL PER DETAIL 2/C38
  - 9 INSTALL RSP PER DETAIL 1/C35
  - 10 REPLACE EXISTING AGGREGATE SURFACE COURSE PER DETAIL 4/C37
  - 11 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	46.60
DESCRIPTION:	SPINDLE	

FIELD BOOK	0000
SCALE:	1" = 10'
H:	1" = 10'
V:	1" = 5'

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21





IMPROVEMENT PLANS FOR:

**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 151**  
**PLAN AND PROFILE 5 - 54" WSP**


65% SUBMITTAL

PN: W14130615	DWG. NO. c7
	SHEET 10 OF 47

Page 18



- NOTES:**
- REMOVE AND DISPOSE OF EXISTING 42" WSP AND APPURTENANCES FROM STA -0+73.4 TO STA 0+69.4 PER DETAIL 2/C38
  - INSTALL 42" WSP FROM STA -0+73.4 TO STA 0+69.4 PER DETAIL 3/C38
  - INSTALL 42" FL x FL KNIFE GATE VALVE
  - INSTALL COMBINATION ANTI-SIPHON AND AIR RELIEF VALVE PER DETAIL 3/C35
  - INSTALL ANTI-SIPHON VAULT PER DETAIL 1/C9
  - CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - CONNECT TO EXISTING STEEL COUPLING
  - RECONSTRUCT LEVEE EMBANKMENT WITH LEVEE FILL MATERIAL PER DETAIL 2/C38
  - INSTALL RSP PER DETAIL 1/C35
  - REPLACE EXISTING AGGREGATE SURFACE COURSE PER DETAIL 4/C37
  - LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

<b>BENCH MARK</b>	ELEV. 46.60
DESCRIPTION:	SPINDLE

<b>FIELD BOOK</b>	0000
SCALE:	1"=10"
H:	1"=10"
V:	1"=5"

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21




IMPROVEMENT PLANS FOR:

**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 151**  
**PLAN AND PROFILE 6 - 42" WSP**

65% SUBMITTAL

PN: W14130615	DWG. NO. c8
	SHEET 11 OF 47

Page 19



- NOTES:
1. CUT 60"x7" OPENING IN FIXED ALUMINUM GRATING FOR 54" KNIFE GATE VALVE.
  2. CUT 48"x7" OPENING IN FIXED ALUMINUM GRATING FOR 42" KNIFE GATE VALVE.
  3. CUT 36"x7" OPENING IN FIXED ALUMINUM GRATING FOR 30" KNIFE GATE VALVE.
  4. CUT 22"x7" OPENING IN FIXED ALUMINUM GRATING FOR 16" KNIFE GATE VALVE.

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV. _____
DESCRIPTION:	

FIELD BOOK	0000
SCALE:	1"=10'
H:	
V:	

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 151**  
**VAULT DETAIL**


65% SUBMITTAL

Page 20


DWG. NO. C9	SHEET 12 OF 47
-------------	----------------

PN: W14130615

PN: W14130615




**SUMP 155 ANTI SIPHON VAULT DETAIL (1)**  
NTS




NOTE: PIPE SUPPORT TO BE STANDON S92 OR APPROVED EQUAL

**PIPE SUPPORT (2)**  
NTS



**SECTION (B)**  
NTS




**PLAN VIEW**

**LIFTING EYE DETAIL**

**TYPICAL ANTI-SIPHON VALVE SIZE**

D1	D2	D3	S	MODEL
16"	12"	10"	3"	HSB-03-A-16
18"	16"	12"	3"	HSB-03-A-18
30"	24"	20"	7"	HSB-07-B-30
36"	30"	24"	5"	HSB-05-A-36
42"	30"	24"	8"	HSB-08-B-42
54"	30"	24"	8"	HSB-08-B-54



**PROFILE VIEW**

**SECTION VIEW**

**WELD DETAIL (4)**  
NTS

**WELD DETAIL (5)**  
NTS

**ANTI-SIPHON AND AIR RELIEF VALVE CONNECTION DETAIL (3)**  
NTS

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.

FIELD BOOK <b>0000</b>	SCALE: 1" = 1'
H: _____	ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"
V: _____	

**CITY OF SACRAMENTO  
DEPARTMENT OF UTILITIES**

DRAWN BY: E. TUTEJA      DESIGNED BY: B. JENSEN      CHECKED BY: A. SMITH  
 DATE: 09/15/20      R.C.E. NO. C90949      DATE: 03/31/22      R.C.E. NO. C86512      DATE: 03/31/21








IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**ANTI SIPHON AND VALVE VAULT**  
**SECTION AND DETAILS**

65% SUBMITTAL

PN: W14130615	DWG. NO. C35
	SHEET 38 OF 47
	Page 21

**GENERAL NOTES:**

1. LINE POSTS SHALL BE MIN 2½" O.D. SPACED AT MAX 10' O.C.
2. HORIZONTAL BRACE AND TOP RAIL SIZE SHALL BE MIN 1½" DIA.
3. END, CORNER, AND GATE POSTS SHALL BE MIN 2½" O.D. WITH 1½" O.D. BRACE RAIL, ¾" TRUSS ASSEMBLY, 12-GAUGE TENSION BANDS SECURED AT MAX 12" O.C.
4. GATE FRAME SHALL BE FABRICATED FROM 2½" O.D. OR 2½" SQUARE MEMBERS WELDED AT ALL CORNERS.
5. CHAIN LINK FABRIC SHALL BE SECURED TO LINE POST AND TOP RAIL USING 9-GAUGE TIE WIRE SPACED AT MAX 12" O.C.
6. 2-3/8" SHOULDERED EYE BOLT 3" LENGTH TO ANCHOR TENSION WIRE PER 10' SECTION EVENLY SPACED, SECURED WITH HOG RING CAPTURING FENCE FABRIC AND TENSION WIRE TO MAINTAIN DOWNWARD TENSION ON SECURITY FENCE SYSTEM.
7. PROVIDE "CITY UTILITY FACILITY - NO TRESPASSING" SIGNAGE GATE.



**8 FOOT HIGH CHAIN LINK FABRIC WITH ANGLED OUTRIGGER AND 3 STRAND BARB WIRE (OUTSIDE) STANDARD FENCING DETAIL**

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK DESCRIPTION:	ELEV. _____
-------------------------	-------------

FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"	

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	




65% SUBMITTAL


IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**

**MISCELLANEOUS VAULT SECURITY DETAILS** Page 22

PN: W14130615	DWG. NO. C36
SHEET 39 OF 47	




OUTFALL STRUCTURE CONNECTION DETAIL **1**  
NTS



NOTES:  
1. PROVIDE HAND HOLES AS NEEDED TO INSTALL FIELD LINING. WELD HAND HOLE CLOSED WHEN COMPLETE. HAND HOLES NOT REQUIRED AT OUTLETS IF ACCESSIBLE THROUGH FLAP GATE.

NEW OR EXISTING STEEL  
PIPE CONNECTION DETAIL **2**  
NTS



TRENCH SECTION AND SEQUENCING **3**  
NTS

NOTES:


- CONTRACTOR SHALL REPLACE EXISTING PAVEMENT IN KIND. BASED ON LIMITED FIELD INVESTIGATIONS, EXISTING PAVEMENT SECTION ARE ASSUMED 2" AC ON 6" AB
- THE OWNER AND THE CONTRACTOR SHALL JOINTLY DETERMINE THE FINAL WIDTH AND LENGTH OF THE BIKE PATH CROSSING BASED ON FIELD CONDITIONS AND CONSTRUCTION PROCEDURES.
- CONTRACTOR SHALL REMOVE EXISTING BIKE PATH AS NEEDED TO CONSTRUCT PROPOSED PIPE. IMPACTED AREAS SHALL BE REPLACED IN ACCORDANCE WITH CITY OF SACRAMENTO STANDARD DETAIL T-21

CONSTRUCTION SEQUENCE:

- STEP 1: SAWCUT LIMITS 09F TRENCH EXCAVATION TO CLEAN CUT LIMITS. REMOVE EXISTING ASPHALT CONCRETE TO THE MIN EXTENT REQUIRED TO CONSTRUCT PROPOSED PIPE. PROPOSED PIPE SHALL BE CONSTRUCTED A MIN OF 2' FROM FG. TRENCH PLATES SHALL BE PROVIDED TO MAINTAIN ACCESS OVER CUTOFF WALL DURING CONSTRUCTION IN ACCORDANCE WITH THE SPECIFICATIONS.
- STEP 2: PLACE AB TO MATCH EXISTING THICKNESS. PLACE AC OVERLAY FROM EXTENT APPROVED BY AGENCY AND CONTRACTOR TO LIMITS OF SAWCUT. PROVIDE PAVEMENT MARKING AND STRIPING TO MATCH EXISTING.

LEGEND:

EXISTING	PROPOSED
GRIND AND OVERLAY ASPHALT CONCRETE	
AGGREGATE BASE (AB)	
ASPHALT CONCRETE (AC)	



CROWN SURFACING DETAIL **4**  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.
DESCRIPTION:	

FIELD BOOK
0000
SCALE:
1"

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

CITY OF SACRAMENTO DEPARTMENT OF UTILITIES			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	




IMPROVEMENT PLANS FOR:  
PUMP OUTFALLS REPLACEMENT PROJECT - A  
MISCELLANEOUS DETAILS I

65% SUBMITTAL

DWG. NO.
C37
SHEET
40
OF
47


PN: W14130615




TYPICAL SLOPE BENCHING NOTES:

1. PLACE FILL IN HORIZONTAL LIFTS AGAINST VERTICAL FACES CUT INTO EXISTING LEVEE MATERIAL.
2. THE BOTTOM OF THE KEY TRENCH SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES AND RECOMPACTED TO 95% MAX DENSITY PER ASTM D698.

SLOPE BENCHING (LANDSIDE OR WATERSIDE) DETAIL 1  
NTS



TYPICAL REMOVAL OF EXISTING PIPE DETAIL 2  
NTS



INSTALLATION OF NEW PIPE DETAIL 3  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615


REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.
DESCRIPTION:	

FIELD BOOK	0000
SCALE:	1" = 1'
H:	
V:	

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

<b>CITY OF SACRAMENTO</b> DEPARTMENT OF UTILITIES			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
MISCELLANEOUS DETAILS II

65% SUBMITTAL

PN: W14130615	DWG. NO. C38
	SHEET 41 OF 47
	Page 24

PN: W14130615





POST-INSTALLED ANCHORS:

- 1. ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS GIVEN IN THE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS (MPI) AND THE RESPECTIVE ICC OR IFPMO REPORT.
A. CONCRETE ANCHORS:
HILTI KWIK-BOLT TZ EXPANSION ANCHORS . . . . . ESR-1917
HILTI HIT-RE 500 V3 ADHESIVE ANCHORS . . . . . ESR-3814
2. SPECIAL INSPECTION IS REQUIRED FOR ALL MECHANICAL AND ADHESIVE ANCHORS PER CBC SECTION 1705.3 AND THE REPORTS NOTED ABOVE, UNLESS NOTED OTHERWISE.
3. SEE ANCHOR SCHEDULE(S) AND DETAILS FOR TEST LOAD OR TORQUE VALUES, IN ACCORDANCE WITH CBC SECTION 1901.3.4.4. TESTING OF UNDERCUT ANCHORS THAT ALLOW VISUAL CONFIRMATION OF FULL SET IS NOT REQUIRED.
4. TEST EACH ANCHOR OF DIFFERENT DIAMETER AND EMBEDMENT DEPTH FOR EACH TYPE AND STRENGTH OF CONCRETE PER CBC SECTION 1901.3.4.3 AS FOLLOWS:
A. ANCHORS USED FOR OTHER STRUCTURAL APPLICATIONS SHALL HAVE 100 PERCENT OF THE ANCHORS TENSION TESTED.
B. ANCHORS USED FOR NON-STRUCTURAL APPLICATIONS SUCH AS EQUIPMENT ANCHORAGE SHALL HAVE 50 PERCENT OR ALTERNATE BOLTS IN A GROUP INCLUDING AT LEAST ONE-HALF THE ANCHORS IN EACH GROUP TENSION TESTED.
5. FAILURE/ACCEPTANCE CRITERIA. THE FOLLOWING CRITERIA APPLY FOR THE ACCEPTANCE OF INSTALLED ANCHORS PER CBC SECTION 1901.3.4.5:
A. HYDRAULIC RAM METHOD: THE ANCHOR MUST MAINTAIN THE TEST LOAD FOR 15 SECONDS AND NOT EXHIBIT OBSERVABLE MOVEMENT AT THE APPLICABLE TEST LOAD. FOR WEDGE AND SLEEVE-TYPE ANCHORS, A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER UNDER THE NUT BECOMES LOOSE. DROP-IN ANCHORS ARE ONLY TO BE TESTED WITH THIS METHOD. FOR ADHESIVE ANCHORS, WHERE OTHER THAN BOND IS BEING TESTED, THE TESTING DEVICE SHALL NOT RESTRICT THE CONCRETE SHEAR CONE TYPE FAILURE MECHANISM FROM OCCURRING.
B. TORQUE WRENCH METHOD: THE APPLICABLE TEST TORQUE FOR WEDGE OR SLEEVE-TYPE ANCHORS MUST BE REACHED WITHIN THE FOLLOWING LIMITS, ONE-HALF (1/2) TURN OF THE NUT; ONE QUARTER (1/4) TURN OF THE NUT FOR THE 3/8" SLEEVE ANCHOR ONLY.
C. PER CBC SECTION 1901.3.4.1 IF ANCHOR FAILS TESTING, ALL ANCHORS OF THE SAME CATEGORY, NOT PREVIOUSLY TESTED, SHALL BE TESTED UNTIL 20 CONSECUTIVE ANCHORS PASS THE TEST REQUIREMENTS THEN INITIAL TESTING FREQUENCY SHALL THEN BE RESUMED.
6. WHEN INSTALLING DRILLED-IN ANCHORS IN EXISTING CONCRETE, USE CARE AND CAUTION TO AVOID CUTTING OR DAMAGING EXISTING REINFORCING BARS.
7. THE TESTING OF THE ANCHORS SHALL BE DONE BY THE TESTING LABORATORY IN THE PRESENCE OF THE SPECIAL INSPECTOR AND A REPORT OF THE TEST RESULTS SHALL BE SUBMITTED TO THE GOVERNING AGENCY AND ARCHITECT/STRUCTURAL ENGINEER. TESTING SHALL OCCUR AT MINIMUM OF 24 HOURS AFTER THE INSTALLATION OF THE ANCHORS.
8. APPLY TENSION TEST LOADS TO EXPANSION OR ADHESIVE ANCHORS WITHOUT REMOVING THE NUT IF POSSIBLE. IF NOT POSSIBLE, REPLACE THE NUT WITH A THREADED COUPLER OF THE SAME DIAMETER AND TORQUE TO THE SAME LEVEL AS THE ORIGINAL NUT AND APPLY TEST LOAD.
9. REACTION LOADS FROM TEST FIXTURES SHALL NOT BE APPLIED CLOSE TO THE ANCHOR BEING TESTED.
10. TEST EQUIPMENT IS TO BE CALIBRATED BY AN APPROVED TESTING LABORATORY IN ACCORDANCE WITH STANDARD RECOGNIZED PROCEDURES.


CONCRETE:

- 1. CONCRETE CONSTRUCTION SHALL CONFORM TO THE CODE PER GENERAL NOTES.
2. CONCRETE SHALL BE PLACED IN ACCORDANCE WITH ASTM C94 AND ACI STANDARD 304. IN ADDITION, MAXIMUM FREE FALL OF CONCRETE SHALL BE 4'-0".
3. ALL CONCRETE SHALL BE THOROUGHLY CONSOLIDATED BY SUITABLE MEANS DURING PLACEMENT AND SHALL BE THOROUGHLY WORKED AROUND REINFORCEMENT AND EMBEDDED FIXTURES AND INTO CORNERS OF FORMS.
4. THE MINIMUM 28 DAY STRENGTH SHALL BE PER MIX DESIGN SCHEDULE.
5. CEMENT SHALL CONFORM TO ASTM C150, TYPE I OR II.
6. CONCRETE AGGREGATES:
A. NATURAL SAND AND ROCK AGGREGATES SHALL CONFORM TO ASTM C33.
B. LIGHTWEIGHT AGGREGATES SHALL CONFORM TO ASTM C330.
7. MINERAL ADMIXTURES SHALL COMPLY WITH ASTM C618 CLASS F.
8. LIQUID ADMIXTURES SHALL COMPLY WITH THE FOLLOWING:
A. WATER REDUCERS . . . . . ASTM C494 TYPE A
B. MID-RANGE WATER REDUCERS . . . . . ASTM C494 TYPE A & F
C. NON-CHLORIDE ACCELERATORS . . . . . ASTM C494 TYPE C OR C & E
D. RETARDING ADMIXTURES . . . . . ASTM C494 TYPE B OR B & D
9. GENERAL:
A. NO PIPES OR DUCT SHALL BE PLACED IN CONCRETE SLABS OR WALLS UNLESS SPECIFICALLY DETAILED.
B. REFER TO ARCHITECTURAL, STRUCTURAL AND MECHANICAL DRAWINGS FOR ALL MOULDS, GROOVES, ORNAMENTS, CLIPS, ETC. TO BE CAST IN CONCRETE.
10. ALL CONSTRUCTION JOINTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH ACI 318 SECTION 26.5.6 AND THE TYPICAL CONSTRUCTION JOINT DETAILS SHOWN ON THE STRUCTURAL DRAWINGS. ALL SURFACES OF CONSTRUCTION JOINTS SHALL BE CLEANED TO REMOVE DUST, CHIPS, OR OTHER FOREIGN MATTER PRIOR TO PLACING THE ADJACENT CONCRETE. THE CONTRACTOR SHALL SUBMIT THE PROPOSED LOCATIONS OF CONSTRUCTION JOINTS TO THE ENGINEER FOR REVIEW BY THE STRUCTURAL ENGINEER BEFORE STARTING CONSTRUCTION.
11. REMOVE ALL DEBRIS AND EXCESS WATER FROM THE FORMS BEFORE PLACING ANY CONCRETE.
12. REINFORCING, DOWELS, BOLTS, ANCHORS, SLEEVES, ETC. TO BE EMBEDDED IN CONCRETE SHALL BE SECURELY POSITIONED AND FREE OF EXCESSIVE SCALE, RUST, DIRT, GREASE, OIL OR ANY OTHER SUBSTANCES THAT WILL IMPAIR BOND WITH CONCRETE. OBTAIN APPROVAL OF ALL AFFECTED TRADES PRIOR TO PLACING CONCRETE.
13. WALLS SHALL BE PLACED IN HORIZONTAL LAYERS OF 2'-0" MAXIMUM DEPTH.
14. CONCRETE IN WALLS, PIERS OR COLUMNS SHALL SET AT LEAST 2 HOURS BEFORE PLACING CONCRETE IN BEAMS, SPANDRELS OR SLABS SUPPORTED THEREON.
15. NO WOOD SPREADERS ALLOWED. NO WOOD STAKES ALLOWED IN AREAS TO BE CONCRETED.
16. CONTRACTOR SHALL PREPARE AND SUBMIT CONCRETE MIX DESIGNS TO THE ARCHITECT/ENGINEER OF RECORD FOR REVIEW PRIOR TO PLACEMENT OF ANY CONCRETE. CONCRETE MIX DESIGNS SHALL BE PER ACI 318 CHAPTER 26 AND ACI 301 SECTION 4. CALCIUM CHLORIDE OR ADMIXTURES WHICH ADD CHLORIDES ARE NOT PERMITTED.
17. NOTIFY THE ENGINEER OF RECORD (AND BUILDING OFFICIAL WHEN REQUIRED) 2 BUSINESS DAYS PRIOR TO PLACING CONCRETE.
18. CAST-IN-PLACE CONCRETE (NON-PRESTRESSED). THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCEMENT:
A. CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH . . . . . 3"
B. CONCRETE EXPOSED TO EARTH OR WEATHER:
NO. 6 THROUGH NO. 11 BAR . . . . . 2"
NO. 5 BAR, W31 OR D31 WIRE, AND SMALLER . . . . . 1 1/2"

- 19. A. ALL BARS SHALL HAVE A CLASS B MINIMUM SPLICE LAP UNO. SEE REINFORCEMENT LAP SPLICES TABLE.
B. SPLICES IN ADJACENT BARS SHALL BE NOT LESS THAN 5'-0" APART. UNO.
C. DOWEL ALL VERTICAL REINFORCING IN WALLS AND COLUMNS FROM FOUNDATION WITH THE SAME SIZE REINFORCING, UNO.
D. SPLICE CONTINUOUS BARS IN SPANDRELS, GRADE BEAMS, WALL BEAMS, ETC. AS FOLLOWS: TOP BARS AT MID-SPAN, BOTTOM BARS AT CENTERLINE SUPPORT UNO.
20. HORIZONTAL WALL REINFORCING IN DOUBLE LAYER WALLS SHALL BE STAGGERED. USE #2 SPREADERS APPROXIMATELY EVERY THIRD INTERSECTION EACH DIRECTION FOR ALL DOUBLE LAYER WALLS.
21. MINIMUM WALL REINFORCING SHALL BE:
WALL THICKNESS SINGLE LAYER DOUBLE LAYER
7" OR LESS . . . #4 @ 12" OC EA WAY
8" . . . . . #4 @ 10" OC EA WAY
9" & 10" . . . . . #4 @ 12" OC EA WAY
11" & 12" . . . . . #4 @ 12" OC EA WAY
22. REINFORCING STEEL SHALL BE DETAILED, FABRICATED AND INSTALLED IN ACCORDANCE WITH ACI 315. SEE REINFORCING STEEL NOTES FOR ADDITIONAL REQUIREMENTS.
23. FINAL PRODUCT AS INDICATED ON DRAWINGS SHALL COMPLY WITH THE FOLLOWING:
A. ALL CONCRETE SHALL HAVE A "CLASS B" FINISH PER ACI 347 WITH GRADUAL IRREGULARITIES LIMITED TO 1/4" IN 5'-0" AS MEASURED WITH A STRAIGHT EDGE.
B. SURFACE IRREGULARITIES ATTRIBUTABLE TO PLACEMENT AND CONSOLIDATION DEFICIENCIES AS DEFINED IN ACI 309.2R (E.G., BUG HOLES, HONEYCOMB, ETC.) WILL BE REVIEWED BY THE ARCHITECT AND ENGINEER. UNSATISFACTORY WORK SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
C. GRADUAL SURFACE IRREGULARITIES SHALL NOT BE CUMULATIVE.

MIX DESIGN SCHEDULE table with columns: TYPE, USE CLASS, STRENGTH (f'c) MIN @ 28 DAYS (PSI), CONCRETE UNIT WEIGHT (PCF), MAX AGGREGATE SIZE (IN), MAX SLUMP (IN), MAX WATER TO CEMENT RATIO (%), FLY ASH (%) REPLACEMENT (%). Rows include SLAB ON GRADE, FOUNDATIONS, WALLS, and ELEVATED SLABS.

- FOOTNOTES:
1. ADD WATER REDUCING ADMIXTURES PER SPECIFICATIONS FOR PLACING.
2. FOR HOT WEATHER CONCRETING REFER TO ACI 305R.
3. FOR COLD WEATHER CONCRETING REFER TO ACI 306R.
4. OTHER ADMIXTURES SHALL BE REVIEWED BY THE ENGINEER OF RECORD AND TESTING LABORATORY UPON CONCRETE MIX DESIGN SUBMITTAL.
5. SLUMPS SHALL NOT EXCEED 8"±1 1/2" WHEN USING MID-RANGE WATER REDUCERS. ADDITIONAL WATER SHALL NOT BE ADDED TO THE CONCRETE ONCE THE TRUCK LEAVES THE BATCH PLANT.
6. MIX DESIGN SHALL NOT BE PROPORTIONED WITHOUT FIELD EXPERIENCE OR TRIAL MIXTURES PER ACI 318, SECTION 26.4.3 WHEN USING MORE THAN 15% FLY ASH REPLACEMENT BY WEIGHT.




HILTI KB-TZ EXPANSION ANCHORS (ICC-ES ESR-1917) table with columns: ANCHOR DIA (INCH), INSTALLATION EMBED (INCH) hnom, EFFECTIVE EMBED (INCH) hef, HOLE DEPTH (INCH) ho, MIN CONC THICKNESS (INCH) h, MIN CONC EDGE DISTANCE (INCH), INSTALLATION TORQUE (FT-LBS).

HILTI HIT-RE 500 V3 ADHESIVE ANCHORS (ICC-ES ESR-3814) table with columns: ANCHOR DIA (INCH), EFFECTIVE EMBED (INCH) hef, MIN CONC THICKNESS (INCH) h, MIN CONC EDGE DISTANCE (INCH).

SHOP DRAWINGS:

PRIOR TO FABRICATION, SHOP DRAWINGS SHALL BE SUBMITTED FOR REVIEW BY THE STRUCTURAL ENGINEER:

- 1. THE CONTRACTOR AGREES THAT SHOP DRAWING SUBMITTALS PROCESSED BY THE ENGINEER ARE NOT CHANGE ORDERS.
2. THE CONTRACTOR AGREES THAT THE PURPOSE OF SHOP DRAWING SUBMITTALS IS TO DEMONSTRATE TO THE ENGINEER THAT THE CONTRACTOR UNDERSTANDS THE DESIGN INTENT OF THE PROJECT AND COMPLIANCE WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS BY INDICATING WHICH MATERIAL THE CONTRACTOR INTENDS TO FURNISH AND INSTALL AND BY DETAILING THE FABRICATION AND INSTALLATION METHODS THE CONTRACTOR INTENDS TO USE.
3. THE CONTRACTOR IS RESPONSIBLE FOR DIMENSIONS ON THE SHOP DRAWINGS, WHICH MUST BE CONFIRMED AND CORRELATED AT THE JOB SITE, FOR COORDINATION OF HIS OR HER WORK WITH THAT OF ALL OTHER TRADES AND FOR PERFORMING WORK IN A SAFE AND SATISFACTORY MANNER.
4. THE CONTRACTOR IS RESPONSIBLE FOR MATERIAL QUANTITIES ON THE SHOP DRAWINGS.
5. THE CONTRACTOR IS TO REVIEW AND BE IN AGREEMENT WITH COMMENTS BY THE STRUCTURAL ENGINEER PRIOR TO PROCEEDING WITH FABRICATION.
6. THE SHOP DRAWINGS SHALL BE PREPARED FROM FRESH WORK. REPRODUCTIONS OF THE APPROVED DRAWINGS IS NOT PERMITTED.
7. PRIOR TO SUBMISSION THE CONTRACTOR SHALL REVIEW ALL SUBMITTALS FOR CONFORMANCE WITH THE CONTRACT DOCUMENTS AND SHALL STAMP SUBMITTALS AS BEING "REVIEWED FOR CONFORMANCE".
8. ANY DETAIL ON THE SHOP DRAWING THAT DEVIATES FROM THE CONTRACT DOCUMENTS SHALL BE CLEARLY MARKED WITH THE NOTE "THIS IS A CHANGE". SEE GENERAL NOTES FOR MATERIAL SUBSTITUTIONS.
9. SHOP DRAWINGS OR CALCULATIONS SUBMITTED FOR REVIEW THAT REQUIRE MORE THAN ONE RESUBMITTAL FOR REVIEW SHALL BE BILLED HOURLY FOR SUCH TIME TO THE GENERAL CONTRACTOR. THE THIRD REVIEW WILL NOT PROCEED WITHOUT WRITTEN APPROVAL FROM THE GENERAL CONTRACTOR FOR ADDITIONAL ENGINEERING REVIEW SERVICES.
10. CAD FILES OF APPROVED DRAWINGS WILL NOT BE PROVIDED TO THE CONTRACTOR, SUBCONTRACTOR OR FABRICATOR FOR THE PREPARATION OF SHOP DRAWINGS.
11. SHOP DRAWING REVIEWS DO NOT CONSTITUTE AN APPROVAL FOR PURCHASE OR FABRICATION OF MATERIALS.



POST INSTALLED ANCHOR SCHED

2

PUMP OUTFALLS REPLACEMENT PROJECT
PN: W14130615

REVISIONS table with columns: NO., DESCRIPTION, DATE, BY.

BENCH MARK table with columns: DESCRIPTION, ELEV.

FIELD BOOK table with columns: 0000, SCALE.

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

CITY OF SACRAMENTO DEPARTMENT OF UTILITIES. Includes project name, date (09/15/20), and names of staff (E. TUTEJA, B. JENSEN, A. SMITH).








PRELIMINARY

PUMP OUTFALLS REPLACEMENT PROJECT - A GENERAL STRUCTURAL NOTES & TYPICAL DETAILS. Includes project details and page number (Page 26).

CYS STRUCTURAL ENGINEERS INC. logo and professional seal information.

65% SUBMITTAL

DWG. NO. s2 SHEET 43 OF 47



L:\Jobs\2020\054 Pump Outfall Replacement Valve Vault\ACAD\STRU\PKG AIS3\_PKG A.dwg Time:Sep14, 2020-02:00pm LogIn:uzamachom DimScale:1 LTScale:8

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.

FIELD BOOK	SCALE:
0000	ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"
H:	
V:	

**CITY OF SACRAMENTO  
DEPARTMENT OF UTILITIES**


DRAWN BY: E. TUTEJA      DESIGNED BY: B. JENSEN      CHECKED BY: A. SMITH  
 DATE: 09/15/20      R.C.E. NO. C90949      DATE: 03/31/22      R.C.E. NO. C86512      DATE: 03/31/21

**PRELIMINARY**

IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**TYPICAL DETAILS - CONCRETE**


DWG. NO.	SHEET	OF
53	44	47

Page 27




PN: W14130615

65% SUBMITTAL



SUMP 151  
TOP OF WALL PLAN  
3/8" = 1'-0"




SUMP 151  
FOUNDATION PLAN  
3/8" = 1'-0"

NOTES

- SEE DWG S1 & S2 FOR GENERAL NOTES.
- SEE DWG S3 FOR TYPICAL DETAILS.
- SEE DWG S5 FOR SECTIONS.
- SEE OTHER CONSULTANT DWGS FOR UTILITIES THAT WILL AFFECT FTGS & COMPLY W/ TYPICAL DETAILS.



THESE DRAWINGS ARE PRELIMINARY AND NOT FOR CONSTRUCTION UNLESS STAMPED & SIGNED BY THE ENGINEER OF RECORD.



CYS Job No. 20054

65% SUBMITTAL

L:\Jobs\2020054 Pump Outfall Replacement Valve Vault\ACAD\STRU\PKG AS4\_PKG A.dwg Time: Sep 14, 2020 04:45:10m LogIn: camachom DimScale: 32 LT Scale: 16

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK DESCRIPTION:	ELEV.

FIELD BOOK 0000	<p>ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"</p>
SCALE:	
H:	
V:	


<b>CITY OF SACRAMENTO DEPARTMENT OF UTILITIES</b>			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	

**PRELIMINARY**

IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**FOUNDATION & FRAMING PLANS**  
**SUMP 151**


PN: W14130615	DWG. NO.	54
	SHEET	45
	OF	47

L:\Jobs\2020\054 Pump Outfall Replacement Valve Vault\ACAD\STRUPKG ANS5\_PKG A.dwg Time: Sep 14, 2020 05:12pm Loghucamachom Dimscale: 12 LT Scale: 16  
 PUMP OUTFALLS REPLACEMENT PROJECT  
 PN: W14130615




**SUMP 151  
 REAR WALL ELEVATION**  
 A  
 S5 3/8" = 1'-0"

NOTE:  
TYP WALL REINF NOT SHOWN FOR CLARITY.




**SUMP 151  
 FRONT WALL ELEVATION**  
 B  
 S5 3/8" = 1'-0"

NOTE:  
TYP WALL REINF NOT SHOWN FOR CLARITY.



**WSP SECTION**  
 C  
 S5 3/8" = 1'-0"



**1'-0\"/>**



THESE DRAWINGS ARE PRELIMINARY AND NOT FOR CONSTRUCTION UNLESS STAMPED & SIGNED BY THE ENGINEER OF RECORD.

CYS Job No. 20054

65% SUBMITTAL

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.

FIELD BOOK 0000	SCALE: ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"
--------------------	---

<b>CITY OF SACRAMENTO DEPARTMENT OF UTILITIES</b>			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	


**PRELIMINARY**

IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**WALL ELEVATIONS & SECTIONS**  
**SUMP 151**


PN: W14130615	DWG. NO. S5
	SHEET 46
	OF 47
	Page 29

PN: W14130615


L:\Jobs\2020054 Pump Outfall Replacement Valve\AutoCAD\STRUPKG AISE\_PKG A.dwg Time: Sep 15, 2020 01:22pm Loghincamacom DimScale: 12 LT Scale: 6  
 PUMP OUTFALLS REPLACEMENT PROJECT  
 PN: W14130615



PLAN VIEW




PLAN VIEW




PARTIAL WALL ELEV BTW OPGS


3  
S6 3/4\"/>




1  
S6 3\"/>



PLAN VIEW  
TYP AT CORNERS




CONDITION B




SECTION A-A

(E) HANDRAIL PLATE REPLACEMENT  
FOR (N) FENCING POST  
DETAIL  
5  
S6 3\"/>




SECTION A-A




PLAN VIEW

(E) HANDRAIL PLATE REPLACEMENT  
FOR (N) FENCING GATE POST  
DETAIL  
6  
S6 3\"/>




SECTION A-A

4  
S6 3\"/>



SECTION B-B



2  
S6 1 1/2\"/>



THESE DRAWINGS ARE PRELIMINARY  
AND NOT FOR CONSTRUCTION  
UNLESS STAMPED & SIGNED BY  
THE ENGINEER OF RECORD.

CYS Job No. 20054

65% SUBMITTAL

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.

FIELD BOOK	SCALE:
0000	1"
H:	ON ORIGINAL SCALE
V:	DRAWING ADJUST
	SCALED DIMENSIONS
	IF THIS DOES NOT
	SCALE AT 1"

<b>CITY OF SACRAMENTO DEPARTMENT OF UTILITIES</b>		
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21

PRELIMINARY

IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**DETAILS**

PN: W14130615	DWG. NO.	S6
	SHEET	47
	OF	47

**Attachment C – Categorical Permission Checklist**

## Categorical Permission Alteration Description – 16. Pressurized Pipes

The categorical permission covers the installation, modification, and replacement of pressurized pipes that comply with certain terms and conditions. Particularly, all pressurized pipes must be designed and installed in accordance with current USACE standards. The total area of disturbance, including staging and access areas, must not exceed 5 acres. Pressurized pipes must also be designed to prevent, (1) flotation from uplift, (2) scour or erosion, (3) damage from debris on the waterside, particularly during flood flows, (4) leakage, (5) seepage along proposed pipes, (6) corrosion, and (7) damage from vehicular loads.

All new pressurized pipes should go up and over the levee DWSE. Pressurized pipes passing over or within the freeboard zone of a levee (i.e., above the levee DWSE), should be made of metal, preferably ductile iron or coated steel, suitable for use with flexible couplings.

Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM). Pipes that pass above the DWSE must have 2 feet of cover (low permeability or CLSM) to prevent damage by vehicles and equipment. Cover material on the levee crown must be placed at a ratio of 10H:1V, in the upstream/downstream direction of the levee. Pipes on the sides of the levee should be covered with a minimum of 1 foot of low permeability material, compacted in 4- to 6-inch lifts or CLSM to protect them from debris during high water (waterside) or to keep them from interfering with or being damaged by operations or maintenance of the levee (landside). Fill must be free of deleterious materials and construction debris and placed in 4- to 6-inch-thick loose lifts and compacted to not less than 95% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D698 (USACE preferred method), or alternately, 90% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D1557. At the sponsor and levee maintaining agency's discretion, pipes on the levee slopes may be left exposed.

Only suitable material must be used as levee fill materials. Fill must be free from: roots and other organic matter, contaminated hazardous or toxic material, trash, debris, and frozen materials. Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve.

Pressurized pipes terminating in the channel require a positive closure device on the waterside that is accessible from the levee crown. Pressurized pipes transporting product completely across or through the federal project easement require positive closure devices located landward of any levees and channel. The positive closure device shall be located within one mile on both sides of the federal project. If the invert of the pipe is over the levee crown, the combination of a pump station on the waterside and a siphon breaker is considered an appropriate means of closure. Pipes located within or beneath a levee must have watertight joints that can accommodate movements resulting from settlement.

All pressurized pipes that cross the levee foundation at a depth less than or equal to two times the height of the levee should be evaluated for uplift. Pipes crossing the surface of the levee must be designed to counteract buoyancy forces of an empty pipe, with water at the DWSE.



Pressurized pipelines running parallel to flood risk management projects should be located at least 15 feet beyond the levee toes. Pipe location and orientation must be clearly marked in the field so they can be easily identified for flood fighting crews.

If appropriate, the requester should prepare an excavation plan demonstrating the effects of excavation on the stability of the embankments.

The site layout should provide adequate access for maintenance vehicles to refill fuel tanks and service/replace pumps, generators, etc. Pressurized pipes must also allow easy access for rapid closure in the event of leakage or rupture.

No plastic pipes (HDPE, PVC, etc.) are allowed in the levee embankment or its foundation unless they are embedded in concrete.

If an electrochemical or chemical reaction between the substratum or groundwater and pipe materials is expected, the pipe and pipe couplings must be protected.

After installation of pressurized pipes, the requester must demonstrate 0% pipe leakage in pipes in the levee. Pipes must be pressure tested to industry standards. Pipes must be regularly inspected, including the interior, if possible, looking for signs of maintenance issues. If an inspection indicates corrosion, alignment sag or heave, or separation at joints, corrective action must be taken as soon as possible to avoid failure. Pipe valves must be periodically inspected and pressure tested to ensure that they are functioning properly. Pressure tests must show no significant loss in pressure. Leaks and other deficiencies must be addressed as soon as possible. All replacement parts must be of equivalent or better quality than those being replaced.

The preferred method for abandoning pipes that pass through or over a levee is complete removal. If removal is not feasible, the pipes and other structures may be filled with a cement/bentonite-based grout or flowable fill. The grout needs to be sufficiently fluid so that it can be pumped to completely fill the pipe leaving no voids.

### Categorical Permission Alteration Checklist – 16. Pressurized Pipes

*Note:* The following checklist is intended for planning purposes only, and includes information that USACE reviewers look for when considering a Section 408 request for pressurized pipes under the Categorical Permission. To be reviewed under the Categorical Permission, the proposed project must adhere to all requirements of the Categorical Permission, including the full alteration description (see previous page). The plans and narrative project description should reflect this information.

1.	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Replacement	<input type="checkbox"/> Modification	<input type="checkbox"/> Authorize Existing
2.	Maximum total area of disturbance is 5 acres:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: <u>Area of disturbance is 0.11 acre.</u>			
3.	Pipes are designed to prevent flotation from uplift, scour or erosion, damage from debris on the waterside (particularly during flood flows), seepage along proposed pipes, corrosion, leakage, and damage from vehicular loads:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>Refer to detail 3 on sheet 41.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
4.	Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM):	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>Refer to detail 3 on sheet 41</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
5.	Pipes passing over the DWSE will have a minimum of 2 feet of cover (low permeability or CLSM):	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	
	Reference: <u>Refer to profiles on sheets 6-11 in Bid Set A</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
6.	If material must be added to the levee crown, the added material must be sloped at a ratio of 10H:1V horizontal to vertical, in the upstream/downstream direction to prevent a “speed bump” effect and facilitate vehicle access:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
7.	Fill will be compacted to at least 95% of maximum density as determined by ASTM D698, between -2 and +3% of optimum moisture content:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>Refer to Spec section 31 00 00 3.6B.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
8.	Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>Refer to Spec section 31 00 00 2.2A.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
9.	All fill will be free of organics or other inappropriate materials:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	
	Reference: <u>Refer to Spec section 31 00 00 3.9.B.1.6.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			

10.	Pipes terminating in the channel have a positive closure device on the waterside that is accessible from the levee crown:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to profiles on Sheets 6-11 and Detail 1 on Sheet 37 in Bid Set A.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
11.	Pipes transporting product completely across the federal project have a positive closure devices located within 1 mile on both sides of the federal project:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
12.	Pipes located within or beneath a levee have watertight joints that can accommodate movements resulting from settlement:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 2 on Sheet 40</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
13.	Pipes crossing the surface of the levee are designed to counteract buoyancy forces of an empty pipe, with water at the DWSE:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
14.	Pipe location and orientation will be clearly marked in the field:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Pipe location and orientation can be identified by vault structure and outfall location</u>		
15.	Pipes will allow easy access for rapid closure:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Positive valve closures on the levee crest will ensure easy access for rapid closure.</u>		
16.	Plastic pipes within the levee embankment or its foundation are embedded in concrete:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
17.	If a chemical or electrochemical reaction is expected, the pipe and pipe couplings must be protected:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
18.	Any work within the levee embankment or foundation?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
19.	Any work ≤50 feet beneath the channel invert?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
20.	Hydraulic blockage calculation ≥1%?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Rip Rap cross-sectional area below ordinary high watermark is anticipated to be significantly less than the cross-sectional area of Morrison Creek and therefore negligible.</u>		
21.	Hydraulic model used for hydraulic analysis?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
		N/A <input checked="" type="checkbox"/>	

**Reference:** [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]

**Comment:** [ Click to enter rationale, explanation, unique situation, etc. ]

– For Official Use Only below this line –

*Comment*

**CP Eligibility Review**

<u>Yes</u>	<u>No</u>	<u>Add'l. Info Requested</u>		
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Environmental Reviewer: _____	Date: <small>Click date</small> _____
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Engineering Reviewer: _____	Date: <small>Click date</small> _____

**American River Flood Control District  
Central Valley Flood Protection Board Permit Application  
Sump 154 Modifications (City of Sacramento)  
Staff Report**

**Discussion:**

The City of Sacramento submitted this encroachment permit application to modify facilities at their Sump 154 Pump Station. The work proposed is to remove and replace approximately 160 ft of three (3) 36" welded steel pipes at the pump discharge locations and outfall structure.

Sump 154 is located adjacent to the Arcade Creek South Levee at the confluence with Steelhead Creek.

These modifications are required to upgrade the pipe outfall system at the pump station. Recent work conducted by SAFCA under the North Area Streams Project replaced only the segments of pipe that crossed through the levee. This work will complete the upgrade to the facility by replacing the pipe discharge sections at the pumps and also the pipe outfall sections and flap gates.

These modifications will be routine construction installations and do not present considerable engineering challenges. It is not anticipated that this work will pose significant operations and maintenance impacts to the District.

**Recommendation:**

The General Manager recommends that the Board of Trustees endorse the CVFPB permit application.

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

**Application No.** \_\_\_\_\_  
(For Office Use Only)

1. Description of proposed work being specific to include all items that will be covered under the issued permit.  
Sump 154 Modifications: Remove and replace approximately 160 ft of three (3) 36" welded steel pipes at the pump discharge locations and outfall structure.

2. Project Location: Sacramento County, in Section See Attachment A  
Township: See Attachment A (N) (S), Range: See Attachment A (E) (W), M. D. B. & M.  
Latitude: 38.61943 Longitude: -121.46703  
Stream: Arcade Creek, Levee: Left Bank Designated Floodway: Arcade Creek  
APN: See Attachment A

3. Raymond Kong, PE of 1395 35th Ave  
Name of Applicant / Land Owner Address  
Sacramento CA 95822 (916) 808-1435  
City State Zip Code Telephone Number  
RKong@cityofsacramento.org  
E-mail

4. Ashley Smith, PE of Peterson Brustad Inc.  
Name of Applicant's Representative Company  
Folsom CA 95630 (916) 608-2212 x 123  
City State Zip Code Telephone Number  
asmith@pbieng.com  
E-mail

5. Endorsement of the proposed project from the Local Maintaining Agency (LMA):

We, the Trustees of American River Flood Control District approve this plan, subject to the following conditions:  
Name of LMA

Conditions listed on back of this form  Conditions Attached  No Conditions

\_\_\_\_\_  
Trustee Date Trustee Date  
\_\_\_\_\_  
Trustee Date Trustee Date

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

6. Names and addresses of adjacent property owners sharing a common boundary with the land upon which the contents of this application apply. If additional space is required, list names and addresses on back of the application form or an attached sheet.

Name	Address	Zip Code
See Attachment A		

7. Has an environmental determination been made of the proposed work under the California Environmental Quality Act of 1970?  Yes  No  Pending

If yes or pending, give the name and address of the lead agency and State Clearinghouse Number:

City of Sacramento  
1395 35th Avenue  
Sacramento, CA 95822

SCH No. Pending

8. When is the project scheduled for construction? April 2021

9. Please check exhibits accompanying this application.

- A.  Regional and vicinity maps showing the location of the proposed work.
- B.  Drawings showing plan view(s) of the proposed work to include map scale.
- C.  Drawings showing the cross section dimensions and elevations (vertical datum?) of levees, berms, stream banks, flood plain,
- D.  Drawings showing the profile elevations (vertical datum?) of levees, berms, flood plain, low flow, etc.
- E.  A minimum of four photographs depicting the project site.

\_\_\_\_\_  
Signature of Applicant

\_\_\_\_\_  
Date

Include any additional information:

A summary of the Project and a description of the proposed methods are provided in Attachment A. Attachment B includes relevant plan sheets which are an excerpt from a larger plan set. Attachment C includes the categorical permission checklist. The intent of this application is to modify the existing encroachment permit. The existing Permit number for Sump 154 is 1845-1.

**Attachment A – Summary of Proposed Work**



**CITY OF SACRAMENTO PUMP OUTFALLS PROJECT:  
CENTRAL VALLEY FLOOD PROTECTION BOARD ENCROACHMENT PERMIT**

**SUMMARY OF PROPOSED WORK**

September 15, 2020

**INTRODUCTION**

As mandated by the Sacramento Area Flood Control Agency (SAFCA) and the U.S. Army Corps of Engineers (USACE), sump station outfalls that penetrate and cross major levees are inspected on a 5-year cycle. The project entails the complete replacement of the pump discharge for three (3) drainage sump station facilities and partial replacement of the pump discharge pipe for five (5) drainage sump station facilities. The following information pertains to a partial replacement sump (Sump 154) that will need an updated Encroachment Permit from the CVFPB.

**APN Parcels**

Sump	Existing Permit #	APN
154	1845-1	263-0010-036-0000, 263-0051-001-0000, 263-0010-037-0000

**ADJACENT PARCELS**

All of the parcels adjacent to the Sump to be modified are listed in the table presented below as provided by the Sacramento County Assessor's Office.

APN	Address	Owner	Owner Address	City	Zip
263-0010-034-0000	NORWOOD AVE	SACTO & SAN JOAQUIN DRAINAGE DIS	PO BOX 942836	SACRAMENTO	94236
263-0051-030-0000	ARCADE BLVD	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
263-0051-032-0000	75 ARCADE BLVD	ILSA MEDINA	75 ARCADE BLVD	SACRAMENTO	95815
263-0051-033-0000	83 ARCADE BLVD	ROHITESHWAR CHAND	83 ARCADE BLVD	SACRAMENTO	95815
263-0110-001-0000	N/A	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
263-0260-008-0000	E LEVEE RD	WESTERN PACIFIC RAILROAD CO	1400 DOUGLAS ST 1640	OMAHA	68179
263-0260-021-0000	3201 NORWOOD AVE	WESTERN PACIFIC RAILROAD CO	1400 DOUGLAS ST 1640	OMAHA	68179
263-0341-001-0000	63 ARCADE BLVD	DAVID R BENNETTE	4813 HUTSON WAY	ELK GROVE	95757

## **TOWNSHIP AND RANGE INFORMATION**

Note that gaps exist in Townships and Ranges within the project area. Land not covered by T9N R5E has been in private ownership since before California joined the United States and therefore is not part of the Township and Range system, which was a survey of federal lands.

## **SITE PHOTOGRAPHS**

Attached to this Summary of Proposed Work are photographs showing levee and channel areas representative of proposed work sites.



Figure 1: Waterside toe near Sump 154 looking toward levee crest



Figure 2: View looking southwest toward the fenced Sump 154 facility on the land side of the levee





Figure 3: View looking south toward the Sump 154 concrete outfall structures from the dry bed of Arcade Creek.



Figure 4: Waterside slope near Sump 154 looking east

**Attachment B – Plan Sheets**

*(Excerpt from larger plan set for Pump Outfalls Replacement Project – A)*



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.22
DESCRIPTION:	CP/RBR&CAP	

FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"	

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21





IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
SUMP 154  
DEMO PLAN

65% SUBMITTAL

PN: W14130615	DWG. NO. C25
	SHEET 28 OF 47

Page 11



PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV. 44.22
DESCRIPTION:	CP/RBR&CAP

FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE	DRAWING ADJUST
SCALED DIMENSIONS	IF THIS DOES NOT
SCALE AT 1"	


<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY:	E. TUTEJA	DESIGNED BY:	B. JENSEN
DATE:	09/15/20	R.C.E. NO.:	C90949 DATE: 03/31/22
		CHECKED BY:	A. SMITH
		R.C.E. NO.:	C86512 DATE: 03/31/21





IMPROVEMENT PLANS FOR:	
PUMP OUTFALLS REPLACEMENT PROJECT - A	
SUMP 154	
SITE PLAN	
Page 12	DWG. NO. C26 SHEET 29 OF 47

65% SUBMITTAL





- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 36" WSP AND APPURTENANCES FROM STA -0+74.9 TO STA -0+48.0 AND STA 0+69.5 TO STA 0+73.4 PER DETAIL 2/C38
  - 2 INSTALL 36" WSP FROM STA -0+74.9 TO STA -0+48.0 AND STA 0+69.5 TO STA 0+73.4 PER DETAIL 3/C38
  - 3 CONNECT TO EXISTING STEEL COUPLING
  - 4 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 5 CONNECT TO EXISTING PIPE PER DETAIL 3/C37
  - 6 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV. 44.22
DESCRIPTION:	
CP/RBR&CAP	

FIELD BOOK	0000
SCALE:	1" = 10'
H: H:	
V: V:	


**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

DRAWN BY: E. TUTEJA      DESIGNED BY: B. JENSEN      CHECKED BY: A. SMITH  
 DATE: 09/15/20      R.C.E. NO. C90949      DATE: 03/31/22      R.C.E. NO. C86512      DATE: 03/31/21





IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 154**  
**PLAN AND PROFILE 1 - 36" WSP**

65% SUBMITTAL  
 DWG. NO. C27  
 SHEET 30 OF 47  
 Page 13



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 30" WSP AND APPURTENANCES FROM STA -0+74.7 TO STA -0+48.3 AND STA 0+68.0 TO STA 0+71.6 PER DETAIL 2/C38
  - 2 INSTALL 30" WSP FROM STA -0+74.7 TO STA -0+48.3 AND STA 0+68.0 TO STA 0+71.6 PER DETAIL 3/C38
  - 3 CONNECT TO EXISTING STEEL COUPLING
  - 4 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 5 CONNECT TO EXISTING PIPE PER DETAIL 3/C37
  - 6 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.22
DESCRIPTION:	CP/RBR&CAP	

FIELD BOOK	0000
SCALE:	1" = 10'
H: H:	
V: V:	

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY:	E. TUTEJA	DESIGNED BY:	B. JENSEN
DATE:	09/15/20	R.C.E. NO.:	C90949 DATE: 03/31/22
		CHECKED BY:	A. SMITH
		R.C.E. NO.:	C86512 DATE: 03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 154**  
**PLAN AND PROFILE 2 - 30" WSP**



65% SUBMITTAL

DWG. NO.	C28
SHEET	31
OF	47

PN: W14130615



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 30" WSP AND APPURTENANCES FROM STA -0+82.1 TO STA -0+52.6 AND STA 0+65.3 TO STA 0+69.5 PER DETAIL 2/C38
  - 2 INSTALL 30" WSP FROM STA -0+82.1 TO STA -0+52.6 AND STA 0+65.3 TO STA 0+69.5 PER DETAIL 3/C38
  - 3 CONNECT TO EXISTING STEEL COUPLING
  - 4 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 5 CONNECT TO EXISTING PIPE PER DETAIL 3/C37
  - 6 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

PN: W14130615

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.22
DESCRIPTION:	CP/RBR&CAP	

FIELD BOOK	0000
SCALE:	1" = 10'
H: H:	
V: V:	

**CITY OF SACRAMENTO  
DEPARTMENT OF UTILITIES**

DRAWN BY: E. TUTEJA      DESIGNED BY: B. JENSEN      CHECKED BY: A. SMITH


DATE: 09/15/20      R.C.E. NO. C90949      DATE: 03/31/22      R.C.E. NO. C86512      DATE: 03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 154**  
**PLAN AND PROFILE 3 - 30" WSP**

65% SUBMITTAL

DWG. NO. **C29**  
SHEET **32** OF **47**  
Page 15




**SUMP 155 ANTI SIPHON VAULT DETAIL 1**  
NTS




NOTE: PIPE SUPPORT TO BE STANDON S92 OR APPROVED EQUAL

**PIPE SUPPORT 2**  
NTS




**PLAN VIEW**



**LIFTING EYE DETAIL**

TYPICAL ANTI-SIPHON VALVE SIZE

D1	D2	D3	S	MODEL
16"	12"	10"	3"	HSB-03-A-16
18"	16"	12"	3"	HSB-03-A-18
30"	24"	20"	7"	HSB-07-B-30
36"	30"	24"	5"	HSB-05-A-36
42"	30"	24"	8"	HSB-08-B-42
54"	30"	24"	8"	HSB-08-B-54



**PROFILE VIEW**

**SECTION VIEW**

**WELD DETAIL 4**  
NTS

**WELD DETAIL 5**  
NTS

**ANTI-SIPHON AND AIR RELIEF VALVE CONNECTION DETAIL 3**  
NTS

**SECTION B**  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY


BENCH MARK	ELEV.

FIELD BOOK	0000
SCALE:	1"

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

DRAWN BY: E. TUTEJA      DESIGNED BY: B. JENSEN      CHECKED BY: A. SMITH  
DATE: 09/15/20      R.C.E. NO. C90949      DATE: 03/31/22      R.C.E. NO. C86512      DATE: 03/31/21





IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**ANTI SIPHON AND VALVE VAULT**  
**SECTION AND DETAILS**

65% SUBMITTAL



PN: W14130615	DWG. NO. C35
	SHEET 38 OF 47
	Page 16

**GENERAL NOTES:**

1. LINE POSTS SHALL BE MIN 2½" O.D. SPACED AT MAX 10' O.C.
2. HORIZONTAL BRACE AND TOP RAIL SIZE SHALL BE MIN 1½" DIA.
3. END, CORNER, AND GATE POSTS SHALL BE MIN 2½" O.D. WITH 1½" O.D. BRACE RAIL, ¾" TRUSS ASSEMBLY, 12-GAUGE TENSION BANDS SECURED AT MAX 12" O.C.
4. GATE FRAME SHALL BE FABRICATED FROM 2½" O.D. OR 2½" SQUARE MEMBERS WELDED AT ALL CORNERS.
5. CHAIN LINK FABRIC SHALL BE SECURED TO LINE POST AND TOP RAIL USING 9-GAUGE TIE WIRE SPACED AT MAX 12" O.C.
6. 2-3/8" SHOULDERED EYE BOLT 3" LENGTH TO ANCHOR TENSION WIRE PER 10' SECTION EVENLY SPACED, SECURED WITH HOG RING CAPTURING FENCE FABRIC AND TENSION WIRE TO MAINTAIN DOWNWARD TENSION ON SECURITY FENCE SYSTEM.
7. PROVIDE "CITY UTILITY FACILITY - NO TRESPASSING" SIGNAGE GATE.




**GATE ANTI-SWING FOOTING DETAIL 1**  
NTS



**LINE POST DETAIL 3**  
NTS

**GATE OPERATOR SECTION A**  
NTS



8 FOOT HIGH CHAIN LINK FABRIC WITH ANGLED OUTRIGGER AND 3 STRAND BARB WIRE (OUTSIDE) STANDARD FENCING DETAIL

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK DESCRIPTION:	ELEV. _____
-------------------------	-------------

FIELD BOOK	0000
SCALE:	1" = _____
H:	
V:	

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"


DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21




65% SUBMITTAL

IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**MISCELLANEOUS VAULT SECURITY DETAILS** Page 17

PN: W14130615	DWG. NO. C36
	SHEET 39 OF 47




OUTFALL STRUCTURE CONNECTION DETAIL **1**  
NTS



NOTES:  
1. PROVIDE HAND HOLES AS NEEDED TO INSTALL FIELD LINING. WELD HAND HOLE CLOSED WHEN COMPLETE. HAND HOLES NOT REQUIRED AT OUTLETS IF ACCESSIBLE THROUGH FLAP GATE.

NEW OR EXISTING STEEL  
PIPE CONNECTION DETAIL **2**  
NTS



TRENCH SECTION AND SEQUENCING **3**  
NTS

NOTES:


- CONTRACTOR SHALL REPLACE EXISTING PAVEMENT IN KIND. BASED ON LIMITED FIELD INVESTIGATIONS, EXISTING PAVEMENT SECTION ARE ASSUMED 2" AC ON 6" AB
- THE OWNER AND THE CONTRACTOR SHALL JOINTLY DETERMINE THE FINAL WIDTH AND LENGTH OF THE BIKE PATH CROSSING BASED ON FIELD CONDITIONS AND CONSTRUCTION PROCEDURES.
- CONTRACTOR SHALL REMOVE EXISTING BIKE PATH AS NEEDED TO CONSTRUCT PROPOSED PIPE. IMPACTED AREAS SHALL BE REPLACED IN ACCORDANCE WITH CITY OF SACRAMENTO STANDARD DETAIL T-21

CONSTRUCTION SEQUENCE:

- STEP 1: SAWCUT LIMITS 09F TRENCH EXCAVATION TO CLEAN CUT LIMITS. REMOVE EXISTING ASPHALT CONCRETE TO THE MIN EXTENT REQUIRED TO CONSTRUCT PROPOSED PIPE. PROPOSED PIPE SHALL BE CONSTRUCTED A MIN OF 2' FROM FG. TRENCH PLATES SHALL BE PROVIDED TO MAINTAIN ACCESS OVER CUTOFF WALL DURING CONSTRUCTION IN ACCORDANCE WITH THE SPECIFICATIONS.
- STEP 2: PLACE AB TO MATCH EXISTING THICKNESS. PLACE AC OVERLAY FROM EXTENT APPROVED BY AGENCY AND CONTRACTOR TO LIMITS OF SAWCUT. PROVIDE PAVEMENT MARKING AND STRIPING TO MATCH EXISTING.

LEGEND:

- |                                    |          |
|------------------------------------|----------|
| EXISTING                           | PROPOSED |
|                                    |          |
| GRIND AND OVERLAY ASPHALT CONCRETE |          |
|                                    |          |
| AGGREGATE BASE (AB)                |          |
|                                    |          |
| ASPHALT CONCRETE (AC)              |          |



CROWN SURFACING DETAIL **4**  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.
DESCRIPTION:	

FIELD BOOK
0000
SCALE:
1"
ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

<b>CITY OF SACRAMENTO</b> DEPARTMENT OF UTILITIES			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	DATE: 03/31/21
DATE: 09/15/20	R.C.E. NO. C90949	DATE: 03/31/22	R.C.E. NO. C86512




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
MISCELLANEOUS DETAILS I

65% SUBMITTAL

DWG. NO. C37
SHEET 40 OF 47
Page 18


PN: W14130615




TYPICAL SLOPE BENCHING NOTES:

1. PLACE FILL IN HORIZONTAL LIFTS AGAINST VERTICAL FACES CUT INTO EXISTING LEVEE MATERIAL.
2. THE BOTTOM OF THE KEY TRENCH SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES AND RECOMPACTED TO 95% MAX DENSITY PER ASTM D698.

SLOPE BENCHING (LANDSIDE OR WATERSIDE) DETAIL **1**  
NTS



TYPICAL REMOVAL OF EXISTING PIPE DETAIL **2**  
NTS



INSTALLATION OF NEW PIPE DETAIL **3**  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.
DESCRIPTION:	

FIELD BOOK	0000
SCALE:	1" = 1'
H:	
V:	

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

<b>CITY OF SACRAMENTO</b> DEPARTMENT OF UTILITIES			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	



65% SUBMITTAL

IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
MISCELLANEOUS DETAILS II

Page 19

DWG. NO. C38
SHEET 41 OF 47

PN: W14130615

**Attachment C – Categorical Permission Checklist**



## Categorical Permission Alteration Description – 16. Pressurized Pipes

The categorical permission covers the installation, modification, and replacement of pressurized pipes that comply with certain terms and conditions. Particularly, all pressurized pipes must be designed and installed in accordance with current USACE standards. The total area of disturbance, including staging and access areas, must not exceed 5 acres. Pressurized pipes must also be designed to prevent, (1) flotation from uplift, (2) scour or erosion, (3) damage from debris on the waterside, particularly during flood flows, (4) leakage, (5) seepage along proposed pipes, (6) corrosion, and (7) damage from vehicular loads.

All new pressurized pipes should go up and over the levee DWSE. Pressurized pipes passing over or within the freeboard zone of a levee (i.e., above the levee DWSE), should be made of metal, preferably ductile iron or coated steel, suitable for use with flexible couplings.

Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM). Pipes that pass above the DWSE must have 2 feet of cover (low permeability or CLSM) to prevent damage by vehicles and equipment. Cover material on the levee crown must be placed at a ratio of 10H:1V, in the upstream/downstream direction of the levee. Pipes on the sides of the levee should be covered with a minimum of 1 foot of low permeability material, compacted in 4- to 6-inch lifts or CLSM to protect them from debris during high water (waterside) or to keep them from interfering with or being damaged by operations or maintenance of the levee (landside). Fill must be free of deleterious materials and construction debris and placed in 4- to 6-inch-thick loose lifts and compacted to not less than 95% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D698 (USACE preferred method), or alternately, 90% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D1557. At the sponsor and levee maintaining agency's discretion, pipes on the levee slopes may be left exposed.

Only suitable material must be used as levee fill materials. Fill must be free from: roots and other organic matter, contaminated hazardous or toxic material, trash, debris, and frozen materials. Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve.

Pressurized pipes terminating in the channel require a positive closure device on the waterside that is accessible from the levee crown. Pressurized pipes transporting product completely across or through the federal project easement require positive closure devices located landward of any levees and channel. The positive closure device shall be located within one mile on both sides of the federal project. If the invert of the pipe is over the levee crown, the combination of a pump station on the waterside and a siphon breaker is considered an appropriate means of closure. Pipes located within or beneath a levee must have watertight joints that can accommodate movements resulting from settlement.

All pressurized pipes that cross the levee foundation at a depth less than or equal to two times the height of the levee should be evaluated for uplift. Pipes crossing the surface of the levee must be designed to counteract buoyancy forces of an empty pipe, with water at the DWSE.

Pressurized pipelines running parallel to flood risk management projects should be located at least 15 feet beyond the levee toes. Pipe location and orientation must be clearly marked in the field so they can be easily identified for flood fighting crews.

If appropriate, the requester should prepare an excavation plan demonstrating the effects of excavation on the stability of the embankments.

The site layout should provide adequate access for maintenance vehicles to refill fuel tanks and service/replace pumps, generators, etc. Pressurized pipes must also allow easy access for rapid closure in the event of leakage or rupture.

No plastic pipes (HDPE, PVC, etc.) are allowed in the levee embankment or its foundation unless they are embedded in concrete.

If an electrochemical or chemical reaction between the substratum or groundwater and pipe materials is expected, the pipe and pipe couplings must be protected.

After installation of pressurized pipes, the requester must demonstrate 0% pipe leakage in pipes in the levee. Pipes must be pressure tested to industry standards. Pipes must be regularly inspected, including the interior, if possible, looking for signs of maintenance issues. If an inspection indicates corrosion, alignment sag or heave, or separation at joints, corrective action must be taken as soon as possible to avoid failure. Pipe valves must be periodically inspected and pressure tested to ensure that they are functioning properly. Pressure tests must show no significant loss in pressure. Leaks and other deficiencies must be addressed as soon as possible. All replacement parts must be of equivalent or better quality than those being replaced.

The preferred method for abandoning pipes that pass through or over a levee is complete removal. If removal is not feasible, the pipes and other structures may be filled with a cement/bentonite-based grout or flowable fill. The grout needs to be sufficiently fluid so that it can be pumped to completely fill the pipe leaving no voids.

### Categorical Permission Alteration Checklist – 16. Pressurized Pipes

*Note:* The following checklist is intended for planning purposes only, and includes information that USACE reviewers look for when considering a Section 408 request for pressurized pipes under the Categorical Permission. To be reviewed under the Categorical Permission, the proposed project must adhere to all requirements of the Categorical Permission, including the full alteration description (see previous page). The plans and narrative project description should reflect this information.

1.	<input type="checkbox"/> New Construction <input checked="" type="checkbox"/> Replacement <input type="checkbox"/> Modification <input type="checkbox"/> Authorize Existing		
2.	Maximum total area of disturbance is 5 acres:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Area of disturbance is 0.02 acre.</u>		
3.	Pipes are designed to prevent flotation from uplift, scour or erosion, damage from debris on the waterside (particularly during flood flows), seepage along proposed pipes, corrosion, leakage, and damage from vehicular loads:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
4.	Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM):	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
5.	Pipes passing over the DWSE will have a minimum of 2 feet of cover (low permeability or CLSM):	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
6.	If material must be added to the levee crown, the added material must be sloped at a ratio of 10H:1V horizontal to vertical, in the upstream/downstream direction to prevent a “speed bump” effect and facilitate vehicle access:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment:		
7.	Fill will be compacted to at least 95% of maximum density as determined by ASTM D698, between -2 and +3% of optimum moisture content:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.6B.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
8.	Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 2.2A.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
9.	All fill will be free of organics or other inappropriate materials:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.9.B.1.6.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		

10.	Pipes terminating in the channel have a positive closure device on the waterside that is accessible from the levee crown:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
11.	Pipes transporting product completely across the federal project have a positive closure devices located within 1 mile on both sides of the federal project:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
12.	Pipes located within or beneath a levee have watertight joints that can accommodate movements resulting from settlement:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>Refer to detail 2 on Sheet 40</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
13.	Pipes crossing the surface of the levee are designed to counteract buoyancy forces of an empty pipe, with water at the DWSE:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	
	Reference: <u>Refer to detail 3 on sheet 41</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
14.	Pipe location and orientation will be clearly marked in the field:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>pipe location and orientation can be identified by vault structure and outfall location</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
15.	Pipes will allow easy access for rapid closure:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: <u>Positive valve closures on the levee crest will ensure easy access for rapid closure.</u>			
16.	Plastic pipes within the levee embankment or its foundation are embedded in concrete:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
17.	If a chemical or electrochemical reaction is expected, the pipe and pipe couplings must be protected:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
18.	Any work within the levee embankment or foundation?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
19.	Any work ≤50 feet beneath the channel invert?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
20.	Hydraulic blockage calculation ≥1%?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
21.	Hydraulic model used for hydraulic analysis?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			

– For Official Use Only below this line –

*Comment*

**CP Eligibility Review**

<u>Yes</u>	<u>No</u>	<u>Add'l. Info Requested</u>		
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Environmental Reviewer: _____	Date: <small>Click date</small> _____
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Engineering Reviewer: _____	Date: <small>Click date</small> _____

**American River Flood Control District  
Central Valley Flood Protection Board Permit Application  
Sump 155 Modifications (City of Sacramento)  
Staff Report**

**Discussion:**

The City of Sacramento submitted this encroachment permit application to modify facilities at their Sump 155 Pump Station. The work proposed is to remove and replace approximately 360 ft of two (2) 36" welded steel pipes. Remove and replace approximately 120 ft of one (1) 42" Corrugated Metal Pipe.

Sump 155 is located adjacent to the American River South Levee and just north of the H Street Bridge in River Park.

These modifications are required to upgrade the pipe outfall system at the pump station. The current system does not meet modern U.S. Army Corps of Engineers' standards. The USACE now requires that all pressurized pipes cross the levee at or above the 200-year flood elevation for the adjacent channel and that the pipes each have a positive closure device (shut-off valve) at the waterside crown hinge point. The proposed work will upgrade the facility to meet all State and Federal requirements.

Once the work is complete, it is not anticipated that this work will pose significant operations and maintenance impacts to the District. There will be temporary loss of access and thoroughfare for the District during construction.

**Recommendation:**

The General Manager recommends that the Board of Trustees endorse the CVFPB permit application.

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

Application No. \_\_\_\_\_  
(For Office Use Only)

1. Description of proposed work being specific to include all items that will be covered under the issued permit.  
Sump 155 Modifications: Remove and replace approximately 360 ft of two (2) 36" welded steel pipes. Remove and replace approximately 120 ft of one (1) 42" Corrugated Metal Pipe.

2. Project Location: Sacramento County, in Section See Attachment A  
Township: See Attachment A (N) (S), Range: See Attachment A (E) (W), M. D. B. & M.  
Latitude: 38.57020 Longitude: -121.42420  
Stream: American River, Levee: Left Bank Designated Floodway: American River  
APN: See Attachment A

3. Raymond Kong, PE of 1395 35th Ave  
Name of Applicant / Land Owner Address  
Sacramento CA 95822 (916) 808-1435  
City State Zip Code Telephone Number  
RKong@cityofsacramento.org  
E-mail

4. Ashley Smith, PE of Peterson Brustad Inc.  
Name of Applicant's Representative Company  
Folsom CA 95630 (916) 608-2212 x 123  
City State Zip Code Telephone Number  
asmith@pbieng.com  
E-mail

5. Endorsement of the proposed project from the Local Maintaining Agency (LMA):

We, the Trustees of American River Flood Control District approve this plan, subject to the following conditions:  
Name of LMA

Conditions listed on back of this form  Conditions Attached  No Conditions

\_\_\_\_\_  
Trustee Date Trustee Date  
\_\_\_\_\_  
Trustee Date Trustee Date

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

6. Names and addresses of adjacent property owners sharing a common boundary with the land upon which the contents of this application apply. If additional space is required, list names and addresses on back of the application form or an attached sheet.

Name	Address	Zip Code
See Attachment A		

7. Has an environmental determination been made of the proposed work under the California Environmental Quality Act of 1970?  Yes  No  Pending

If yes or pending, give the name and address of the lead agency and State Clearinghouse Number:

City of Sacramento  
1395 35th Avenue  
Sacramento, CA 95822

SCH No. Pending

8. When is the project scheduled for construction? April 2021

9. Please check exhibits accompanying this application.

- A.  Regional and vicinity maps showing the location of the proposed work.
- B.  Drawings showing plan view(s) of the proposed work to include map scale.
- C.  Drawings showing the cross section dimensions and elevations (vertical datum?) of levees, berms, stream banks, flood plain,
- D.  Drawings showing the profile elevations (vertical datum?) of levees, berms, flood plain, low flow, etc.
- E.  A minimum of four photographs depicting the project site.

\_\_\_\_\_  
Signature of Applicant Date

Include any additional information:

A summary of the Project and a description of the proposed methods are provided in Attachment A. Attachment B includes relevant plan sheets which are an excerpt from a larger plan set. Attachment C includes the categorical permission checklist for pressurized pipe. Attachment D includes the categorical permission checklist for gravity pipe. Attachment E includes the Biological Assessment.



**Attachment A – Summary of Proposed Work**

**CITY OF SACRAMENTO PUMP OUTFALLS PROJECT:  
CENTRAL VALLEY FLOOD PROTECTION BOARD ENCROACHMENT PERMIT**

**SUMMARY OF PROPOSED WORK**

September 15, 2020

**INTRODUCTION**

As mandated by the Sacramento Area Flood Control Agency (SAFCA) and the U.S. Army Corps of Engineers (USACE), sump station outfalls that penetrate and cross major levees are inspected on a 5-year cycle. The project entails the complete replacement of the pump discharge for three (3) drainage sump station facilities and partial replacement of the pump discharge pipe for five (5) drainage sump station facilities. The following information pertains to a complete replacement sump (Sump 155) that will need an updated Encroachment Permit from the CVFPB.

**APN Parcels**

Sump	Existing Permit #	APN
155	N/A	005-0010-024-0000, 005-0010-025-0000

**ADJACENT PARCELS**

All of the parcels adjacent to the Sump to be modified are listed in the table presented below as provided by the Sacramento County Assessor's Office.

APN	Address	Owner	Owner Address	City	Zip
005-0010-005-0000	SEWARD CT	STATE OF CALIFORNIA	N/A	SACRAMENTO	95826
005-0203-002-0000	250 SANDBURG DR	TIMOTHY C JOHNSON	250 SANDBURG DR	SACRAMENTO	95819
005-0203-003-0000	240 SANDBURG DR	MICHAEL L CHIECHI	240 SANDBURG DR	SACRAMENTO	95819
005-0203-004-0000	230 SANDBURG DR	OBRIEN FAMILY TRUST	230 SANDBURG DR	SACRAMENTO	95819
005-0203-005-0000	220 SANDBURG DR	SURVIVORS TRUST	220 SANDBURG DR	SACRAMENTO	95819
005-0203-006-0000	210 SANDBURG DR	DONALD T TERRELL	210 SANDBURG DR	SACRAMENTO	95819

005-0203-014-0000	E SANDBURG DR	AMERICAN RIVER FLOOD CONTROL DIST	165 COMMERCE CIR UNIT D	SACRAMENTO	95815
005-0203-018-0000	6005 CAMELLIA AVE	SEAN RANNEY	PO BOX 191334	SACRAMENTO	95819
005-0233-003-0000	6025 CAMELLIA AVE	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
005-0233-004-0000	6009 CAMELLIA AVE	SCOTTISH GARDENS LLC	5813 W 2 <sup>ND</sup> ST	RIO LINDA	95673
005-0233-006-0000	H ST	AMERICAN RIVER FLOOD CONTROL DIST	185 COMMERCE CIR	SACRAMENTO	95815

### **TOWNSHIP AND RANGE INFORMATION**

Note that gaps exist in Townships and Ranges within the project area. Land not covered by T9N R5E has been in private ownership since before California joined the United States and therefore is not part of the Township and Range system, which was a survey of federal lands.

### **SITE PHOTOGRAPHS**

Attached to this Summary of Proposed Work are photographs showing levee and channel areas representative of proposed work sites.



Figure 1: View of pump station



Figure 2: View from waterside TOE of Levee facing Levee crest (upstream)



Figure 3: View from waterside slope of levee facing downstream towards American River






Figure 4: View of outfall structure with flapgates at the waterside slope of Levee

**Attachment B – Plan Sheets**

*(Excerpt from larger plan set for Pump Outfalls Replacement Project – B)*





PN: W14130615

DATE: 09/19/20  
 DRAWN BY: E. JUEA  
 CHECKED BY: A. SMITH  
 R.C.E. NO. 08502  
 DATE: 03/31/21

REVISIONS  
 DESCRIPTION  
 DATE  
 BY

FIELD BOOK  
 0000  
 SCALE:  
 H. \_IN\_ / V. \_IN\_

BENCH MARK  
 DESCRIPTION:  
 ELEV.:

1" = 1000'  
 ON ORIGINAL SCALE  
 DRAWING ADJUSTS  
 TO MATCH ORIGINALS  
 IF THIS DOES NOT  
 SCALE AT 1"

CITY OF SACRAMENTO  
 DEPARTMENT OF UTILITIES

IMPROVEMENT PLANS FOR:  
 PUMP OUTFALLS REPLACEMENT PROJECT - B  
 SUMP 089 AND 155  
 STAGING AREA



65% SUBMITTAL

PN: W14130615

DATE: 09/19/20

DATE: 03/31/21

DATE: 03/31/21

DATE: 03/31/21

DATE: 03/31/21

DATE: 03/31/21


DATE: 03/31/21

DATE: 03/31/21

DATE: 03/31/21

DATE: 03/31/21


DATE: 03/31/21



HOR SCALE: 1"=10'  
 10 5 0 0  
 5 2.5 0 5  
 VERT SCALE: 1"=5'

PN: W14130615  
 65% SUBMITTAL

IMPROVEMENT PLANS FOR  
**PUMP OUTFALLS REPLACEMENT PROJECT - B**  
 SUMP 155  
 DEMO PLAN



**CITY OF SACRAMENTO**  
 DEPARTMENT OF UTILITIES

DESIGNED BY: B. JENSEN  
 DRAWN BY: E. JUEGA  
 CHECKED BY: A. SMITH

DATE: 09/19/20  
 DATE: 03/21/22  
 DATE: 03/21/21

R.C.E. NO. 090849  
 R.C.E. NO. 08602

FIELD BOOK  
 0000


SCALE:  
 H. 1"=10'  
 V. 1"=5'

ON ORIGINAL SCALE  
 DRAWING ADJUST  
 IF THIS DOES NOT  
 SCALE AT 1"

BENCH MARK  
 DESCRIPTION:  
 MONUMENT, IRL & WISER

ELEV. 36.95

REVISIONS	DATE	BY



HOR SCALE: 1"=10'  
 10 5 0 0  
 5 2.5 0 0  
 VERT SCALE: 1"=5'

PN: W14130615  
 65% SUBMITTAL

IMPROVEMENT PLANS FOR  
**PUMP OUTFALLS REPLACEMENT PROJECT - B**  
**SUMP 155**  
**SITE PLAN**



**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

DESIGNED BY: E. JUEVA  
 DRAWN BY: B. JENSEN  
 CHECKED BY: A. SMITH

DATE: 09/19/20  
 DATE: 03/21/22  
 DATE: 03/31/21

R.C.E. NO. 09049  
 R.C.E. NO. 08502

FIELD BOOK  
 0000



SCALE:  
 H. 1"=10'  
 V. 1"=5'

ON ORIGINAL SCALE  
 DRAWING ADJUST  
 IF THIS DOES NOT  
 SCALE AT 1"

BENCH MARK  
 DESCRIPTION:  
 MONUMENT, IRL & WISER

ELEV. 36.95

REVISIONS	DATE	BY
DESCRIPTION		



65% SUBMITTAL

**CITY OF SACRAMENTO**  
DEPARTMENT OF UTILITIES

**PUMP OUTFALLS REPLACEMENT PROJECT - B**  
SUMP 155  
PLAN AND PROFILE 1 - 36" WSP

DRAWN BY: E. JUEVA  
CHECKED BY: A. SMITH  
DATE: 09/19/20  
R.C.E. NO. 08602



DATE: 03/31/21

FIELD BOOK: 0000  
SCALE: 1" = 10'  
H. 1" = 10'  
V. 1" = 5'


BENCH MARK DESCRIPTION: ELEV. 36.95  
MARKED: M.L. & WISER

REVISIONS  
DATE BY DESCRIPTION



PN: W14130615  
R14130615



- NOTES:
- 1 REMOVE AND DISPOSE OF EXISTING 42" CMP AND APPURTENANCES FROM STA -0+46.7 TO STA 0+70.3 PER DETAIL 2/C19
  - 2 INSTALL 42" RCP FROM STA -0+46.7 TO STA 0+70.3 PER DETAIL 2/C19
  - 3 INSTALL GATE RISER STRUCTURE PER DETAIL 1/C17
  - 4 INSTALL GATE RISER PER DETAIL 1/C19
  - 5 CONNECT TO PROPOSED GATE RISER STRUCTURE
  - 6 CONNECT TO OUTFALL STRUCTURE PER DETAIL 1/C18
  - 7 CONNECT TO EXISTING VAULT
  - 8 RECONSTRUCT LEVEE EMBANKMENT WITH LEVEE FILL MATERIAL
  - 9 INSTALL RSP PER DETAIL 1/C18
  - 10 REPLACE AGGREGATE SURFACE PER DETAIL 4/C17
  - 11 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS. THE CONTRACTOR IS RESPONSIBLE TO POthOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.




PN: W14130615		IMPROVEMENT PLANS FOR		65% SUBMITTAL	
PUMP OUTFALLS REPLACEMENT PROJECT		CITY OF SACRAMENTO		PUMP OUTFALLS REPLACEMENT PROJECT - B	
SUMP 155		DEPARTMENT OF UTILITIES		SUMP 155	
PLAN AND PROFILE 2 - 42" RCP		CHECKED BY: A. SMITH		DATE: 03/31/21	
REVISIONS		DESIGNED BY: B. GIBSON		R.C.E. NO. 09049	
DESCRIPTION		DRAWN BY: E. JUEVA		DATE: 09/19/20	
DATE		SCALE: 1" = 10'		SCALE AT 1" = 10'	
ELEV.		FIELD BOOK		0000	
MARKED, MEAS. & WISER		SCALE: 1" = 10'		ON ORIGINAL SCALE	
DRAWING ADJUSTS		H. 1" = 10'		DRAWING ADJUSTS	
DATE		V. 1" = 5'		IF THIS DOES NOT	
DATE		SCALE AT 1"		SCALE AT 1"	




NOTES:

- 1 REMOVE AND DISPOSE OF EXISTING 36" WSP AND APPURTENANCES FROM STA -0+56.5 TO STA 1+16.8 PER DETAIL 2/C19
- 2 INSTALL 36" WSP FROM STA -0+56.5 TO STA 0+74.2 PER DETAIL 3/C19
- 3 INSTALL 36" FL X FL KNEE GATE VALVE
- 4 INSTALL COMBINATION ANTI-SIPHON AND AIR RELIEF VALVE PER DETAIL 3/C15
- 5 INSTALL ANTI-SIPHON VALVE PER DETAIL 1/C14
- 6 CONNECT TO OUTFALL STRUCTURE PER DETAIL 1/C18
- 7 CONNECT TO EXISTING STEEL COUPLING
- 8 RECONSTRUCT LEVEE EMBANKMENT WITH LEVEE FILL MATERIAL
- 9 INSTALL RSP PER DETAIL 1/C15
- 10 REPLACE AGGREGATE SURFACE PER DETAIL 4/C18
- 11 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS. THE CONTRACTOR IS RESPONSIBLE TO POthOLE ALL EXISTING UTILITIES IN CONDUCT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO PREVENT ANY DAMAGE TO EXISTING UTILITIES. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.



REVISIONS DESCRIPTION DATE BY		BENCH MARK DESCRIPTION: ELEV. 36.95 MARKED, N.W. & W.S.R.	FIELD BOOK 0000 SCALE: H. 1"=10' V. 1"=5'	ON ORIGINAL SCALE DRAWING ADJUST DIMENSIONS IF THIS DOES NOT SCALE AT 1"		CITY OF SACRAMENTO DEPARTMENT OF UTILITIES CHECKED BY: A. SMITH DESIGNED BY: B. GIBSON DRAWN BY: E. LITKA DATE: 09/19/20 R.C.E. NO. 09852 DATE: 03/31/21	IMPROVEMENT PLANS FOR PUMP OUTFALLS REPLACEMENT PROJECT - B SUMP 155 PLAN AND PROFILE 3 - 36" WSP	65% SUBMITTAL PLAN NO. 155 SHEET 16 OF 30 PN: W14130615
--	--	---	---	--	--	---	---	--











NOTES:  
 1. CUT 48"x7" OPENING IN FIXED ALUMINUM GRATING FOR 42" KNIFE GATE VALVE.  
 2. CUT 42"x7" OPENING IN FIXED ALUMINUM GRATING FOR 36" KNIFE GATE VALVE.

REVISIONS	DATE	BY	ELEV.
DESCRIPTION			



FIELD BOOK  
 0000  
 SCALE:  
 H. 1"=10'  
 V. 1"=10'

CITY OF SACRAMENTO  
 DEPARTMENT OF UTILITIES  
 DESIGNED BY: B. JENSEN  
 DRAWN BY: E. JUEVA  
 CHECKED BY: A. SMITH  
 DATE: 09/15/20  
 DATE: 03/31/21  
 R.C.E. NO. 09849  
 R.C.E. NO. 09852





- NOTES:
1. DETAILS FOR CAST IN PLACE STRUCTURE ARE SHOWN ON STRUCTURAL DRAWINGS. GATE RISER STRUCTURE MAY BE PRECAST AS AN ALTERNATIVE.
  2. HINGED COVER SHALL HAVE TORSION ASSIST PER SPECIFICATION 05 50 00.



PN: W14130615  
 12 19 30  
 19 30  
 19 30  
 19 30

IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - B**  
**SUMP 155 GATE RISER ACCESS DETAIL AND SECTIONS**



**CITY OF SACRAMENTO**  
 DEPARTMENT OF UTILITIES

DESIGNED BY: B. JENSEN  
 DRAWN BY: E. LITZEA  
 CHECKED BY: A. SMITH

DATE: 09/21/20  
 DATE: 09/21/20  
 DATE: 09/21/21


R.C.E. NO. 090849  
 R.C.E. NO. 08652

FIELD BOOK 0000  
 SCALE: ON ORIGINAL SCALE  
 DRAWING ADJUSTED TO ORIGINAL SCALE  
 IF THIS DOES NOT SCALE AT 1"


REVISIONS	DATE	BY	BENCH MARK DESCRIPTION	ELEV.

**GENERAL NOTES:**

1. LINE POSTS SHALL BE MIN 2 1/2" O.D. SPACED AT MAX 10' O.C.
2. HORIZONTAL BRACE AND TOP RAIL SIZE SHALL BE MIN 1 1/2" DIA.
3. END, CORNER, AND GATE POSTS SHALL BE MIN 2 1/2" O.D. WITH 1 1/2" O.D. BRACE RAIL. 3/8" TRUSS ASSEMBLY, 12-GAUGE TENSION BANDS SECURED AT MAX 12" O.C.
4. GATE FRAME SHALL BE FABRICATED FROM 2 1/2" O.D. OR 2 1/2" SQUARE MEMBERS WELDED AT ALL CORNERS.
5. CHAIN LINK FABRIC SHALL BE SECURED TO LINE POST AND TOP RAIL USING 9-GAUGE TIE WIRE SPACED AT MAX 12" O.C.
6. 2-3/8" SHOULDERS EYE BOLT 3" LENGTH TO ANCHOR TENSION WIRE PER 10' SECTION EVENLY SPACED, SECURED WITH HOG RING CAPTURING FENCE FABRIC SYSTEM.
7. PROVIDE "CITY UTILITY FACILITY - NO TRESPASSING" SIGNAGE GATE.




CORNER DETAIL 2  
NTS




RIGHT SWING FOOTING DETAIL 1  
NTS

GATE ANTI-SWING FOOTING DETAIL 1  
NTS



SIDE VIEW DETAIL 4  
NTS



MAINTENANCE GATE DETAIL 5  
NTS

GATE OPERATOR SECTION A  
NTS

8 FOOT HIGH CHAIN LINK FABRIC WITH ANGLED OUTRIGGER AND 3 STRAND BARB WIRE (OUTSIDE) STANDARD FENCING DETAIL

LINE POST DETAIL 3  
NTS

PN: W14130615

IMPROVEMENT PLANS FOR: PUMP OUTFALLS REPLACEMENT PROJECT - B

MISCELLANEOUS VAULT SECURITY DETAILS

65% SUBMITTAL

DATE: 09/21/22

CHECKED BY: A. SMITH

DRAWN BY: E. JUEGA

DATE: 09/21/22

R.C.E. NO. 08502

DATE: 03/31/21

FIELD BOOK NO. 0000

ELEV. \_\_\_\_\_

SCALE: \_\_\_\_\_

H. \_\_\_\_\_


V. \_\_\_\_\_

BENCH MARK DESCRIPTION: \_\_\_\_\_


REVISIONS	DATE	BY

PN: W14130615


PUMP OUTFALLS REPLACEMENT PROJECT



PIPE CONNECTION DETAIL **1**



PIPE CONNECTION DETAIL **2**



OUTFALL STRUCTURE CONNECTION DETAIL **1**



CROWN SURFACING DETAIL **4**

PN: W14130615  
 65% SUBMITTAL

IMPROVEMENT PLANS FOR  
**PUMP OUTFALLS REPLACEMENT PROJECT - B**  
 MISCELLANEOUS DETAILS I




**CITY OF SACRAMENTO**  
 DEPARTMENT OF UTILITIES

DESIGNED BY: B. JENSEN  
 CHECKED BY: A. SMITH  
 DATE: 09/21/22  
 R.C.E. NO. 09852


REVISIONS	DATE	BY	ELEV.

FIELD BOOK: 0000  
 SCALE: 1" = 10'-0"  
 ON ORIGINAL SCALE  
 DRAWING ADJUST  
 IF THIS DOES NOT  
 SCALE AT 1"




- TYPICAL SLOPE BENCHING NOTES:
1. PLACE FILL IN HORIZONTAL LIFTS AGAINST VERTICAL FACES CUT INTO EXISTING LEVEE MATERIAL.
  2. THE BOTTOM OF THE KEY TRENCH SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES AND RECOMPACTED TO 95% MAX DENSITY PER ASTM D698.

SLOPE BENCHING (LANDSIDE OR WATERSIDE) DETAIL **1**



TYPICAL REMOVAL OF EXISTING PIPE DETAIL **2**



INSTALLATION OF NEW PIPE DETAIL **3**

REVISIONS DESCRIPTION DATE BY		FIELD BOOK 0000 SCALE:	BENCH MARK DESCRIPTION: ELEV.	CITY OF SACRAMENTO DEPARTMENT OF UTILITIES	IMPROVEMENT PLANS FOR PUMP OUTFALLS REPLACEMENT PROJECT - B MISCELLANEOUS DETAILS II	65% SUBMITTAL
REVISIONS DESCRIPTION DATE BY		DRAWING ADJUST IF THIS DOES NOT SCALE AT 1"	DRAWN BY: E. JUEVA DATE: 09/19/20	CHECKED BY: A. SMITH R.C.E. NO. 08602 DATE: 03/31/21	DRAWING NO. 102 SHEET 30 PN: W14130615	PN: W14130615






**CITY OF SACRAMENTO**  
DEPARTMENT OF UTILITIES  
REVISIONS: \_\_\_\_\_  
DATE: \_\_\_\_\_  
BENCH MARK DESCRIPTION: \_\_\_\_\_  
ELEV: \_\_\_\_\_

**POST-INSTALLED ANCHORS**  
FIELD BOOK NO. 0000  
SCALE: \_\_\_\_\_  
DATE: \_\_\_\_\_  
REVISIONS: \_\_\_\_\_  
DATE: \_\_\_\_\_  
DESCRIPTION: \_\_\_\_\_


**SHOP DRAWINGS:**  
PRIOR TO FABRICATION, SHOP DRAWINGS SHALL BE SUBMITTED FOR REVIEW BY THE STRUCTURAL ENGINEER.  
1. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR REVIEW BY THE ENGINEER WITH THE ORIGINAL DRAWINGS.  
2. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS BY INDICATING THE MATERIALS TO BE USED FOR THE FABRICATION OF THE STRUCTURE.  
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FABRICATION OF THE STRUCTURE AND SHALL BE RESPONSIBLE FOR THE PERFORMANCE OF THE WORK.  
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FABRICATION OF THE STRUCTURE AND SHALL BE RESPONSIBLE FOR THE PERFORMANCE OF THE WORK.  
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FABRICATION OF THE STRUCTURE AND SHALL BE RESPONSIBLE FOR THE PERFORMANCE OF THE WORK.  
6. ANY DETAIL ON THE SHOP DRAWING THAT DEVIATES FROM THE CONTRACT DOCUMENTS SHALL BE APPROVED BY THE CONTRACTOR AND THE STRUCTURAL ENGINEER.  
7. SHOP DRAWINGS OF CALCULATIONS SHALL BE SUBMITTED FOR REVIEW THAT REQUIRE MORE THAN ONE SHEET. THE THIRD REVIEW WILL NOT BE PROCEED WITHOUT WRITTEN APPROVAL FROM THE STRUCTURAL ENGINEER.  
8. SUBCONTRACTOR OR FABRICATOR FOR THE PREPARATION OF SHOP DRAWINGS SHALL BE RESPONSIBLE FOR THE FABRICATION OF THE STRUCTURE AND SHALL BE RESPONSIBLE FOR THE PERFORMANCE OF THE WORK.

**CONCRETE:**  
1. ALL REINFORCEMENT SHALL BE PLACED IN ACCORDANCE WITH THE CODE FOR GENERAL NOTES.  
2. ALL REINFORCEMENT SHALL BE PLACED IN ACCORDANCE WITH THE CODE FOR GENERAL NOTES.  
3. ALL CONCRETE SHALL BE THOROUGHLY CONSOLIDATED BY SUITABLE MEANS DURING PLACEMENT AND SHALL BE THOROUGHLY CURED BY SUITABLE MEANS DURING PLACEMENT.  
4. THE MINIMUM 28 DAY STRENGTH SHALL BE PER MIX DESIGN SCHEDULE.  
5. CONCRETE AGGREGATES SHALL CONFORM TO ASTM C33.  
6. MINERAL AD MixTURES SHALL COMPLY WITH ASTM C618 CLASS F.  
7. WATER REDUCERS SHALL COMPLY WITH THE FOLLOWING:  
A. TYPE I WATER REDUCERS SHALL COMPLY WITH ASTM C494 TYPE A & B.  
B. TYPE II WATER REDUCERS SHALL COMPLY WITH ASTM C494 TYPE B & D.  
C. RETARDING AD MixTURES SHALL COMPLY WITH ASTM C494 TYPE B & D.  
D. AIR ENTRAINING AD MixTURES SHALL COMPLY WITH ASTM C494 TYPE B & D.  
E. SET RETARDERS SHALL COMPLY WITH ASTM C494 TYPE B & D.  
F. ALL OTHER AD MixTURES SHALL COMPLY WITH ASTM C494 TYPE A & B & D.  
8. THE CONTRACTOR SHALL SUBMIT THE PROPOSED LOCATIONS OF CONSTRUCTION JOINTS AND THE LOCATION OF ALL JOINTS TO THE STRUCTURAL ENGINEER FOR REVIEW PRIOR TO THE FABRICATION OF THE STRUCTURE.  
9. THE CONTRACTOR SHALL SUBMIT THE PROPOSED LOCATIONS OF CONSTRUCTION JOINTS AND THE LOCATION OF ALL JOINTS TO THE STRUCTURAL ENGINEER FOR REVIEW PRIOR TO THE FABRICATION OF THE STRUCTURE.  
10. THE CONTRACTOR SHALL SUBMIT THE PROPOSED LOCATIONS OF CONSTRUCTION JOINTS AND THE LOCATION OF ALL JOINTS TO THE STRUCTURAL ENGINEER FOR REVIEW PRIOR TO THE FABRICATION OF THE STRUCTURE.

**REVISIONS**  
DESCRIPTION: \_\_\_\_\_  
DATE: \_\_\_\_\_  
BY: \_\_\_\_\_  
DATE: \_\_\_\_\_  
BY: \_\_\_\_\_



**CONC PUMP HOSE PLACEMENT DETAIL**  
NO. 5 BAR, W31 OR D31 WIRE, AND SMALLER  
NO. 5 BAR, W31 OR D31 WIRE, AND SMALLER  
NO. 5 BAR, W31 OR D31 WIRE, AND SMALLER



**POST-INSTALLED ANCHOR SCHED**  
MIN. CONC. THICKNESS (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)


**EXPANSION ANCHORS**  
MIN. CONC. THICKNESS (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)

TYPE	USE CLASS	MIN. CONC. THICKNESS (IN)	MIN. CONC. EDGE DISTANCE (IN)	MIN. CONC. EDGE DISTANCE (IN)	MIN. CONC. EDGE DISTANCE (IN)	MIN. CONC. EDGE DISTANCE (IN)	MIN. CONC. EDGE DISTANCE (IN)	MIN. CONC. EDGE DISTANCE (IN)	MIN. CONC. EDGE DISTANCE (IN)	MIN. CONC. EDGE DISTANCE (IN)	MIN. CONC. EDGE DISTANCE (IN)
A	SLAB ON GRADE	4000	150	1.34"	4.31"	.50	152K MAX	152K MAX	152K MAX	152K MAX	152K MAX
B	FOUNDATIONS	4000	150	1.34"	4.31"	.50	152K MAX	152K MAX	152K MAX	152K MAX	152K MAX
C	WALLS	4000	150	1.34"	4.31"	.50	152K MAX	152K MAX	152K MAX	152K MAX	152K MAX
D	ELEVATED SLABS	4000	150	1.34"	4.31"	.50	152K MAX	152K MAX	152K MAX	152K MAX	152K MAX


**MIX DESIGN SCHEDULE**  
STRENGTH CONCRETE CLASS (PSI)  
MIN. CONC. THICKNESS (IN)  
MIN. CONC. EDGE DISTANCE (IN)  
MIN. CONC. EDGE DISTANCE (IN)  
MIN. CONC. EDGE DISTANCE (IN)  
MIN. CONC. EDGE DISTANCE (IN)  
MIN. CONC. EDGE DISTANCE (IN)  
MIN. CONC. EDGE DISTANCE (IN)  
MIN. CONC. EDGE DISTANCE (IN)  
MIN. CONC. EDGE DISTANCE (IN)

**CONCRETE NOTES**  
1. ALL REINFORCEMENT SHALL BE PLACED IN ACCORDANCE WITH THE CODE FOR GENERAL NOTES.  
2. ALL REINFORCEMENT SHALL BE PLACED IN ACCORDANCE WITH THE CODE FOR GENERAL NOTES.  
3. ALL CONCRETE SHALL BE THOROUGHLY CONSOLIDATED BY SUITABLE MEANS DURING PLACEMENT AND SHALL BE THOROUGHLY CURED BY SUITABLE MEANS DURING PLACEMENT.  
4. THE MINIMUM 28 DAY STRENGTH SHALL BE PER MIX DESIGN SCHEDULE.  
5. CONCRETE AGGREGATES SHALL CONFORM TO ASTM C33.  
6. MINERAL AD MixTURES SHALL COMPLY WITH ASTM C618 CLASS F.  
7. WATER REDUCERS SHALL COMPLY WITH THE FOLLOWING:  
A. TYPE I WATER REDUCERS SHALL COMPLY WITH ASTM C494 TYPE A & B.  
B. TYPE II WATER REDUCERS SHALL COMPLY WITH ASTM C494 TYPE B & D.  
C. RETARDING AD MixTURES SHALL COMPLY WITH ASTM C494 TYPE B & D.  
D. AIR ENTRAINING AD MixTURES SHALL COMPLY WITH ASTM C494 TYPE B & D.  
E. SET RETARDERS SHALL COMPLY WITH ASTM C494 TYPE B & D.  
F. ALL OTHER AD MixTURES SHALL COMPLY WITH ASTM C494 TYPE A & B & D.  
8. THE CONTRACTOR SHALL SUBMIT THE PROPOSED LOCATIONS OF CONSTRUCTION JOINTS AND THE LOCATION OF ALL JOINTS TO THE STRUCTURAL ENGINEER FOR REVIEW PRIOR TO THE FABRICATION OF THE STRUCTURE.  
9. THE CONTRACTOR SHALL SUBMIT THE PROPOSED LOCATIONS OF CONSTRUCTION JOINTS AND THE LOCATION OF ALL JOINTS TO THE STRUCTURAL ENGINEER FOR REVIEW PRIOR TO THE FABRICATION OF THE STRUCTURE.


**POST-INSTALLED ANCHORS**  
1. ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS GIVEN IN THE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS (MPI) AND THE RESPECTIVE CONCRETE ANCHORS.  
2. BENCH MARK DESCRIPTION: \_\_\_\_\_  
ELEV: \_\_\_\_\_  
3. SEE ANCHOR SCHEDULES AND DETAILS FOR TENSILE AND TORQUE VALUES, VISUAL CONFIRMATION OF FULL SET IS NOT REQUIRED.  
4. STRENGTH OF CONCRETE PER EDC SECTION 100.3.4.5. AS FOLLOWS:  
A. ANCHORS USED FOR OTHER STRUCTURAL APPLICATIONS SHALL HAVE 100 PERCENT DEVELOPMENT LENGTH.  
B. ANCHORS USED FOR NON-STRUCTURAL APPLICATIONS SUCH AS EQUIPMENT ANCHORS SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
C. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
D. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
E. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
F. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
G. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
H. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
I. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
J. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
K. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
L. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
M. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
N. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
O. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
P. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
Q. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
R. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
S. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
T. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
U. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
V. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
W. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
X. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
Y. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.  
Z. ANCHORS USED FOR CONCRETE REPAIR SHALL HAVE 80 PERCENT DEVELOPMENT LENGTH.




**EXPANSION ANCHORS**  
MIN. CONC. THICKNESS (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)  
MIN. CONC. EDGE DISTANCE (INCH)




8  
3/4" = 1'-0"




6  
CONC WALL CONSTR JT




5  
CONC WALL CONSTR JT AT BOTTOM OF WALL




7  
CONC WALL CONSTR JT AT BOTTOM OF WALL




4  
TYP REINF SPLICED AT INTERSECTIONS OF WALLS & FTGS




3  
SLAB OPG & RE-ENTRANT CORNER




1  
UNFORMED FTG DETAIL




2  
MIN REBAR BENDS



5  
SLAB OPG & RE-ENTRANT CORNER




4  
TYP REINF SPLICED AT INTERSECTIONS OF WALLS & FTGS



3  
TYP REINF DETAIL



2  
MIN REBAR BENDS



3  
TYP REINF DETAIL

TIE & STIRRUP HOOKS REBAR	
#3	3\"/>
#4	4\"/>
#5	5\"/>
#6	6\"/>
#8	8\"/>
#10	10\"/>

BENDS & HOOKS REBAR	
#3	3\"/>
#4	4\"/>
#5	5\"/>
#6	6\"/>
#8	8\"/>
#10	10\"/>

FOOTNOTES:  
 1.  $\phi$  = DIA OF REIN  
 2.  $\phi$  = DIA OF REBAR

**CYS**  
 CIVIL & STRUCTURAL ENGINEERING  
 1710 UNIVERSITY AVENUE, SUITE 100  
 SACRAMENTO, CA 95811  
 (916) 441-1111  
 CYS Job No. 20054

**SEAL**  
 REGISTERED PROFESSIONAL ENGINEER  
 CIVIL ENGINEERING  
 STATE OF CALIFORNIA  
 NO. 50302  
 EXPIRES 01/31/2012

THESE DRAWINGS ARE PRELIMINARY AND NOT TO BE USED FOR CONSTRUCTION UNLESS CHANGES & CORRECTIONS ARE MADE TO THE DRAWING AS NOTED.

65% SUBMITTAL  
 DATE: 03/15/2011  
 TIME: 11:25 AM  
 SHEET: 26 OF 30  
 PLAN: W14130615

IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - B**  
 TYPICAL DETAILS - CONCRETE

PRELIMINARY

**CITY OF SACRAMENTO**  
 DEPARTMENT OF UTILITIES

DESIGNED BY: B. JENSEN  
 CHECKED BY: A. SMITH  
 DATE: 03/15/22  
 R.C.E. NO. 038612

FIELD BOOK: 0000  
 SCALE: 1" = 1'-0"  
 ON ORIGINAL SCALE  
 DRAWING ADJUSTED TO THIS SCALE  
 IF THIS DOES NOT SCALE AT 1"




REVISIONS	DESCRIPTION	DATE	BY

BENCH MARK DESCRIPTION: ELEV. \_\_\_\_\_

PN: W14130615  
 PUMP OUTFALLS REPLACEMENT PROJECT

**NOTES**

1. SEE DWG S1 & S2 FOR GENERAL NOTES.
2. SEE DWG S3 FOR TYPICAL DETAILS.
3. SEE DWG S6 FOR SECTIONS.
4. SEE OTHER CONSULTANT DWGS FOR UTILITIES THAT WILL AFFECT FITS & COMPLY W/ TYPICAL DETAILS.



**CYS**  
 CIVIL ENGINEERING  
 1000 J STREET, SUITE 200  
 SACRAMENTO, CA 95811  
 (916) 441-1111  
 www.cysinc.com

CYS Job No. 20054  
 THESE DRAWINGS ARE PRELIMINARY  
 AND ARE SUBJECT TO CHANGE BY  
 THE COURSE OF RECORD.

PN: W14130615  
 SHEET NO. 26  
 OF 30  
 65% SUBMITTAL

**IMPROVEMENT PLANS FOR:  
 PUMP OUTFALLS REPLACEMENT PROJECT - B  
 FOUNDATION & FRAMING PLANS  
 SUMP 155**

PRELIMINARY

**CITY OF SACRAMENTO  
 DEPARTMENT OF UTILITIES**


DESIGNED BY: B. JENSEN  
 CHECKED BY: A. SMITH  
 DATE: 03/15/22  
 R.C.E. NO. 038612

DRAWN BY: E. JUTERA  
 DATE: 09/15/20  
 R.C.E. NO. 038649

FIELD BOOK 0000  
 SCALE: 1" = 3/8" = 1'-0"  
 ON ORIGINAL SCALE  
 DRAWING ADJUSTS  
 TO ORIGINAL SCALE  
 IF THIS DOES NOT  
 SCALE AT 1"

NO.	REVISIONS	DATE	BY	ELEV.
	DESCRIPTION			






HORIZ REINF SCHED	
DEPTH	REINF "B"
1	#5 @ 12" OC
2	#5 @ 8" OC
3	#5 @ 12" OC
4	#6 @ 8" OC

SUMP 155  
 WALL ELEVATION  
 1/2" = 1'-0"



**CYS**  
 CIVIL ENGINEER  
 10058  
 01/31/21  
 THESE DRAWINGS ARE PRELIMINARY  
 AND ARE NOT TO BE USED FOR  
 THE CONSTRUCTION OF RECORD.

REVISIONS DESCRIPTION DATE BY		FIELD BOOK 0000 SCALE:	1" ON ORIGINAL SCALE DRAWING ADJUSTED TO THIS SCALE IF THIS DOES NOT SCALE AT 1"	CITY OF SACRAMENTO DEPARTMENT OF UTILITIES DESIGNED BY: E. JUREVA CHECKED BY: A. SMITH DATE: 09/15/20 R.C.E. NO. 09849 DATE: 03/15/22 R.C.E. NO. 09812	PRELIMINARY IMPROVEMENT PLANS FOR: PUMP OUTFALLS REPLACEMENT PROJECT - B WALL ELEVATIONS & SECTIONS SUMP 155	65% SUBMITTAL DATE: 03/28/22 SHEET: 30 P.N: W14130615
-------------------------------------	--	------------------------------	---	---	--	--



65% SUBMITTAL  
 SHEET NO. 37  
 OF 37  
 P.N. W14130615

**PUMP OUTFALLS REPLACEMENT PROJECT - B**  
**DETAILS**

PRELIMINARY

CITY OF SACRAMENTO  
 DEPARTMENT OF UTILITIES

DESIGNED BY: E. JUREA  
 CHECKED BY: B. JENSEN  
 DATE: 09/15/20  
 R.C.E. NO. 03849

DESIGNED BY: A. SMITH  
 CHECKED BY: A. SMITH  
 DATE: 03/17/21  
 R.C.E. NO. 08612

NO.	REVISIONS	DATE	BY	ELEV.

FIELD BOOK  
 SCALE: 0000  
 ON ORIGINAL SCALE  
 DRAWING ADJUST  
 CALCULATIONS  
 IF THIS DOES NOT  
 SCALE AT 1"

**Attachment C – Categorical Permission Checklist**  
*(Pressurized Pipe)*

## Categorical Permission Alteration Description – 16. Pressurized Pipes

The categorical permission covers the installation, modification, and replacement of pressurized pipes that comply with certain terms and conditions. Particularly, all pressurized pipes must be designed and installed in accordance with current USACE standards. The total area of disturbance, including staging and access areas, must not exceed 5 acres. Pressurized pipes must also be designed to prevent, (1) flotation from uplift, (2) scour or erosion, (3) damage from debris on the waterside, particularly during flood flows, (4) leakage, (5) seepage along proposed pipes, (6) corrosion, and (7) damage from vehicular loads.

All new pressurized pipes should go up and over the levee DWSE. Pressurized pipes passing over or within the freeboard zone of a levee (i.e., above the levee DWSE), should be made of metal, preferably ductile iron or coated steel, suitable for use with flexible couplings.

Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM). Pipes that pass above the DWSE must have 2 feet of cover (low permeability or CLSM) to prevent damage by vehicles and equipment. Cover material on the levee crown must be placed at a ratio of 10H:1V, in the upstream/downstream direction of the levee. Pipes on the sides of the levee should be covered with a minimum of 1 foot of low permeability material, compacted in 4- to 6-inch lifts or CLSM to protect them from debris during high water (waterside) or to keep them from interfering with or being damaged by operations or maintenance of the levee (landside). Fill must be free of deleterious materials and construction debris and placed in 4- to 6-inch-thick loose lifts and compacted to not less than 95% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D698 (USACE preferred method), or alternately, 90% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D1557. At the sponsor and levee maintaining agency's discretion, pipes on the levee slopes may be left exposed.

Only suitable material must be used as levee fill materials. Fill must be free from: roots and other organic matter, contaminated hazardous or toxic material, trash, debris, and frozen materials. Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve.

Pressurized pipes terminating in the channel require a positive closure device on the waterside that is accessible from the levee crown. Pressurized pipes transporting product completely across or through the federal project easement require positive closure devices located landward of any levees and channel. The positive closure device shall be located within one mile on both sides of the federal project. If the invert of the pipe is over the levee crown, the combination of a pump station on the waterside and a siphon breaker is considered an appropriate means of closure. Pipes located within or beneath a levee must have watertight joints that can accommodate movements resulting from settlement.

All pressurized pipes that cross the levee foundation at a depth less than or equal to two times the height of the levee should be evaluated for uplift. Pipes crossing the surface of the levee must be designed to counteract buoyancy forces of an empty pipe, with water at the DWSE.

Pressurized pipelines running parallel to flood risk management projects should be located at least 15 feet beyond the levee toes. Pipe location and orientation must be clearly marked in the field so they can be easily identified for flood fighting crews.

If appropriate, the requester should prepare an excavation plan demonstrating the effects of excavation on the stability of the embankments.

The site layout should provide adequate access for maintenance vehicles to refill fuel tanks and service/replace pumps, generators, etc. Pressurized pipes must also allow easy access for rapid closure in the event of leakage or rupture.

No plastic pipes (HDPE, PVC, etc.) are allowed in the levee embankment or its foundation unless they are embedded in concrete.

If an electrochemical or chemical reaction between the substratum or groundwater and pipe materials is expected, the pipe and pipe couplings must be protected.

After installation of pressurized pipes, the requester must demonstrate 0% pipe leakage in pipes in the levee. Pipes must be pressure tested to industry standards. Pipes must be regularly inspected, including the interior, if possible, looking for signs of maintenance issues. If an inspection indicates corrosion, alignment sag or heave, or separation at joints, corrective action must be taken as soon as possible to avoid failure. Pipe valves must be periodically inspected and pressure tested to ensure that they are functioning properly. Pressure tests must show no significant loss in pressure. Leaks and other deficiencies must be addressed as soon as possible. All replacement parts must be of equivalent or better quality than those being replaced.

The preferred method for abandoning pipes that pass through or over a levee is complete removal. If removal is not feasible, the pipes and other structures may be filled with a cement/bentonite-based grout or flowable fill. The grout needs to be sufficiently fluid so that it can be pumped to completely fill the pipe leaving no voids.

### Categorical Permission Alteration Checklist – 16. Pressurized Pipes

*Note:* The following checklist is intended for planning purposes only, and includes information that USACE reviewers look for when considering a Section 408 request for pressurized pipes under the Categorical Permission. To be reviewed under the Categorical Permission, the proposed project must adhere to all requirements of the Categorical Permission, including the full alteration description (see previous page). The plans and narrative project description should reflect this information.

1.	<input type="checkbox"/> New Construction <input checked="" type="checkbox"/> Replacement <input type="checkbox"/> Modification <input type="checkbox"/> Authorize Existing		
2.	Maximum total area of disturbance is 5 acres:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Area of disturbance is 0.07 acre.</u>		
3.	Pipes are designed to prevent flotation from uplift, scour or erosion, damage from debris on the waterside (particularly during flood flows), seepage along proposed pipes, corrosion, leakage, and damage from vehicular loads:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
4.	Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM):	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
5.	Pipes passing over the DWSE will have a minimum of 2 feet of cover (low permeability or CLSM):	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to profiles on sheets 14-16 in Bid Set B</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
6.	If material must be added to the levee crown, the added material must be sloped at a ratio of 10H:1V horizontal to vertical, in the upstream/downstream direction to prevent a “speed bump” effect and facilitate vehicle access:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
7.	Fill will be compacted to at least 95% of maximum density as determined by ASTM D698, between -2 and +3% of optimum moisture content:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.6B.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
8.	Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 2.2A.</u>		
	Comment:		
9.	All fill will be free of organics or other inappropriate materials:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.9.B.1.6.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		

10.	Pipes terminating in the channel have a positive closure device on the waterside that is accessible from the levee crown:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to profiles on Sheets 14-16 and Detail 6 on Sheet 18 in Bid Set B</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
11.	Pipes transporting product completely across the federal project have a positive closure devices located within 1 mile on both sides of the federal project:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
12.	Pipes located within or beneath a levee have watertight joints that can accommodate movements resulting from settlement:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 2 on Sheet 40</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
13.	Pipes crossing the surface of the levee are designed to counteract buoyancy forces of an empty pipe, with water at the DWSE:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
14.	Pipe location and orientation will be clearly marked in the field:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Pipe location and orientation can be identified by vault structure and outfall location</u>		
15.	Pipes will allow easy access for rapid closure:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Positive valve closures on the levee crest will ensure easy access for rapid closure</u>		
16.	Plastic pipes within the levee embankment or its foundation are embedded in concrete:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
17.	If a chemical or electrochemical reaction is expected, the pipe and pipe couplings must be protected:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
18.	Any work within the levee embankment or foundation?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Detail 1 on Sheet 22 in Bid Set B</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
19.	Any work ≤50 feet beneath the channel invert?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
20.	Hydraulic blockage calculation ≥1%?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Rip Rap cross-sectional area below ordinary high watermark is anticipated to be significantly less than the cross-sectional area of the American River and therefore negligible.</u>		
21.	Hydraulic model used for hydraulic analysis?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
		N/A <input checked="" type="checkbox"/>	

**Reference:** [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]

**Comment:** [ Click to enter rationale, explanation, unique situation, etc. ]

– For Official Use Only below this line –

*Comment*

**CP Eligibility Review**

<u>Yes</u>	<u>No</u>	<u>Add'l. Info Requested</u>		
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Environmental Reviewer: _____	Date: <small>Click date</small> _____
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Engineering Reviewer: _____	Date: <small>Click date</small> _____



**Attachment D – Categorical Permission Checklist**  
*(Gravity Pipe)*

### **Categorical Permission Alteration Description – 13. Gravity Pipes**

The categorical permission covers the installation, modification, and replacement of gravity pipes and culverts that comply with certain terms and conditions. The total area of disturbance, including staging and access areas, must not exceed 5 acres.

Generally, cast-in-place reinforced concrete pipes are preferable for gravity lines where considerable settlement is expected. No plastic pipes are allowed in the levee embankment or its foundation unless they are embedded in concrete or encased in a steel conduit with the annular space completely grouted.

Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM).

Suitable material must be used as levee fill materials. Fill must be free from: roots and other organic matter, contaminated hazardous or toxic material, trash, debris, and frozen materials. Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve.

Fill must be free of deleterious materials and construction debris and placed in 4- to 6-inch-thick loose lifts and compacted to not less than 95% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D698 (USACE preferred method), or alternately, 90% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D1557.

Pipe joints must have sufficient flexibility to adjust under expected settlement and stretching of the pipe. Pipes should be designed to counteract uplift of the empty pipe at the design high water stage. If a chemical or electrochemical reaction is expected, the pipe and pipe couplings must be protected.

All new and existing gravity-flowing culverts must have a flap gate on the waterside end with provisions for positive closure (slide gate or sluice gate). The slide gate or sluice gate should be housed in a gatewell at the waterside edge of the levee crown to provide access.

Internal inspections must occur to ensure the pipes are in good condition. Video inspection of the internal condition of the pipe or pressure testing should be undertaken at least once every five years. Valves and gates should be periodically inspected and tested to ensure they are functioning properly. If the inspection indicates corrosion, alignment sag or heave, or separation at joints, corrective action must be taken as soon as possible. In most cases, once a pipe begins to oval or flatten at the crown or has lost more than 5% of its original interior height, it should be replaced.

Periodically, debris must be removed and corrosion or other damage on trash screens repaired.

If maintenance indicates that pipe replacement is necessary, all replacement parts must be of equivalent or better quality than those to be replaced. All repairs must restore pipes and associated equipment to the standards of the original design, or better.

### Categorical Permission Alteration Checklist – 13. Gravity Pipes

*Note:* The following checklist is intended for planning purposes only, and includes information that USACE reviewers look for when considering a Section 408 request for gravity pipes under the Categorical Permission. To be reviewed under the Categorical Permission, the proposed project must adhere to all requirements of the Categorical Permission, including the full alteration description (see previous page). The plans and narrative project description should reflect this information.

1.	<input type="checkbox"/> New Installation	<input checked="" type="checkbox"/> Replacement	<input type="checkbox"/> Modification	<input type="checkbox"/> Authorize Existing
2.	Maximum total area of disturbance is 5 acres: <input checked="" type="checkbox"/>			
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: <u>Area of disturbance is 0.07 acre.</u>			
3.	Plastic pipes within the levee embankment or foundation will be embedded in concrete or encased in a steel conduit with the annular space completely grouted: Yes <input type="checkbox"/> N/A <input checked="" type="checkbox"/>			
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
4.	Pipe joints will have sufficient flexibility to adjust under the expected settlement and stretching of the pipe: <input checked="" type="checkbox"/>			
	Reference: <u>Detail 3 on Sheet 21 (Bid Set B)</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
5.	Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM): <input checked="" type="checkbox"/>			
	Reference: <u>Refer to detail 3 on sheet 41</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
6.	Fill will be compacted to at least 95% of maximum density as determined by ASTM D698, between -2 and +3% of optimum moisture content: <input checked="" type="checkbox"/>			
	Reference: <u>Refer to Spec section 31 00 00 3.6B.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
7.	Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve: <input checked="" type="checkbox"/>			
	Reference: <u>Refer to Spec section 31 00 00 2.2A.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
8.	All fill will be free of organics or other inappropriate materials: <input checked="" type="checkbox"/>			
	Reference: <u>Refer to Spec section 31 00 00 3.9.B.1.6.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
9.	New and existing gravity-flowing culverts will have a flap gate on the waterside end with provisions for positive closure: Yes <input checked="" type="checkbox"/> N/A <input type="checkbox"/>			
	Reference: <u>Detail 1 on Sheet 21 in Bid Set B</u>			
	Comment: <u>42" CMP pipe</u>			

- Continued on next page -

10.	If a chemical or electrochemical reaction is expected, the pipe and pipe couplings must be protected:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: <a href="#">[ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]</a>		
	Comment: <a href="#">[ Click to enter rationale, explanation, unique situation, etc. ]</a>		
11.	Any work within the levee embankment or foundation?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Reference: <a href="#">[ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]</a>		
	Comment: <a href="#">[ Click to enter rationale, explanation, unique situation, etc. ]</a>		
12.	Hydraulic blockage calculation $\geq 1\%$ ?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/> N/A <input type="checkbox"/>
	Reference: <a href="#">[ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]</a>		
	Comment: <b>Rip Rap cross-sectional area below ordinary high watermark is anticipated to be significantly less than the cross-sectional area of the American River and therefore negligible.</b>		
13.	Hydraulic model used for hydraulic analysis?	Yes <input type="checkbox"/>	No <input type="checkbox"/> N/A <input checked="" type="checkbox"/>
	Reference: <a href="#">[ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]</a>		
	Comment: <a href="#">[ Click to enter rationale, explanation, unique situation, etc. ]</a>		

– For Official Use Only below this line –

*Comment*

**CP Eligibility Review**

<u>Yes</u>	<u>No</u>	<u>Add'l. Info Requested</u>		
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Environmental Reviewer: _____	Date: <a href="#">[Click date]</a>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Engineering Reviewer: _____	Date: <a href="#">[Click date]</a>

**American River Flood Control District  
Central Valley Flood Protection Board Permit Application  
Sump 159-1 Modifications (City of Sacramento)  
Staff Report**

**Discussion:**

The City of Sacramento submitted this encroachment permit application to modify facilities at their Sump 159 Pump Station. The work proposed is to remove and replace approximately 4 ft of one (1) 12" welded steel pipe at the pump outfall structure.

Sump 159 is located adjacent to the Arcade Creek South Levee and just west of the bike trail bridge crossing.

This modification is required to upgrade the pipe outfall system at the pump station. Recent work conducted by SAFCA under the North Area Streams Project replaced only the segments of pipe that crossed through the levee. This work will complete the upgrade to the facility by replacing the pipe outfall section and flap gate.

This modification will be a routine construction installation and does not present a considerable engineering challenge. It is not anticipated that this work will pose significant operations and maintenance impacts to the District.

**Recommendation:**

The General Manager recommends that the Board of Trustees endorse the CVFPB permit application.

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

**Application No.** \_\_\_\_\_  
(For Office Use Only)

1. Description of proposed work being specific to include all items that will be covered under the issued permit.  
Sump 159 Modifications: Remove and replace approximately 4 ft of one (1) 12" welded steel pipe at the pump outfall structure.

2. Project  
Location: Sacramento County, in Section See Attachment A  
Township: See Attachment A (N) (S), Range: See Attachment A (E) (W), M. D. B. & M.  
Latitude: 38.62504 Longitude: -121.44762  
Stream: Arcade Creek, Levee: Left Bank Designated Floodway: Arcade Creek  
APN: See Attachment A

3. Raymond Kong, PE of 1395 35th Ave  
Name of Applicant / Land Owner Address  
Sacramento CA 95822 (916) 808-1435  
City State Zip Code Telephone Number  
RKong@cityofsacramento.org  
E-mail

4. Ashley Smith, PE of Peterson Brustad Inc.  
Name of Applicant's Representative Company  
Folsom CA 95630 (916) 608-2212 x 123  
City State Zip Code Telephone Number  
asmith@pbieng.com  
E-mail

5. Endorsement of the proposed project from the Local Maintaining Agency (LMA):

We, the Trustees of American River Flood Control District approve this plan, subject to the following conditions:  
Name of LMA

Conditions listed on back of this form       Conditions Attached       No Conditions

\_\_\_\_\_  
Trustee Date      Trustee Date  
\_\_\_\_\_  
Trustee Date      Trustee Date

### APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD ENCROACHMENT PERMIT

6. Names and addresses of adjacent property owners sharing a common boundary with the land upon which the contents of this application apply. If additional space is required, list names and addresses on back of the application form or an attached sheet.

Name	Address	Zip Code
<u>See Attachment A</u>		

7. Has an environmental determination been made of the proposed work under the California Environmental Quality Act of 1970?  Yes  No  Pending

If yes or pending, give the name and address of the lead agency and State Clearinghouse Number:

City of Sacramento  
1395 35th Avenue  
Sacramento, CA 95822  
SCH No. Pending

8. When is the project scheduled for construction? April 2021

9. Please check exhibits accompanying this application.

- A.  Regional and vicinity maps showing the location of the proposed work.
- B.  Drawings showing plan view(s) of the proposed work to include map scale.
- C.  Drawings showing the cross section dimensions and elevations (vertical datum?) of levees, berms, stream banks, flood plain,
- D.  Drawings showing the profile elevations (vertical datum?) of levees, berms, flood plain, low flow, etc.
- E.  A minimum of four photographs depicting the project site.

\_\_\_\_\_  
Signature of Applicant Date

Include any additional information:  
A summary of the Project and a description of the proposed methods are provided in Attachment A. Attachment B includes relevant plan sheets which are an excerpt from a larger plan set. Attachment C includes the categorical permission checklist. The intent of this application is to modify the existing encroachment permit. The existing Permit number for Sump 159 is 4417-1.

**Attachment A – Summary of Proposed Work**



**CITY OF SACRAMENTO PUMP OUTFALLS PROJECT:  
CENTRAL VALLEY FLOOD PROTECTION BOARD ENCROACHMENT PERMIT**

**SUMMARY OF PROPOSED WORK**

September 15, 2020

**INTRODUCTION**

As mandated by the Sacramento Area Flood Control Agency (SAFCA) and the U.S. Army Corps of Engineers (USACE), sump station outfalls that penetrate and cross major levees are inspected on a 5-year cycle. The project entails the complete replacement of the pump discharge for three (3) drainage sump station facilities and partial replacement of the pump discharge pipe for five (5) drainage sump station facilities. The following information pertains to a partial replacement sump (Sump 159) that will need an updated Encroachment Permit from the CVFPB.

**APN Parcels**

Sump	Existing Permit #	APN
159	4417-1	263-0260-010-0000, 263-0010-016-0000

**ADJACENT PARCELS**

All of the parcels adjacent to the Sump to be modified are listed in the table presented below as provided by the Sacramento County Assessor's Office.

APN	Address	Owner	Owner Address	City	Zip
250-0270-009-0000	ALTOS AVE	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
250-0270-012-0000	ALTOS AVE	UNION PACIFIC RAILROAD CO	1400 DOUGLAS ST 1640	OMAHA	68179
251-0291-011-0000	RIO LINDA BLVD	AMERICAN RIVER FLOOD CONTROL DIST	165 COMMERCE CIR UNIT D	SACRAMENTO	95815
251-0291-012-0000	3201 RIO LINDA BLVD	CONIGLIO 2007 REVOCABLE TRUST	3201 RIO LINDA BLVD	SACRAMENTO	95815
251-0291-018-0000	RIO LINDA BLVD	SACTO & SAN JOAQUIN DRAINAGE DIS	3310 EL CAMINO AVE	SACRAMENTO	95821
263-0010-015-0000	FAIRBANKS AVE	SACTO & SAN JOAQUIN DRAINAGE DIS	3310 EL CAMINO AVE	SACRAMENTO	95821

263-0041-019-0000	813 ARCADE BLVD	SHARON LEE NAYLOR	813 ARCADE BLVD	SACRAMENTO	95815
263-0046-001-0000	3148 ALTOS AVE	IVAN PARRA	3148 ALTOS AVE	SACRAMENTO	95815
263-0046-002-0000	808 ARCADE BLVD	RUBEN O LUA	808 ARCADE BLVD	SACRAMENTO	95815
263-0260-020-0000	TRACTION AVE	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
265-0011-001-0000	3141 RIO LINDA BLVD	S M U D	PO BOX 15830	SACRAMENTO	95852
265-0011-002-0000	3139 RIO LINDA BLVD	JAMES RODARAKIS	205 ARCADE BLVD	SACRAMENTO	95815

### **TOWNSHIP AND RANGE INFORMATION**

Note that gaps exist in Townships and Ranges within the project area. Land not covered by T9N R5E has been in private ownership since before California joined the United States and therefore is not part of the Township and Range system, which was a survey of federal lands.

### **SITE PHOTOGRAPHS**

Attached to this Summary of Proposed Work are photographs showing levee and channel areas representative of proposed work sites.



Figure 1: Sump 159 looking North West



Figure 2: Landside slope near Sump 159





Figure 3: Siphon breaker vaults on levee crest near Sump 159



Figure 4: View looking southwest toward the Sump 159 outfall into Arcade Creek

**Attachment B – Plan Sheets**

*(Excerpt from larger plan set for Pump Outfalls Replacement Project – A)*



PN: W14130615

PN: W14130615

65% SUBMITTAL

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.65
DESCRIPTION:		
CP/RBR&CAP		

FIELD BOOK	0000
SCALE:	1" = 10'
H: H:	
V: V:	

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**



DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 159**  
**DEMO PLAN**

DWG. NO.	C30
SHEET	33
OF	47





PN: W14130615

PN: W14130615

65% SUBMITTAL

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.65
DESCRIPTION:		
CP/RBR&CAP		


FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE	DRAWING ADJUST
SCALED DIMENSIONS	IF THIS DOES NOT
SCALE AT 1"	

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY:	E. TUTEJA	DESIGNED BY:	B. JENSEN
DATE:	09/15/20	R.C.E. NO.	C90949 DATE: 03/31/22
CHECKED BY:	A. SMITH	R.C.E. NO.	C86512 DATE: 03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 159**  
**SITE PLAN**

DWG. NO.	C31
SHEET	34
OF	47
Page 13	



- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 12" WSP AND APPURTENANCES FROM STA 0+62.7 TO STA 0+65.6 PER DETAIL 2/C38
  - 2 INSTALL 12" WSP FROM STA 0+62.7 TO STA 0+65.6 PER DETAIL 3/C38
  - 3 CONNECT TO EXISTING STEEL COUPLING
  - 4 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 5 CONNECT TO EXISTING PIPE PER DETAIL 3/C37
  - 6 REMOVE AND SALVAGE STEEL COUPLING
  - 7 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV. 44.65
DESCRIPTION:	
CP/RBR&CAP	

FIELD BOOK	0000
SCALE:	
H: H:	
V: V:	

**CITY OF SACRAMENTO**  
**DEPARTMENT OF UTILITIES**

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"


DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 159**  
**PLAN AND PROFILE 3 - 12" WSP**

65% SUBMITTAL

DWG. NO.	C34
SHEET	37
OF	47




OUTFALL STRUCTURE CONNECTION DETAIL **1**  
NTS



NOTES:  
1. PROVIDE HAND HOLES AS NEEDED TO INSTALL FIELD LINING. WELD HAND HOLE CLOSED WHEN COMPLETE. HAND HOLES NOT REQUIRED AT OUTLETS IF ACCESSIBLE THROUGH FLAP GATE.

NEW OR EXISTING STEEL  
PIPE CONNECTION DETAIL **2**  
NTS



TRENCH SECTION AND SEQUENCING **3**  
NTS

NOTES:


- CONTRACTOR SHALL REPLACE EXISTING PAVEMENT IN KIND. BASED ON LIMITED FIELD INVESTIGATIONS, EXISTING PAVEMENT SECTION ARE ASSUMED 2" AC ON 6" AB
- THE OWNER AND THE CONTRACTOR SHALL JOINTLY DETERMINE THE FINAL WIDTH AND LENGTH OF THE BIKE PATH CROSSING BASED ON FIELD CONDITIONS AND CONSTRUCTION PROCEDURES.
- CONTRACTOR SHALL REMOVE EXISTING BIKE PATH AS NEEDED TO CONSTRUCT PROPOSED PIPE. IMPACTED AREAS SHALL BE REPLACED IN ACCORDANCE WITH CITY OF SACRAMENTO STANDARD DETAIL T-21

CONSTRUCTION SEQUENCE:

- STEP 1: SAWCUT LIMITS 09F TRENCH EXCAVATION TO CLEAN CUT LIMITS. REMOVE EXISTING ASPHALT CONCRETE TO THE MIN EXTENT REQUIRED TO CONSTRUCT PROPOSED PIPE. PROPOSED PIPE SHALL BE CONSTRUCTED A MIN OF 2' FROM FG. TRENCH PLATES SHALL BE PROVIDED TO MAINTAIN ACCESS OVER CUTOFF WALL DURING CONSTRUCTION IN ACCORDANCE WITH THE SPECIFICATIONS.
- STEP 2: PLACE AB TO MATCH EXISTING THICKNESS. PLACE AC OVERLAY FROM EXTENT APPROVED BY AGENCY AND CONTRACTOR TO LIMITS OF SAWCUT. PROVIDE PAVEMENT MARKING AND STRIPING TO MATCH EXISTING.

LEGEND:

EXISTING	PROPOSED
GRIND AND OVERLAY ASPHALT CONCRETE	
AGGREGATE BASE (AB)	
ASPHALT CONCRETE (AC)	



CROWN SURFACING DETAIL **4**  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615


REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.
DESCRIPTION:	

FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"	

H:	
V:	

<b>CITY OF SACRAMENTO DEPARTMENT OF UTILITIES</b>			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
MISCELLANEOUS DETAILS I

65% SUBMITTAL

DWG. NO.	C37
SHEET	40
OF	47


PN: W14130615




TYPICAL SLOPE BENCHING NOTES:

1. PLACE FILL IN HORIZONTAL LIFTS AGAINST VERTICAL FACES CUT INTO EXISTING LEVEE MATERIAL.
2. THE BOTTOM OF THE KEY TRENCH SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES AND RECOMPACTED TO 95% MAX DENSITY PER ASTM D698.

SLOPE BENCHING (LANDSIDE OR WATERSIDE) DETAIL 1  
NTS



TYPICAL REMOVAL OF EXISTING PIPE DETAIL 2  
NTS



INSTALLATION OF NEW PIPE DETAIL 3  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615


REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK DESCRIPTION:	ELEV. _____

FIELD BOOK	0000
SCALE:	1" = _____
H:	
V:	

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

<b>CITY OF SACRAMENTO</b> <b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**MISCELLANEOUS DETAILS II**

65% SUBMITTAL

PN: W14130615	DWG. NO. C38
	SHEET 41 OF 47
	Page 16

**Attachment C – Categorical Permission Checklist**

## Categorical Permission Alteration Description – 16. Pressurized Pipes

The categorical permission covers the installation, modification, and replacement of pressurized pipes that comply with certain terms and conditions. Particularly, all pressurized pipes must be designed and installed in accordance with current USACE standards. The total area of disturbance, including staging and access areas, must not exceed 5 acres. Pressurized pipes must also be designed to prevent, (1) flotation from uplift, (2) scour or erosion, (3) damage from debris on the waterside, particularly during flood flows, (4) leakage, (5) seepage along proposed pipes, (6) corrosion, and (7) damage from vehicular loads.

All new pressurized pipes should go up and over the levee DWSE. Pressurized pipes passing over or within the freeboard zone of a levee (i.e., above the levee DWSE), should be made of metal, preferably ductile iron or coated steel, suitable for use with flexible couplings.

Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM). Pipes that pass above the DWSE must have 2 feet of cover (low permeability or CLSM) to prevent damage by vehicles and equipment. Cover material on the levee crown must be placed at a ratio of 10H:1V, in the upstream/downstream direction of the levee. Pipes on the sides of the levee should be covered with a minimum of 1 foot of low permeability material, compacted in 4- to 6-inch lifts or CLSM to protect them from debris during high water (waterside) or to keep them from interfering with or being damaged by operations or maintenance of the levee (landside). Fill must be free of deleterious materials and construction debris and placed in 4- to 6-inch-thick loose lifts and compacted to not less than 95% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D698 (USACE preferred method), or alternately, 90% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D1557. At the sponsor and levee maintaining agency's discretion, pipes on the levee slopes may be left exposed.

Only suitable material must be used as levee fill materials. Fill must be free from: roots and other organic matter, contaminated hazardous or toxic material, trash, debris, and frozen materials. Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve.

Pressurized pipes terminating in the channel require a positive closure device on the waterside that is accessible from the levee crown. Pressurized pipes transporting product completely across or through the federal project easement require positive closure devices located landward of any levees and channel. The positive closure device shall be located within one mile on both sides of the federal project. If the invert of the pipe is over the levee crown, the combination of a pump station on the waterside and a siphon breaker is considered an appropriate means of closure. Pipes located within or beneath a levee must have watertight joints that can accommodate movements resulting from settlement.

All pressurized pipes that cross the levee foundation at a depth less than or equal to two times the height of the levee should be evaluated for uplift. Pipes crossing the surface of the levee must be designed to counteract buoyancy forces of an empty pipe, with water at the DWSE.

Pressurized pipelines running parallel to flood risk management projects should be located at least 15 feet beyond the levee toes. Pipe location and orientation must be clearly marked in the field so they can be easily identified for flood fighting crews.

If appropriate, the requester should prepare an excavation plan demonstrating the effects of excavation on the stability of the embankments.

The site layout should provide adequate access for maintenance vehicles to refill fuel tanks and service/replace pumps, generators, etc. Pressurized pipes must also allow easy access for rapid closure in the event of leakage or rupture.

No plastic pipes (HDPE, PVC, etc.) are allowed in the levee embankment or its foundation unless they are embedded in concrete.

If an electrochemical or chemical reaction between the substratum or groundwater and pipe materials is expected, the pipe and pipe couplings must be protected.

After installation of pressurized pipes, the requester must demonstrate 0% pipe leakage in pipes in the levee. Pipes must be pressure tested to industry standards. Pipes must be regularly inspected, including the interior, if possible, looking for signs of maintenance issues. If an inspection indicates corrosion, alignment sag or heave, or separation at joints, corrective action must be taken as soon as possible to avoid failure. Pipe valves must be periodically inspected and pressure tested to ensure that they are functioning properly. Pressure tests must show no significant loss in pressure. Leaks and other deficiencies must be addressed as soon as possible. All replacement parts must be of equivalent or better quality than those being replaced.

The preferred method for abandoning pipes that pass through or over a levee is complete removal. If removal is not feasible, the pipes and other structures may be filled with a cement/bentonite-based grout or flowable fill. The grout needs to be sufficiently fluid so that it can be pumped to completely fill the pipe leaving no voids.

### Categorical Permission Alteration Checklist – 16. Pressurized Pipes

*Note:* The following checklist is intended for planning purposes only, and includes information that USACE reviewers look for when considering a Section 408 request for pressurized pipes under the Categorical Permission. To be reviewed under the Categorical Permission, the proposed project must adhere to all requirements of the Categorical Permission, including the full alteration description (see previous page). The plans and narrative project description should reflect this information.

1.	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Replacement	<input type="checkbox"/> Modification	<input type="checkbox"/> Authorize Existing
2.	Maximum total area of disturbance is 5 acres:		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: <u>Area of disturbance is 0.0002 acre.</u>			
3.	Pipes are designed to prevent flotation from uplift, scour or erosion, damage from debris on the waterside (particularly during flood flows), seepage along proposed pipes, corrosion, leakage, and damage from vehicular loads:		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
4.	Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM):		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
5.	Pipes passing over the DWSE will have a minimum of 2 feet of cover (low permeability or CLSM):		Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
6.	If material must be added to the levee crown, the added material must be sloped at a ratio of 10H:1V horizontal to vertical, in the upstream/downstream direction to prevent a “speed bump” effect and facilitate vehicle access:		Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment:			
7.	Fill will be compacted to at least 95% of maximum density as determined by ASTM D698, between -2 and +3% of optimum moisture content:		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.6B.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
8.	Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve:		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 2.2A.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
9.	All fill will be free of organics or other inappropriate materials:		Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.9.B.1.6.</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			



10.	Pipes terminating in the channel have a positive closure device on the waterside that is accessible from the levee crown:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
11.	Pipes transporting product completely across the federal project have a positive closure devices located within 1 mile on both sides of the federal project:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
12.	Pipes located within or beneath a levee have watertight joints that can accommodate movements resulting from settlement:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>Refer to detail 2 on Sheet 40</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
13.	Pipes crossing the surface of the levee are designed to counteract buoyancy forces of an empty pipe, with water at the DWSE:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	
	Reference: <u>Refer to detail 3 on sheet 41</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
14.	Pipe location and orientation will be clearly marked in the field:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>pipe location and orientation can be identified by vault structure and outfall location</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
15.	Pipes will allow easy access for rapid closure:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: <u>Positive valve closures on the levee crest will ensure easy access for rapid closure.</u>			
16.	Plastic pipes within the levee embankment or its foundation are embedded in concrete:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
17.	If a chemical or electrochemical reaction is expected, the pipe and pipe couplings must be protected:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
18.	Any work within the levee embankment or foundation?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
19.	Any work ≤50 feet beneath the channel invert?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
20.	Hydraulic blockage calculation ≥1%?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
21.	Hydraulic model used for hydraulic analysis?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			

– For Official Use Only below this line –

*Comment*

**CP Eligibility Review**

<u>Yes</u>	<u>No</u>	<u>Add'l. Info Requested</u>		
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Environmental Reviewer: _____	Date: <small>Click date</small> _____
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Engineering Reviewer: _____	Date: <small>Click date</small> _____

**American River Flood Control District  
Central Valley Flood Protection Board Permit Application  
Sump 159-2 Modifications (City of Sacramento)  
Staff Report**

**Discussion:**

The City of Sacramento submitted this encroachment permit application to modify facilities at their Sump 159 Pump Station. The work proposed is to remove and replace approximately 40 ft of one (1) 36" welded steel pipe and approximately 30 ft of one (1) 24" welded steel pipe at the pump discharge location and outfall structure.

Sump 159 is located adjacent to the Arcade Creek South Levee and just west of the bike trail bridge crossing.

These modifications are required to upgrade the pipe outfall system at the pump station. Recent work conducted by SAFCA under the North Area Streams Project replaced only the segments of pipe that crossed through the levee. This work will complete the upgrade to the facility by replacing the pipe discharge sections at the pumps and also the pipe outfall sections and flap gates.

These modifications will be routine construction installations and do not present considerable engineering challenges. It is not anticipated that this work will pose significant operations and maintenance impacts to the District.

**Recommendation:**

The General Manager recommends that the Board of Trustees endorse the CVFPB permit application.

**APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD  
ENCROACHMENT PERMIT**

**Application No.** \_\_\_\_\_  
(For Office Use Only)

1. Description of proposed work being specific to include all items that will be covered under the issued permit.  
Sump 159 Modifications: Remove and replace approximately 40 ft of one (1) 36" welded steel pipe and approximately 30 ft of one (1) 24" welded steel pipe at the pump discharge location and outfall structure.

2. Project  
Location: Sacramento County, in Section See Attachment A  
Township: See Attachment A (N) (S), Range: See Attachment A (E) (W), M. D. B. & M.  
Latitude: 38.62504 Longitude: -121.44762  
Stream: Arcade Creek, Levee: Left Bank Designated Floodway: Arcade Creek  
APN: See Attachment A

3. Raymond Kong, PE of 1395 35th Ave  
Name of Applicant / Land Owner Address  
Sacramento CA 95822 (916) 808-1435  
City State Zip Code Telephone Number  
RKong@cityofsacramento.org  
E-mail

4. Ashley Smith, PE of Peterson Brustad Inc.  
Name of Applicant's Representative Company  
Folsom CA 95630 (916) 608-2212 x 123  
City State Zip Code Telephone Number  
asmith@pbieng.com  
E-mail

5. Endorsement of the proposed project from the Local Maintaining Agency (LMA):

We, the Trustees of American River Flood Control District approve this plan, subject to the following conditions:  
Name of LMA

Conditions listed on back of this form  Conditions Attached  No Conditions

\_\_\_\_\_  
Trustee Date Trustee Date  
\_\_\_\_\_  
Trustee Date Trustee Date

### APPLICATION FOR A CENTRAL VALLEY FLOOD PROTECTION BOARD ENCROACHMENT PERMIT

6. Names and addresses of adjacent property owners sharing a common boundary with the land upon which the contents of this application apply. If additional space is required, list names and addresses on back of the application form or an attached sheet.

Name	Address	Zip Code
See Attachment A		

7. Has an environmental determination been made of the proposed work under the California Environmental Quality Act of 1970?  Yes  No  Pending

If yes or pending, give the name and address of the lead agency and State Clearinghouse Number:

City of Sacramento  
1395 35th Avenue  
Sacramento, CA 95822  
SCH No. Pending

8. When is the project scheduled for construction? April 2021

9. Please check exhibits accompanying this application.

- A.  Regional and vicinity maps showing the location of the proposed work.
- B.  Drawings showing plan view(s) of the proposed work to include map scale.
- C.  Drawings showing the cross section dimensions and elevations (vertical datum?) of levees, berms, stream banks, flood plain,
- D.  Drawings showing the profile elevations (vertical datum?) of levees, berms, flood plain, low flow, etc.
- E.  A minimum of four photographs depicting the project site.

\_\_\_\_\_  
Signature of Applicant Date

Include any additional information:

A summary of the Project and a description of the proposed methods are provided in Attachment A. Attachment B includes relevant plan sheets which are an excerpt from a larger plan set. Attachment C includes the categorical permission checklist. The intent of this application is to modify the existing encroachment permit. The existing Permit number for Sump 159 is 3216-1.

**Attachment A – Summary of Proposed Work**

**CITY OF SACRAMENTO PUMP OUTFALLS PROJECT:  
CENTRAL VALLEY FLOOD PROTECTION BOARD ENCROACHMENT PERMIT**

**SUMMARY OF PROPOSED WORK**

September 15, 2020

**INTRODUCTION**

As mandated by the Sacramento Area Flood Control Agency (SAFCA) and the U.S. Army Corps of Engineers (USACE), sump station outfalls that penetrate and cross major levees are inspected on a 5-year cycle. The project entails the complete replacement of the pump discharge for three (3) drainage sump station facilities and partial replacement of the pump discharge pipe for five (5) drainage sump station facilities. The following information pertains to a partial replacement sump (Sump 159) that will need an updated Encroachment Permit from the CVFPB.

**APN Parcels**

Sump	Existing Permit #	APN
159	3216-1	263-0260-010-0000, 263-0010-016-0000

**ADJACENT PARCELS**

All of the parcels adjacent to the Sump to be modified are listed in the table presented below as provided by the Sacramento County Assessor's Office.

APN	Address	Owner	Owner Address	City	Zip
250-0270-009-0000	ALTOS AVE	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
250-0270-012-0000	ALTOS AVE	UNION PACIFIC RAILROAD CO	1400 DOUGLAS ST 1640	OMAHA	68179
251-0291-011-0000	RIO LINDA BLVD	AMERICAN RIVER FLOOD CONTROL DIST	165 COMMERCE CIR UNIT D	SACRAMENTO	95815
251-0291-012-0000	3201 RIO LINDA BLVD	CONIGLIO 2007 REVOCABLE TRUST	3201 RIO LINDA BLVD	SACRAMENTO	95815
251-0291-018-0000	RIO LINDA BLVD	SACTO & SAN JOAQUIN DRAINAGE DIS	3310 EL CAMINO AVE	SACRAMENTO	95821
263-0010-015-0000	FAIRBANKS AVE	SACTO & SAN JOAQUIN DRAINAGE DIS	3310 EL CAMINO AVE	SACRAMENTO	95821

263-0041-019-0000	813 ARCADE BLVD	SHARON LEE NAYLOR	813 ARCADE BLVD	SACRAMENTO	95815
263-0046-001-0000	3148 ALTOS AVE	IVAN PARRA	3148 ALTOS AVE	SACRAMENTO	95815
263-0046-002-0000	808 ARCADE BLVD	RUBEN O LUA	808 ARCADE BLVD	SACRAMENTO	95815
263-0260-020-0000	TRACTION AVE	CITY OF SACRAMENTO	915 I ST FL5	SACRAMENTO	95814
265-0011-001-0000	3141 RIO LINDA BLVD	S M U D	PO BOX 15830	SACRAMENTO	95852
265-0011-002-0000	3139 RIO LINDA BLVD	JAMES RODARAKIS	205 ARCADE BLVD	SACRAMENTO	95815

### **TOWNSHIP AND RANGE INFORMATION**

Note that gaps exist in Townships and Ranges within the project area. Land not covered by T9N R5E has been in private ownership since before California joined the United States and therefore is not part of the Township and Range system, which was a survey of federal lands.

### **SITE PHOTOGRAPHS**

Attached to this Summary of Proposed Work are photographs showing levee and channel areas representative of proposed work sites.





Figure 1: Sump 159 looking North West



Figure 2: Landside slope near Sump 159





Figure 3: Siphon breaker vaults on levee crest near Sump 159



Figure 4: View looking southwest toward the Sump 159 outfall into Arcade Creek

**Attachment B – Plan Sheets**

*(Excerpt from larger plan set for Pump Outfalls Replacement Project – A)*



PN: W14130615

PN: W14130615


65% SUBMITTAL

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.65
DESCRIPTION:	CP/RBR&CAP	



FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE	DRAWING ADJUST
SCALED DIMENSIONS	IF THIS DOES NOT
SCALE AT 1"	

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY:	E. TUTEJA	DESIGNED BY:	B. JENSEN
DATE:	09/15/20	R.C.E. NO.	C90949 DATE: 03/31/22
		CHECKED BY:	A. SMITH
		R.C.E. NO.	C86512 DATE: 03/31/21



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 159**  
**DEMO PLAN**

DWG. NO.	C30
SHEET	33
OF	47



PN: W14130615

PN: W14130615

65% SUBMITTAL

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.65
DESCRIPTION:		
CP/RBR&CAP		


FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE	DRAWING ADJUST
SCALED DIMENSIONS	IF THIS DOES NOT
SCALE AT 1"	

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY:	E. TUTEJA	DESIGNED BY:	B. JENSEN
DATE:	09/15/20	R.C.E. NO.	C90949 DATE: 03/31/22
CHECKED BY:	A. SMITH	R.C.E. NO.	C86512 DATE: 03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 159**  
**SITE PLAN**

DWG. NO.	C31
SHEET	34
OF	47
Page 13	



- NOTES:
- 1 REMOVE AND DISPOSE OF EXISTING 24" WSP AND APPURTENANCES FROM STA -0+36.9 TO STA -0+28.1 AND STA 0+57.1 TO STA 0+60.1 PER DETAIL 2/C38
  - 2 INSTALL 24" WSP FROM STA -0+40.2 TO STA -0+28.1 AND STA 0+57.1 TO STA 0+60.1 PER DETAIL 3/C38
  - 3 CONNECT TO EXISTING STEEL COUPLING
  - 4 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 5 CONNECT TO EXISTING PIPE PER DETAIL 3/C37
  - 6 REMOVE AND SALVAGE STEEL COUPLING
  - 7 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.65
DESCRIPTION:	CP/RBR&CAP	

FIELD BOOK	0000
SCALE:	1"
ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"	
H: H:	
V: V:	

<b>CITY OF SACRAMENTO</b>			
<b>DEPARTMENT OF UTILITIES</b>			
DRAWN BY:	E. TUTEJA	DESIGNED BY:	B. JENSEN
DATE:	09/15/20	R.C.E. NO.:	C90949 DATE: 03/31/22
CHECKED BY:	A. SMITH	R.C.E. NO.:	C86512 DATE: 03/31/21




IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 159**  
**PLAN AND PROFILE 1 - 24" WSP**

65% SUBMITTAL


DWG. NO.	C32
SHEET	35
OF	47

PN: W14130615





- NOTES:**
- 1 REMOVE AND DISPOSE OF EXISTING 24\" WSP AND APPURTENANCES FROM STA -0+42.8 TO STA -0+27.2 AND STA 0+57.1 TO STA 0+59.8 PER DETAIL 2/C38
  - 2 INSTALL 24\" WSP FROM STA -0+42.8 TO STA -0+27.2 AND STA 0+57.1 TO STA 0+59.8 PER DETAIL 3/C38
  - 3 CONNECT TO EXISTING STEEL COUPLING
  - 4 CONNECT TO EXISTING OUTFALL STRUCTURE PER DETAIL 1/C37
  - 5 CONNECT TO EXISTING PIPE PER DETAIL 3/C37
  - 6 REMOVE AND SALVAGE STEEL COUPLING
  - 7 LOCATION OF ALL EXISTING UTILITIES ARE APPROXIMATE IN PLAN AND PROFILE AND ARE BASED ON THE BEST AVAILABLE UTILITY MAPPING PROVIDED BY UTILITY OWNERS, THE CONTRACTOR IS RESPONSIBLE TO POTHOLE ALL EXISTING UTILITIES IN CONFLICT WITH THE PROJECT IN ADVANCE OF CONSTRUCTION TO DETERMINE ACTUAL DEPTH AND LOCATION. DAMAGE TO ANY EXISTING UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR



PN: W14130615

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.	44.65
DESCRIPTION:	CP/RBR&CAP	
FIELD BOOK	0000	
SCALE:	1\"	
H: H:		
V: V:		

**CITY OF SACRAMENTO**  
DEPARTMENT OF UTILITIES

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1\"

DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21




65% SUBMITTAL


IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**SUMP 159**  
**PLAN AND PROFILE 2 - 36\" WSP**

PN: W14130615	DWG. NO. C33
	SHEET 36 OF 47

Page 15




OUTFALL STRUCTURE CONNECTION DETAIL **1**  
NTS



NOTES:  
1. PROVIDE HAND HOLES AS NEEDED TO INSTALL FIELD LINING. WELD HAND HOLE CLOSED WHEN COMPLETE. HAND HOLES NOT REQUIRED AT OUTLETS IF ACCESSIBLE THROUGH FLAP GATE.

NEW OR EXISTING STEEL  
PIPE CONNECTION DETAIL **2**  
NTS



TRENCH SECTION AND SEQUENCING **3**  
NTS

NOTES:


- CONTRACTOR SHALL REPLACE EXISTING PAVEMENT IN KIND. BASED ON LIMITED FIELD INVESTIGATIONS, EXISTING PAVEMENT SECTION ARE ASSUMED 2" AC ON 6" AB
- THE OWNER AND THE CONTRACTOR SHALL JOINTLY DETERMINE THE FINAL WIDTH AND LENGTH OF THE BIKE PATH CROSSING BASED ON FIELD CONDITIONS AND CONSTRUCTION PROCEDURES.
- CONTRACTOR SHALL REMOVE EXISTING BIKE PATH AS NEEDED TO CONSTRUCT PROPOSED PIPE. IMPACTED AREAS SHALL BE REPLACED IN ACCORDANCE WITH CITY OF SACRAMENTO STANDARD DETAIL T-21

CONSTRUCTION SEQUENCE:

- STEP 1: SAWCUT LIMITS 09F TRENCH EXCAVATION TO CLEAN CUT LIMITS. REMOVE EXISTING ASPHALT CONCRETE TO THE MIN EXTENT REQUIRED TO CONSTRUCT PROPOSED PIPE. PROPOSED PIPE SHALL BE CONSTRUCTED A MIN OF 2' FROM FG. TRENCH PLATES SHALL BE PROVIDED TO MAINTAIN ACCESS OVER CUTOFF WALL DURING CONSTRUCTION IN ACCORDANCE WITH THE SPECIFICATIONS.
- STEP 2: PLACE AB TO MATCH EXISTING THICKNESS. PLACE AC OVERLAY FROM EXTENT APPROVED BY AGENCY AND CONTRACTOR TO LIMITS OF SAWCUT. PROVIDE PAVEMENT MARKING AND STRIPING TO MATCH EXISTING.

LEGEND:

EXISTING	PROPOSED
GRIND AND OVERLAY ASPHALT CONCRETE	
AGGREGATE BASE (AB)	
ASPHALT CONCRETE (AC)	



CROWN SURFACING DETAIL **4**  
NTS

PN: W14130615

REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.
DESCRIPTION:	

FIELD BOOK	0000
SCALE:	1" = 1'
ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"	


<b>CITY OF SACRAMENTO</b> DEPARTMENT OF UTILITIES			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
MISCELLANEOUS DETAILS I

65% SUBMITTAL


DWG. NO.	C37
SHEET	40
OF	47




TYPICAL SLOPE BENCHING NOTES:

1. PLACE FILL IN HORIZONTAL LIFTS AGAINST VERTICAL FACES CUT INTO EXISTING LEVEE MATERIAL.
2. THE BOTTOM OF THE KEY TRENCH SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES AND RECOMPACTED TO 95% MAX DENSITY PER ASTM D698.

SLOPE BENCHING (LANDSIDE OR WATERSIDE) DETAIL 1  
NTS



TYPICAL REMOVAL OF EXISTING PIPE DETAIL 2  
NTS



INSTALLATION OF NEW PIPE DETAIL 3  
NTS

PUMP OUTFALLS REPLACEMENT PROJECT  
PN: W14130615

PN: W14130615


REVISIONS			
NO.	DESCRIPTION	DATE	BY

BENCH MARK	ELEV.
DESCRIPTION:	

FIELD BOOK	0000
SCALE:	1" = 1'
H:	
V:	

ON ORIGINAL SCALE DRAWING ADJUST SCALED DIMENSIONS IF THIS DOES NOT SCALE AT 1"

<b>CITY OF SACRAMENTO</b> DEPARTMENT OF UTILITIES			
DRAWN BY: E. TUTEJA	DESIGNED BY: B. JENSEN	CHECKED BY: A. SMITH	
DATE: 09/15/20	R.C.E. NO. C90949 DATE: 03/31/22	R.C.E. NO. C86512 DATE: 03/31/21	



IMPROVEMENT PLANS FOR:  
**PUMP OUTFALLS REPLACEMENT PROJECT - A**  
**MISCELLANEOUS DETAILS II**

65% SUBMITTAL

PN: W14130615	DWG. NO. C38
	SHEET 41 OF 47
	Page 17

PN: W14130615

**Attachment C – Categorical Permission Checklist**

## Categorical Permission Alteration Description – 16. Pressurized Pipes

The categorical permission covers the installation, modification, and replacement of pressurized pipes that comply with certain terms and conditions. Particularly, all pressurized pipes must be designed and installed in accordance with current USACE standards. The total area of disturbance, including staging and access areas, must not exceed 5 acres. Pressurized pipes must also be designed to prevent, (1) flotation from uplift, (2) scour or erosion, (3) damage from debris on the waterside, particularly during flood flows, (4) leakage, (5) seepage along proposed pipes, (6) corrosion, and (7) damage from vehicular loads.

All new pressurized pipes should go up and over the levee DWSE. Pressurized pipes passing over or within the freeboard zone of a levee (i.e., above the levee DWSE), should be made of metal, preferably ductile iron or coated steel, suitable for use with flexible couplings.

Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM). Pipes that pass above the DWSE must have 2 feet of cover (low permeability or CLSM) to prevent damage by vehicles and equipment. Cover material on the levee crown must be placed at a ratio of 10H:1V, in the upstream/downstream direction of the levee. Pipes on the sides of the levee should be covered with a minimum of 1 foot of low permeability material, compacted in 4- to 6-inch lifts or CLSM to protect them from debris during high water (waterside) or to keep them from interfering with or being damaged by operations or maintenance of the levee (landside). Fill must be free of deleterious materials and construction debris and placed in 4- to 6-inch-thick loose lifts and compacted to not less than 95% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D698 (USACE preferred method), or alternately, 90% of the maximum density at moistures between -2 and +3 percent of optimum moisture content obtained from ASTM D1557. At the sponsor and levee maintaining agency's discretion, pipes on the levee slopes may be left exposed.

Only suitable material must be used as levee fill materials. Fill must be free from: roots and other organic matter, contaminated hazardous or toxic material, trash, debris, and frozen materials. Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve.

Pressurized pipes terminating in the channel require a positive closure device on the waterside that is accessible from the levee crown. Pressurized pipes transporting product completely across or through the federal project easement require positive closure devices located landward of any levees and channel. The positive closure device shall be located within one mile on both sides of the federal project. If the invert of the pipe is over the levee crown, the combination of a pump station on the waterside and a siphon breaker is considered an appropriate means of closure. Pipes located within or beneath a levee must have watertight joints that can accommodate movements resulting from settlement.

All pressurized pipes that cross the levee foundation at a depth less than or equal to two times the height of the levee should be evaluated for uplift. Pipes crossing the surface of the levee must be designed to counteract buoyancy forces of an empty pipe, with water at the DWSE.

Pressurized pipelines running parallel to flood risk management projects should be located at least 15 feet beyond the levee toes. Pipe location and orientation must be clearly marked in the field so they can be easily identified for flood fighting crews.

If appropriate, the requester should prepare an excavation plan demonstrating the effects of excavation on the stability of the embankments.

The site layout should provide adequate access for maintenance vehicles to refill fuel tanks and service/replace pumps, generators, etc. Pressurized pipes must also allow easy access for rapid closure in the event of leakage or rupture.

No plastic pipes (HDPE, PVC, etc.) are allowed in the levee embankment or its foundation unless they are embedded in concrete.

If an electrochemical or chemical reaction between the substratum or groundwater and pipe materials is expected, the pipe and pipe couplings must be protected.

After installation of pressurized pipes, the requester must demonstrate 0% pipe leakage in pipes in the levee. Pipes must be pressure tested to industry standards. Pipes must be regularly inspected, including the interior, if possible, looking for signs of maintenance issues. If an inspection indicates corrosion, alignment sag or heave, or separation at joints, corrective action must be taken as soon as possible to avoid failure. Pipe valves must be periodically inspected and pressure tested to ensure that they are functioning properly. Pressure tests must show no significant loss in pressure. Leaks and other deficiencies must be addressed as soon as possible. All replacement parts must be of equivalent or better quality than those being replaced.

The preferred method for abandoning pipes that pass through or over a levee is complete removal. If removal is not feasible, the pipes and other structures may be filled with a cement/bentonite-based grout or flowable fill. The grout needs to be sufficiently fluid so that it can be pumped to completely fill the pipe leaving no voids.

### Categorical Permission Alteration Checklist – 16. Pressurized Pipes

*Note:* The following checklist is intended for planning purposes only, and includes information that USACE reviewers look for when considering a Section 408 request for pressurized pipes under the Categorical Permission. To be reviewed under the Categorical Permission, the proposed project must adhere to all requirements of the Categorical Permission, including the full alteration description (see previous page). The plans and narrative project description should reflect this information.

1.	<input type="checkbox"/> New Construction <input checked="" type="checkbox"/> Replacement <input type="checkbox"/> Modification <input type="checkbox"/> Authorize Existing		
2.	Maximum total area of disturbance is 5 acres:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: <u>Area of disturbance is 0.008 acre.</u>		
3.	Pipes are designed to prevent flotation from uplift, scour or erosion, damage from debris on the waterside (particularly during flood flows), seepage along proposed pipes, corrosion, leakage, and damage from vehicular loads:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
4.	Backfill under and around (to 1 foot over) the proposed pipe must be controlled low-strength material (CLSM):	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to detail 3 on sheet 41</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
5.	Pipes passing over the DWSE will have a minimum of 2 feet of cover (low permeability or CLSM):	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
6.	If material must be added to the levee crown, the added material must be sloped at a ratio of 10H:1V horizontal to vertical, in the upstream/downstream direction to prevent a “speed bump” effect and facilitate vehicle access:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]		
	Comment:		
7.	Fill will be compacted to at least 95% of maximum density as determined by ASTM D698, between -2 and +3% of optimum moisture content:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.6B.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
8.	Satisfactory fill material must have a plasticity index between 8 and 25, have a liquid limit less than 45, a minimum fines content of 20%, and 100% passing the 3-inch sieve:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 2.2A.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		
9.	All fill will be free of organics or other inappropriate materials:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>
	Reference: <u>Refer to Spec section 31 00 00 3.9.B.1.6.</u>		
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]		

10.	Pipes terminating in the channel have a positive closure device on the waterside that is accessible from the levee crown:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
11.	Pipes transporting product completely across the federal project have a positive closure devices located within 1 mile on both sides of the federal project:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
12.	Pipes located within or beneath a levee have watertight joints that can accommodate movements resulting from settlement:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>Refer to detail 2 on Sheet 40</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
13.	Pipes crossing the surface of the levee are designed to counteract buoyancy forces of an empty pipe, with water at the DWSE:	Yes <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	
	Reference: <u>Refer to detail 3 on sheet 41</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
14.	Pipe location and orientation will be clearly marked in the field:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: <u>pipe location and orientation can be identified by vault structure and outfall location</u>			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
15.	Pipes will allow easy access for rapid closure:	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: <u>Positive valve closures on the levee crest will ensure easy access for rapid closure.</u>			
16.	Plastic pipes within the levee embankment or its foundation are embedded in concrete:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
17.	If a chemical or electrochemical reaction is expected, the pipe and pipe couplings must be protected:	Yes <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
18.	Any work within the levee embankment or foundation?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
19.	Any work ≤50 feet beneath the channel invert?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
20.	Hydraulic blockage calculation ≥1%?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			
21.	Hydraulic model used for hydraulic analysis?	Yes <input type="checkbox"/>	No <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>
	Reference: [ Click to enter document source. Example – plan sheet (p. 4), specs, report. ]			
	Comment: [ Click to enter rationale, explanation, unique situation, etc. ]			



– For Official Use Only below this line –

*Comment*

**CP Eligibility Review**

<u>Yes</u>	<u>No</u>	<u>Add'l. Info Requested</u>		
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Environmental Reviewer: _____	Date: <small>Click date</small> _____
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Engineering Reviewer: _____	Date: <small>Click date</small> _____

## General Manager's Meeting Summary

### September 2020

**9/11: American River Flood Control District Board of Trustees meeting.** The Board met in regular session. The agenda items included correspondence from the City of Sacramento Police Department regarding extensive camping along the roadways of the Johnston Business Park, a discussion on the District's carbon footprint, and addressing permitted encroachments in River Park.

**9/14: DWR Deferred Maintenance Project meeting.** I met via web conference with staff from DWR to learn about the extension of the Deferred Maintenance Project grant program. The District has funding available to inspect or repair levee pipes in 2021.

**9/15: Sacramento County Local Hazard Mitigation Plan Kick-off meeting.** I attended this meeting via teleconference with representatives from the County of Sacramento and numerous Special Districts to discuss the 2021 update to the Local Hazard Mitigation Plan.

**9/16: Central Valley Flood Control Association Board of Directors meeting.** This meeting was held via web teleconference. Topics of discussion included the State's regional meetings on the Sacramento San Joaquin Drainage District assessment, extension of the Flood Maintenance Assistance Program, and a legislative update on bills for 2020.

**9/16: Field Visit for Kelton Way Pedestrian Access.** Superintendent Kawamura and I met with residents that use the levee along Robla Creek for exercise and recreation. They requested the meeting to ask if the District could install a recreation trail along the levee similar to the American River Parkway.

**9/16: ARFCD Quarterly Safety meeting.** The Safety Committee met to discuss safety items for the District. Items of discussion included the OSH Act of 1970, clearance zones around electrical equipment in the warehouse, Firecode training, and the Cintas training program.

**9/21: Phone Meeting with Dude Solutions.** I met with staff from Dude Solutions to discuss implementation of the workflow tracking software, Asset Essentials. Sara Poffenbarger from Dude is our implementation consultant and she is able to walk clients through the steps to set-up the software specific to our District.

**9/23: ARFCD Roof Repair/Replacement Pre-Construction Meeting.**

I met with Don Mariano from Lionakis and Dennis Philips from Rua and Son to discuss progress on the roof project. Two-thirds of the old roof has been removed and the crews are constructing framing for the new HVAC unit. Two sections of dry-rot were removed and repaired along the west wall.

**9/28: Steelhead Creek Clean-up Meeting.**

Superintendent Kawamura and I met with the Central Valley Regional Water Quality Control Board to discuss the annual clean-up effort in Steelhead Creek. This year, the City will distribute trash bags prior to the clean-up and RD 1000 and ARFCD will use equipment to load and haul-off the filled bags.

## Request for Porta-potties at District's Lathrop Way Parcel

District staff received a request from a neighboring business owner for the District to consider placing porta-potties on our Lathrop Way parcel. The narrow parcel lies between the levee and the roadside curb on Lathrop way and extends for roughly 2,000-feet.

The Board reviewed a letter from Sacramento PD at their September meeting regarding the extensive parking of RVs along this part of the Johnston Business Park.

Louis Warfield, from Rhino Designs, requested that the District consider placing porta-potties on this parcel to assist the camping population and to reduce the amount of bathroom breaks the campers are making next to adjacent businesses. Mr. Warfield indicated that Rocket Restrooms can provide two porta-potties at a cost of \$450/month. Mr. Warfield also indicated he is considering providing a dumpster adjacent to his business for the campers to use.

Staff is looking into costs for United Rentals to provide porta-potties and is thinking through complications from removing trash and debris deposited into the porta-potty. It is also possible that the Central Valley Flood Protection Board would require an encroachment permit to place the porta-potties adjacent to the levee.




District parcel along Lathrop Way (apn 275-0300-009)





Fires 2020







## American River Flood Control District

## Homeless Camp Cost

January 1, 2020 – June 30, 2020

Cost Code Summary	
Bell Marine Co.	\$844.15
HercRentals	\$1,657.74
Home Depot	\$181.42
L and D Landfill	\$3,479.72
Mahaney Co., John F.	\$903.99
Sacramento County MSA	\$900.30
Sacramento County Sheriff, Work Release	\$13,706.00
Sierra Waste Recycling & Transfer Station	\$121.60
Teichert & Son, Inc	\$1,916.78
United Site Services	\$259.50
US Bank	\$1,451.28
Wilson Bohannon Padlock Co.	\$860.77
<b>Total</b>	<b>\$26,283.25</b>

Unit	Hours	Costs \$56/Hour
1	206	\$11,536
2	81	\$4,536
3	16	\$896
4	144	\$8,064
5	256	\$14,336
6	16	\$896
7	109	\$6,104
<b>Total</b>	<b>828</b>	<b>\$46,368</b>