

## **American River Flood Control District**

### **Request Bids for Purchase and Delivery of Rock Rip Rap Staff Report**

#### **Discussion:**

The District's upcoming Arcade Creek Erosion Repair Project requires the placement of 3,000 tons of rock rip rap along the damaged sections of the bank in Arcade Creek. The project plan is to purchase the rip rap in advance of construction and store it at the District's storage facility at Lathrop Way.

Typically, rock is made per the desired specification at one of the local quarries in either the lone or Marysville area. Construction companies or Trucking companies are likely to bid on the project to provide this rock directly to the District and bring it to the storage facility. The delivered rock rip rap will have certifications indicating that it meets the desired specification. These certifications are part of the permit requirements from the Central Valley Flood Protection Board.

#### **Recommendation:**

The General Manager recommends that the Board of Trustees direct staff to advertise an invitation for bids to supply 3,000 tons of rock rip rap per the attached specification.

**American River Flood Control District**  
**Bid Packet**

*185 Commerce Circle*  
*Sacramento CA, 95815*

**The American River Flood Control District invites bids for the purchase of three thousand tons, minus 15 inch rip-rap, delivered by vendor, to ARFCD Sacramento storage facility at Lathrop Way.**

**IFB NUMBER 10-001**

**Bids must be submitted and received by June 9<sup>th</sup>, 2022, 3:30P.M. They will be publicly opened and read in the American River Flood Control District Board Meeting June 10<sup>th</sup>, 2022 at 185 Commerce Circle, Sacramento CA, 95815.**

Mail to: American River Flood Control District

185 Commerce Circle  
Sacramento, CA 95815

Attn: Tim Kerr  
General Manager

**ARFCD****IFB Number 22-001****Request for Bid and Specifications****Three Thousand Tons Minus 15 Inch Rip Rap. Delivered by vendor to ARFCD Sacramento storage facility at Lathrop Way****1. Specifications**

Minus 15-inch Quarry Rock

Minus 15-inch quarry rock material shall consist of a well graded and angular 15-inch minus quarry rock. Minus 15-inch quarry rock shall be free from weak cleavages, undesirable weathering, and other defects that would tend to increase unduly its deterioration from handling or natural causes. The inclusion of objectionable quantities of dirt, sand, clay, and rock fines will not be permitted. .

Size	Percent Passing
15 inch	100
8 inch	80-95
6 inch	45-80
4 inch	15-45
2 inch	0-15

**2. Delivery and Inspection:**

Deliver shall be completed within 60 days of the award of contract. Receiving and inspection will be made by the American River Flood Control District Superintendent. 185 Commerce Cr, Sacramento, CA 95815.

# ARFCD IFB 22-001 Bid Sheet

Item 12

Three Thousand Tons Minus 15 inch Rip-Rap  
Haulage to Lathrop Way  
Tax Rate  
Total Tax  
Fees


Total Delivered Bid Price

--

## **Copy to Be Posted in Advertisement**

### **Notice of Request for Bids**

The American River Flood Control District (District) is accepting bids for the purchase of three thousand tons of minus 15 inch rip rap delivered to Sacramento storage facility Lathrop Way. All bids must be submitted at the District office, 185 Commerce Circle, Sacramento CA 95815 by June 9<sup>th</sup>, 2022. For a detailed list of rip rap specifications and bid sheet, please contact the District office at 916-929-4006 or at the District website, [www.arfed.org](http://www.arfed.org). The Board of Trustees will review the bids and may reject any and all bids and re-advertise at their discretion.